


ELEVENTH FLOOR PLAN






ELEVENTH FLOOR PLAN

| Polygon | Area |
|---|---|
| A-Block | 1225.40 |
| B1 | 61.14 |
| B2 | 61.14 |
| B3 | 30.41 |
| B4 | 30.41 |
| B5 | 360.84 |
| L1 | 2.96 |
| L2 | 2.96 |
| L3 | 2.96 |
| L4 | 2.96 |
| LW1 | 1.66 |
| LW2 | 1.66 |
| VS1 | 5.36 |
| VS2 | 0.96 |
| V1 | 5.17 |
| V2 | 1.22 |
| V3 | 7.46 |
| V4 | 5.62 |
| V5 | 5.17 |
| V6 | 1.22 |
| V7 | 7.46 |
| V8 | 5.62 |
| P1 | 62.46 |
| P2 | 62.46 |
| S1 | 23.14 |
| S2 | 23.14 |
| S3 | 10.06 |
| S4 | 10.06 |
| Total | 1925.04 |

OFFICE OF THE CORPORATION OF THE CITY NAGPUR.
Building Permit No. 2411/NAGPUR/NMRD/
Dated 7.12.15 Collection No. 1/2015
SANCTIONED
subject to conditions mentioned in the building permit
Assistant Director
Town Planning
Nagpur Municipal Corporation

The Zero Waste Component is proposed to be provided in the form of Govt. of Maharashtra Vide No. UPD-4515/CR-206/UD-11, dated 16th March, 2016 as per schedule for every 500 sq.mts. built up area. The system may be by open well, percolation tank, deep with filtration chamber for every 500 sq.mtr. built-up area. Other options mentioned in the rules, may be adopted.
a) The authority may impose a levy of Rs. 10,000/- per annum for every 500 sq.mts. of built-up area, for failure of the owner of the building.

provision for Solar Water Heating System:
Solar Water Heating System should be installed in the building as it will serve purpose as per capacity mentioned as under
Type of Building — For Capital Cost (Investment) of Rs.
1) Hospitals — 100 Litres/day/person,
2) Hotels — 150 Litres/day/person
3) Hostels & other such buildings — 25 Ltrs./day/person.
4) Resident — 25 Ltrs./day/person.
If the provisions as above is not made, the occupancy certificate will not be issued from NMC

SPECIFIC APPROVES OF THE BUILDING PLAN HAVE TO BE SUBMITTED WITH STRUCTURAL DESIGN & DRAWING DULY CHECKED FROM VNIT FOR NMC RECORD, BEFORE ONE MONTH OF COMMENCEMENT OF CONSTRUCTION OR WITHIN THREE MONTHS FROM THE SANCTION OF BUILDING PLAN WHICHEVER IS EARLIER.

STAMP OF APPROVAL

PLOTING :
BILLDOSS TO
RAMDHIA HARJAYA PAU
SIGN

LANDUSE: AS PER SANCTION DEVELOPMENT PLAN : Residential
LOCATION OF PLOT : Non-Congested
ZONE AS PER APPENDIX-XII : R2
PROP BLDG USE SUBMITTED AS PER PLAN : Resi_Commercial

SPECIFICATIONS
REVISED RESIDENTIAL & COMMERCIAL BUILDING OF Smt GAGAN PAU, & OTHER AT MOUZA WAZHAPARKHAD CST No. 50 SHEET NO. 11 HOUSE No.828 & 835A, NEAR KADSI SQUARE ,NAGPUR

| A) AREA STATEMENT | | SQ.M. |
|---|---|---|
| 1. AREA OF PLOT | | 3650.85 |
| 2. DEDUCTIONS FOR : | | |
| (a) ROAD SETBACK (DP) | | 0.00 |
| (b) PROPOSED ROAD (DP) | | 0.00 |
| (c) RESERVE AREA | | 0.00 |
| (d) ENCROACHMENT AREA | | 0.00 |
| (e) NDZ AREA | | 000.00 |
| TOTAL (a+b+c+d+e) | | 0.00 |
| 3. BALANCE AREA OF PLOT (1-2) | | 3650.85 |
| 4. DEDUCTIONS FOR : | | |
| (a) AMENITY SPACE OF DEDUCTABLE | | 0.00 |
| (b) RECREATIONAL GROUND OF DEDUCTABLE | | 0.00 |
| (PHYSICAL TO BE PROVIDED 000.00) | | |
| 5. NET BALANCE PLOT AREA OF PLOT (3-4) | | 3650.85 |
| 6. ADDITION FOR NET PLOT : | | |
| (a) ROAD 1 SETBACK 000.00 | | 000.00 |
| (b) ROAD 2 SET BACK 000.00 | | 000.00 |
| (c) ROAD 3 SET BACK 000.00 | | 000.00 |
| (d) ROAD 4 SET BACK 000.00 | | 000.00 |
| (e) PROPOSED ROAD (DP) | | 0.00 |
| (f) AMENITY SPACE | | 0.00 |
| (g) NDZ AREA | | 000.00 |
| (h) OTHER (ONZ AREA ETC.) | | 0.00 |
| TOTAL (a+b+c+d+e+f+g+h) | | 0.00 |
| 7. NET PLOT AREA (5+6) : | | 3650.85 |
| 8. PERMISSIBLE FSI | | 1.2500 |
| TERRI BUILT UP AREA (7*8) | | 4563.57 |
| 9. TDR AREA ( DRC No. for Reservation ) | | 1969.04 |
| ORIGINAL TDR AREA | | 1969.04 |
| BALANCE TDR AREA | | 0.00 |
| 10. SPECIAL CASES FSI | | 0.00 |
| 11. TOTAL PERMI BUILT UP AREA (9+10) | | 6532.61 |
| 12. PROPOSED AREAS | | |
| (a) PROPOSED RESIDENTIAL AREA | | 6275.36 |
| (b) PROPOSED COMMERCIAL AREA | | 1121.68 |
| (c) PROPOSED INDUSTRIAL AREA | | 0.00 |
| (d) PROPOSED SPECIAL USE AREA | | 0.00 |
| TOTAL PROPOSED AREA (a+b+c+d) | | 7396.98 |
| 13. SUB STRUCTURE AREA ADDITION (FOR FSI) | | 0.00 |
| 14. SUB STRUCTURE AREA DEDUCTION (FOR FSI) | | 0.00 |
| 15. EXCESS BALCONY AREA TAKEN IN FSI | | 0.00 |
| 16. EXISTING BUILT UP AREA | | 0.00 |
| 17. SURRENDERED AREA | | 000.00 |
| 18. TOTAL BUILT UP AREA PROPOSED | | 7361.76 |
| 19. CONSUMED FSI | | 2.06 |
| B) BALCONY STATEMENT | | |
| (a) PERMISSIBLE BALCONY AREA | | 1103.54 |
| (b) PROPOSED BALCONY AREA | | 738.08 |
| (c) EXCESS BALCONY AREA | | 0.00 |
| C) TENEMENT STATEMENT | | |
| (a) TENEMENTS AREA (12) | | 7396.98 |
| (b) LESS NON RESIDENTIAL AREA | | 1121.68 |
| (c) AREA AVAILABLE FOR TENEMENTS (b - a) | | 6275.36 |
| (d) TENEMENTS PERMISSIBLE 250.00 Mtrsq. | | 37 |
| (e) TENEMENTS PROPOSED | | 40 |
| (f) TENEMENTS EXCESS NO. | | 0 |
| (g) TOTAL TENEMENTS ON THE PLOT (e+f) | | 40 |

PROJECT :
Survey No. : 50 CTS No.
NAGPUR
LEGEND
PLOT BOUNDARY SHOWN THICK BLACK
PROPOSED WORK SHOWN RED FILLED IN
DRAINAGE LINE SHOWN RED DOTTED
ADDITION/ EXTENSION DOTTED
EXISTING TO BE RETAINED HATCHED
DEMOLISHION SHOWN HATCHED YELLOW

CERTIFICATE OF AREA
CERTIFIED THAT I HAVE SURVEYED THE PLOT UNDER REFERENCE ON ____ AND THAT THE DIMENSIONS OF THE BOUNDING OF THE PLOT STATED ON THE PLAN ARE AS MEASURED ON THE SITE AND THE AREA SO ENTERED ON IS ____ SQ.M ARE METRES AND THAT IS WITH THE AREA STATED IN THE DOCUMENT OF OWNERSHIP/TOWN PLANNING SCHEME RECORDS.

ARCHITECT: ARC REGTN 3938
VIRENDRA ISHWARI PRASAD KHARE

| JOB NO. | DRG NO. | SCALE | DRAWN BY | CHECKED BY |
|---|---|---|---|---|
| | | 1:100 | | |
| INWARD NO | CITIZENGRIEVANCE/2015 | | 30-10-2015 | |
| KEY NO. | [illegible] | SHEET NO | 20of1 | |

Disclaimer: AutoDCR is an input based software tool used by Municipal Corporations but the final approval lies with concerned Officer / Authority.