




FRONT ELEVATION
SCALE 1:100



SECTION AT A-A
SCALE 1:100



SEPTIC TANK DETAIL



COMPOUND WALL DETAIL



DETAIL OF FILTER BED FOR RAIN WATER HARVESTING.





GROUND FLOOR
SCALE 1:100



TYPICAL FIRST AND SECOND FLOOR
SCALE 1:100



THIRD FLOOR
SCALE 1:100



12 MT WIDE ROAD

SITE PLAN
SCALE 1:200

N

PROPOSED RESIDENCE ON PLOT
NO.65 SURVEY NO.83
MOUZA:-KOSARA
TAHSIL AND DIST :-CHANDRAPUR
BELONGING TO :-
Synergy Plotters and Structures
Shri. Girish Shridhar rav Padmawar
Smt. Meena Avinash Uttarwar
Shri. Nitin Vijay Mamidwar
Shri.Nilesh Gajanan Chandewar
Shri. Kapil Sudhakar Vatragade

Plot Area Calculation

PLOT AREA	705.000 SQ.MT.
FSI	1.00
Permissible Built up Area	705.000 SQ.MT.
Proposed Area Calculation	

TOTAL FLOOR AREA

FLOOR	BUILT UP
GROUND FLOOR	18.220
FIRST FLOOR	289.019
SECOND FLOOR	289.019
THIRD FLOOR	103.362
TOTAL	697.620

TOTAL BALCONY AREA

FLOOR	PERMISSIBLE BALCONY	OPEN BALCONY	TOTAL
FIRST FLOOR	28.001	24.040	24.040
SECOND FLOOR	28.001	24.040	24.040
THIRD FLOOR	10.336	8.155	8.155
TOTAL			56.235

PARKING CALCULATION

BLOCK CALCULATION	CAR	SCOOTER	CYCLE
4 TENAMENTS HAVING BUILT UP AREA TO 40,00 SQ.MT.			
NO. OF TENAMENTS=TOTAL			
TOTAL PARKING REQUIRED	4	16	16
TOTAL PARKING PROVIDE	3	20	16
CAR	342.00 X 3.0 = 10.260SQ.MT.		
SCOOTER	342=20 X 3.0 = 70.000SQ.MT.		
CYCLE	1900.75 X 3.0 = 20.250SQ.MT.		

INDEX

ALL DIMENSIONS ARE IN METERS
PLOT BOUNDRY SHOWN IN BLACK COLOUR
PROPOSED BUP AREA SHOWN RED COLOUR

SCALE : 1:100, 1:200 , 1:500 DRG.NO

DATE DRAWN BY:-VIVEK SP

SCHEDULE FOR OPENING

TYPE	SIZE	PARTICULAR
D	1.00 X 1.20	T.W. DOOR
D1	0.90 X 2.10	T.W. DOOR
D2	0.75 X 2.10	T.W. DOOR
W	1.50 X 1.20	T.W. WINDOW
W1	1.20 X 1.20	T.W. WINDOW
W2	0.90 X 0.90	T.W. WINDOW
V	0.60 X 0.45	VENTILATOR

OWNERS SIGNATURE

ARCHITECTS SIGNATURE SIGNATURE