






या बांधकाम अत्यावश्यक बांधकाम आहे
कोल्हापूर जिल्हास्तर (Plinth Level) व
बांधकाम पूर्ण झाल्यावर बांधकाम /
व्यवसायिक अभियंता/ सुपरवायझर, यांचे
मार्फत अत्यावश्यक पूर्णत्वाचे प्रमाणपत्र हा
कार्यालयामधून प्राप्त करून घेऊन नंतरच
पूढीत बांधकाम सुरू करावे अन्यथा आपण
त्या बांधकामावर अत्यावश्यक समजून

PARKING AREA STATEMENT FOR AB BUILDING						
CARPET AREA	NO OF ROW HOUSE	REQUIRED LOTS		PROVIDED LOTS		Remark
		4 WHEELER	2 WHEELER	4 WHEELER	2 WHEELER	
RESIDENTIAL AREA						
<=101	0	0	0	0	0	
>101 - 150	24	24	48	24	48	
>150	0	0	0	0	0	
TOTAL	24	24	48	24	48	

SCHEDULE OF OPENING:			
NAME	LENGTH	HEIGHT	NOS.
d1	1.00	2.10	1
d1	1.03	2.10	1
d2	0.75	2.10	3

SCHEDULE OF OPENING:			
NAME	LENGTH	HEIGHT	NOS.
v	0.60	0.60	2
w2	1.70	1.20	1
w2	1.72	1.20	1
w	1.85	1.20	2



Polygon	LENGTH	WIDTH	Area
A-Block	3.90	0.90	3.53
Total ->	->	->	3.53

Polygon	LENGTH	WIDTH	Area
A-Block	7.40	5.10	37.74
D-01	->	->	1.49
Total ->	->	->	36.25

FIRST / SECOND FLOOR PLAN

BUILDING	FLOORS	FSI AREA					BALCONY			STAIR	LIFT	PASSAGE	LIFT M/C ROOM	TENE.	TOTAL FSI AREA
		COMM.	RESI.	IND.	SPECIAL	DOUBLE HT	PERM.	PROP.	EXCESS	PAID	PAID	PAID			
I (RH)	STILT FLOOR	0.00	3.53	0.00	0.00	0.00	0.53	0.00	-	0.00	0.00	0.00	-	0	3.53
I (RH)	FIRST FLOOR	0.00	36.25	0.00	0.00	0.00	5.44	5.35	-	0.00	0.00	0.00	-	1	36.25
I (RH)	SECOND FLOOR	0.00	36.25	0.00	0.00	0.00	5.44	5.35	-	0.00	0.00	0.00	-	0	36.25
I (RH)	Total	0.00	76.03	0.00	0.00	0.00	11.40	10.69	0.00	0.00	0.00	0.00	0.00	1	76.03

अर्जदार यांची प्रत

Approved as recommended

OFFICE USE

Subject to the conditions mentioned in

this office Building permit No. 705/2011/12

09/11/2011

DY. TOWN PLANNING

Municipal Corporation

AURANGABAD.

BUILT UP AREA		
BUILDING D1		
BUILT UP AREA ON PARKING FLOOR	= 03.53	
BUILT UP AREA ON FIRST FLOOR	= 36.25	SQ.M.
BUILT UP AREA ON SECOND FLOOR	= 36.25	SQ.M.
TOTAL	= 76.03	SQ.M.

NO. OF TENEMENTS = 24 X1 = 24 TENEMENTS

TOTAL AREA = 24 X 76.03 = 1824.72 SQ.M.

- NOTES.
- DO NOT SCALE THE DRAWING.
 - INTERNAL B.M. SHALL BE 100 MM THK AND EXTERNAL SAHL BE 150 MM THK
 - INTERNAL PLASTER SHALL BE NEERU FINISH AND EXTERNAL SAHL BE SAND FACED FINISH.
 - INTERNAL COLOUR SHALL BE OBD AND EXTERNAL SAHL BE CEMENT PAINT.
 - STAIRS TREAD SHALL BE NON-SLIPPERY.
 - ALL THE HT DIMENSIONS SHALL BE MEASURED FROM FFL.

SCHEDULE OF OPENINGS :	
DOORS	WINDOWS
D 1.0 X 2.10	W-2 1.50 X 0.90
D-1 0.90 X 2.10	W-3 1.20 X 0.90
D-2 0.75 X 2.10	W-4 0.90 X 1.50
D/W 1.50 X 2.10	V-1 0.60 X 1.50
W-1 1.50 X 1.20	V2 0.60 X 0.75
W-1 1.50 X 1.20	

LEGEND :	
PLOT BOUNDARY SHOWN AS (BLACK)	
PROPOSED LINE SHOWN AS (RED)	
DRAINAGE LINE SHOWN AS (YELLOW)	
WATER LINE SHOWN AS (GREEN)	

PROPOSED RESIDENTIAL BUILDING ON G.NO-210 HARSUL, AURANGABAD.

FOR

M/S RAJ REAL ESTATE THROUGH Partners

1.SANJAY K. BHALEKAR

2.RAJESH B. GUNJAL

SUBMISSION DRAWING

	JOB NO. :- G-1103	ROW TYPE
	DATE :- 9-APRIL-2011	
	SCALE :- 1:100, 1:200	
	DEALT BY :-	
CHECKED BY :- SNA		

SAMIL ARCHITECTS

ARCHITECTS, INTERIOR DESIGNERS, AND PROJECT CONSULTANTS

C- NISHIGANDHA, DISHA BRUSHI, RANA NAGAR, OPP. ATITHI HOTEL, JALNA ROAD AURANGABAD PH- 240 2451616 email - samil@sm.in

OWNER'S SIGN.

Architects

SAMEER N. AUSEKAR

REGD. NO. CA - 95 19301

MILIND M. WADEKAR

REGD. NO. 152 / 92