अंजदार यांची प्रत

----- -15.00 M. WIDE D. P. ROAD -----

BASEMENT FLOOR PLAN



----- -15.00 M. WIDE D. P. ROAD -----

GROUND FLOOR PLAN



TYPICAL FIRST & SECOND FLOOR PLAN

Approved as ammended
in.....Colour
Subject to the conditions mentioned in
this office Building permit No.....
Date.....

By Order
Town Planning
Municipal Corporation
AURANGABAD.

O/C Signed by A.D.T.P.

ONLY OFFICE USE

A	FSI STATEMENTS	
1.	Area of plot (Minimum as per D.C. regulation)	
	a) As per demarcation document (7/12, CTS extract)	1109.00
	b) As per measurement sheet / Layout	1109.00
	c) As per site	1109.00
	d) Gross Plot Area	1109.00
2.	Deductions for	
	a) Proposed DP / D.P. Road widening Area	0.00
	b) Area of D.P. Reservations (park)	0.00
	c) Nallah / Water course area	0.00
	d) Total deduction	0.00
3.	Gross Area of Plot (1-2)	1109.00
4.	Permissible F.S.I. Gross zone	
	a) Residential	0.00
	b) Commercial	0.00
5.	Amenity Space -	
	a) Residential -	0.00
	b) Commercial -	0.00
6.	Service road cum Highway widening	0.00
7.	Internal Road area	0.00
8.	Net Area of Plot (3 – 5[a])	1109.00
	(Max Permissible F.S.I. as per 4 a/b)	
9.	Built up area admissible on Basic F.S.I. as per local road width (viz. no. 8.7 x 4.5)	1296.90
10.	Addition of area for F.S.I.	
	a) Area to be considered D.P. road, if any	0.00
	b) Mutation premium Amenity Space	0.00
	c) Premium FSI as permitted to employers of 5 acre, sec. 8.1	332.70
	d) TDR area	0.00
	e) Additional FSI on payment of premium	0.00
	(Area of sub-contents)	332.70
11.	Total area admissible (9+10)	1552.60
12.	Maximum utilization of F.S.I. Permissible as per Road width (i.e. per Regulations, 15.4.1)	1,552
13.	Total Built-up Area (in occupancy, deduction area as per Sr.No. 15.8)	
	a) Existing Built-up Area	0.00
	b) Proposed Built-up Area	1550.38
	c) Excess Balcony area, covered in F.S.I.	0.00
	d) Excess Double Height staircase area covered in F.S.I.	0.00
	Total built-up area	1550.38
14.	F.S.I. Consumed (13[b] should not be more than Sr.no. 12 above)	1,398
15.	Loading Unloading Space, if any	
	a) Required (Check as per D)	0.00
	b) Provided	0.00

AREA STATEMENT

1.	**AREA OF PLOT AS PER LAYOUT**	=	1109.00 SQ.M.
2.	PERMISSIBLE F.S.I. (1.10)	=	1219.90 SQ.M.
3.	ADD PREMIUM AREA (0.30)	=	332.70 SQ.M.
4.	TOTAL PERMISSIBLE B/UP AREA (2+3)	=	1552.60 **SQ.M.**
	BUILT UP AREA		
1.	GROUND FLOOR B/UP AREA	=	422.78 SQ.M.
2.	FIRST FLOOR B/UP AREA	=	471.17 SQ.M.
3.	SECOND FLOOR B/UP AREA	=	471.17 SQ.M.
4.	THIRD FLOOR B/UP AREA	=	185.26 SQ.M.
5.	TOTAL BUILT UP AREA	=	1550.38 SQ.M.
6.	F. S. I. CONSUMED (1550.38/1109.00)	=	1.398

NOTE: EXTERNAL WALL 0.15 M. AND INTERNAL WALL 0.10 M.
ALL BOX = 0.60 M.WIDE
BALCONY OUTER TO OUTER DISTANCE

SCHEDULE OF OPENING

DOORS		WINDOWS	
D	1.0 X 2.10	W-2	1.10 X 1.20
D-1	0.90 X 2.10	W-3	1.20 X 0.90
D-2	0.75 X 2.10	W-4	0.90 X 1.50
D/W	1.50 X 2.10	V	0.60 X 0.75
W	1.50 X 1.20	W-1	1.20 X 1.20

LEGEND

PLOT BOUNDRY SHOWN AS

PROPOSED LINE SHOWN AS

PROPOSED PLAN OF RESIDENTIAL BUILDING
SITUATED AT. PLOT NO. 02, GUT NO.107 (PART) AT
MITMITA , AURANGABAD
FOR
M/S. Kamalleela Developers
Through Its Partner
Shri. Sushil Kamalnayan Bharuka

DEALT BY- GANESH	JOB NO - AR-1601
CHECKD BY- MMW	
DATE: 15 / 10 / 2018	SCALE 1:100 ,1:200

SAMIL ARCHITECTS
NISHIGANDH 'C', DISHA SRUSHTI, RANA NAGAR, JALNA ROAD,
OPP. HOTEL ATITHI AURANGABAD.
PIN-431005 PH-0240 2451616
EMAIL- samil@live.in
SAMEER- 9823008899 MILIND - 9326209499

NORTH

TITLE

SUBMISSION DRAWING

OWNER'S SIGNATURE

Kamalleela Developers
1) Partner

ARCHITECTS:-

SAMEER N. AUSEKAR
REGD. NO. CA / 95 / 9301

MILIND M. WADEKAR
REGD. NO. / 16262