




Assistant Town Planner Date: 12/02/2025
Recommended for rejection, proposal number 224471 by
Head Draftsman Assistant Director Town Planning on 13/02/2025
Date: 11/01/2024
Town Planner Date: 28/10/2024



PROPOSED BUILT UP AREA							
SR. NO.	TYPE	G.F. B/UP AREA	F.F. B/UP AREA	TOTAL B/UP AREA UNIT	TOTAL C/UP AREA UNIT	NO. OF UNIT	TOTAL B/UP AREA OF UNITS
01	P	32.42	27.09	59.51	49.81	05	297.55
02	Q	31.83	26.67	58.50	49.81	43	2515.50
03	R	32.10	26.92	59.02	49.81	17	1003.34
04	S	32.17	0.00	32.17	27.59	04	128.68
05	T	31.49	0.00	31.49	27.59	43	1354.07
TOTAL						112	5299.14

NOTE :-
CARPET AREA < 30 > 0 = 47 UNITS = $\frac{47}{112} = 0.4196$
CARPET AREA < 50 > 30 = 65 UNITS = $\frac{65}{112} = 0.5803$



Project Details	
Proposal code -RPAUR-23-96549	Zone Type - Agricultural Zone
Location - Non-Congested	Name of service - Building Development
Sub service -	Cts No./Survey No. - 708/P
Tahsil : VAJJAPUR	Mouza : shioor B
Prorate Value : 1.000	

JOB TITLE
PROPOSED RES. GROUP HOUSING FOR EWS / LIG PLAN UNDER RULE NO.7.2.2 & 7.7.1 OF UDCPR ON GUT NO.708 (pt.), AT. SHIOOR, TQ.VAJJAPUR, DIST.CHH. SAMBHAINAGAR.

Performance / Area Statement	
1. Area of plot (Minimum area of a, b, c to be considered) or area of subplot with sanctioned layout No. and subplot No.	16813.731
(a) As per ownership document (7/12, CTS extract)	17600.000
(b) as per TILN or City Survey measurement sheet	17000.000
(c) as per Demarcation drawing area	16813.731
2. Less	
3. Total area (1-2)	0.000
4. Deductions for	
(a) Proposed D.P / P.F. Road widening Area /Service Road / Highway widening	1604.618
(b) Any D.P. Reservation area	0.000
(c) Green belt	0.000
Total (a+b+c)	1604.618
5. Balance area of plot (3-4)	15209.113
6. Amenity Space	1553.286
Applicable if (1) > 4000 sqm	
(Required -in) Upto 4000 sqm - Nil	
(d) Above 4000 sqm - (a) * 10 % of Total area	0.000
7. Net Plot Area (5-6)	12153.730
8. Recreational Open Space	
(a) If area (6) is more than 4000 sqm - 10 % of (6) is required.	1520.911
Proposed	1522.089
(b) If area is less than 4000 sqm - Check -	
(c) If it is full number like 1,2,125,418 etc. As per 7.12 Abstract or City Survey Number - No Recreational open space is required.	
(d) If it is subdivision like 1/2, 3/5, 1/25, 1/251, 4/191 etc then recreational open space is required.	
(A) 10 % Subject to minimum 200 sqm	0.000
Proposed	1522.089
(B) Exemption to leave open space subject to availing basic F.S.I. of 75 %	
(C) Exemption to leave open space subject to payment of 10 % land value of land at (7) as per annual statement of rate.	
Certificate of Area:	
Certified that the plot under reference was surveyed by me on 2023-11-02 and the dimensions of sides etc. of plot stated on plan as measured on site and the area is worked out in accordance with the area stated in document of Ownership T.P. Scheme Records/Land Records Department/City Survey records.	
Signature (Name of Architect/ Licensed Engineer/ Supervisor)	
Owner's Declaration :-	
I/We undersigned hereby confirm that I/We would abide by plans approved by Authority / Collector. I/We would execute the structure as per approved plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site.	
Owner (s) name and signature	
Architect/ Licensed Engineer/ Supervisor name and signature	
Job No.	

Name Of : Owner Mukund Sudhakar Kharote

Postal Address : ,shivoor,Aurangabad,Maharashtra-431116

Phone No.:9421419294

DESCRIPTION OF PROJECT :

Type of Proposal : Residential
BUILDING ON CTS. NO./SURVEY NO.--

SITE ADDRESS :
SHIOOR


Name Of Engineer : Padmabhushan Dinkar Saindane

LOGO	ADDRESS OF OFFICE
	OFFICE - Nanded

OWNERS SIGN -	TECHNICAL PERSON SIGN

N	SCALE - 1:100	Date: 11/02/25
	JOB NO - RPAUR-23-96549	CHECK BY - -

Verified by approval **SUBMISSION DRAWING**



AMENITY CALCULATION		
Sr.No	NAME	AREA(Sq.M)
1	AMENITY SPACE	1553.288
	Total	1553.288

LEGENDS:

PLOT BOUNDARY SHOWN WHITE
PROPOSED WORK SHOWN RED
DRAINAGE LINE SHOWN YELLOW LIGHT
WATER LINE SHOWN BLUE DOTTED
ENCLOSED BAL SHOWN BROWN
TERRACE SHOWN DARK YELLOW
OPEN BAL SHOWN BROWN
EXISTING SHOWN BLUE HATCHED