FORM OF STATEMENT TWO
SR.NO. 11(A)

BUILDING NO.	FLOOR NO.	TOTAL BUP AREA OF FLOOR	BALCONY AREA WITHIN 15%	EXCESS BAL. AREA COUNTED IN FSI	DOUBLE HEIGHT TERRACE AREA WITHIN 20%	EXCESS DOUBLE HEIGHT TERRACE AREA COUNTED IN FSI	TOTAL FSI 3+5+7
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
	FIRST FLOOR	124.55	18.68	0.00	0.00	0.00	124.55
	SECOND FLOOR	124.55	18.68	0.00	0.00	0.00	124.55
	THIRD FLOOR	124.55	18.68	0.00	0.00	0.00	124.55
	FOURTH FLOOR	69.62	10.44	0.00	0.00	0.00	69.62

BALCONY AREA STATEMENT

FLOOR NO.	BUP AREA	PERMISSIBLE BAL. AREA	PROPOSED BAL. AREA	EXCESS BAL. AREA
FIRST FLOOR	124.55	18.68	17.79	0.00
SECOND FLOOR	124.55	18.68	17.79	0.00
THIRD FLOOR	124.55	18.68	17.79	0.00
FOURTH FLOOR	69.62	10.44	8.85	0.00

TOTAL EXCECS BALCONY AREA AT ALL FLOORS = 0.00



NORTH ELEVATION
SCALE 1: 100



SECTION AA
SCALE 1: 100

FORM OF STATEMENT TWO
SR.NO. 11(B)

BUILDING NO.	FLOOR NO.	FLAT NO.	BUILTUP AREA OF FLAT ALONG WITH SHARE OF COMMON AREAS LIKE STAIRCASE,PASSAGE	AREA OF BALCONY ATTACHED TO FLAT	AREA OF DOUBLE HEIGHT TERRACE ATTACHED TO FLAT,UNIT	TOTAL AREA OF FLAT,UNIT (3+5+6)
(1)	(2)	(3)	(4)	(5)	(6)	(7)
	FIRST FLOOR	1	66.41+4.86=71.27	12.73	0.00	84.00
		2	28.11+4.86=32.97	3.17	0.00	36.14
		3	30.03+4.86=34.89	7.19	0.00	42.08
	SECOND FLOOR	4	66.41+4.86=71.27	12.73	0.00	84.00
		5	28.11+4.86=32.97	3.17	0.00	36.14
		6	30.03+4.86=34.89	7.19	0.00	42.08
	THIRD FLOOR	7	66.41+4.86=71.27	12.73	0.00	84.00
		8	28.11+4.86=32.97	3.17	0.00	36.14
		9	30.03+4.86=34.89	7.19	0.00	42.08
	FOURTH FLOOR	10	66.41+4.86=71.27	12.73	0.00	84.00



AREA CALCULATION
TYPICAL FIRST/SECOND/THIRD FLOOR AREA

AREA OF BLOCK ABCD = 11.60 X 12.51
= 145.11 SQ.M.....A

DEDUCTION
AREA OF BLOCK 1 = 2.40 X 7.55 = 18.12 SQ.M.
AREA OF BLOCK 2 = 1.50 X 1.65 = 2.47 SQ.M.
AREA OF BLOCK 3 = 0.45 X 6.62 = 2.97 SQ.M.
AREA OF BLOCK 4 = 0.70 X 2.92 = 2.04 SQ.M.
TOTAL DEDUCTION=25.60 SQ.M.

ADDITION
AREA OF BLOCK 1 = 4.43 X 0.39 = 1.72 SQ.M.
AREA OF BLOCK 2 = 4.62 X 0.72 = 3.32 SQ.M.
TOTAL ADDITION=5.04 SQ.M.

TOTAL AREA OF TYPICAL FLOOR = 124.55 SQ.M....A



AREA CALCULATION
FOURTH FLOOR AREA

AREA OF BLOCK ABCD = 7.13 X 12.51
= 89.19 SQ.M.....A

DEDUCTION
AREA OF BLOCK 1 = 2.55 X 7.55 = 19.25 SQ.M.

AREA OF BLOCK 4 = 0.70 X 2.92 = 2.04 SQ.M.
TOTAL DEDUCTION=21.29 SQ.M.

ADDITION
AREA OF BLOCK 1 = 4.43 X 0.39 = 1.72 SQ.M.

TOTAL ADDITION= 1.72 SQ.M.

TOTAL AREA OF FOURTH FLOOR =89.19-21.29+1.72
=69.62 SQ.M....A

CARPET AREA STATEMENT(ALL UNITS ARE IN SQ.M.)

FLOOR	FLAT NO.	FLOOR AREA OF ALL ROOMS EXCLUDING BALCONY/TERRACE (INCLUDING AREA UNDER INTERNAL WALLS)	USE
FIRST FLOOR	1	61.12	RESIDENTIAL
	2	25.19	
	3	27.02	
SECOND FLOOR	4	61.12	RESIDENTIAL
	5	25.19	
	6	27.02	
THIRD FLOOR	7	61.12	RESIDENTIAL
	8	25.19	
	9	27.02	
FOURTH FLOOR	10	61.12	RESIDENTIAL

PARKING STATEMENT RESIDENTIAL

CARPET AREA OF TENAMENT	NO.OF TENAMENTS	TWO WHEELER REQUIRED	TWO WHEELER PROPOSED	FOUR WHEELERS REQUIRED	FOUR WHEELERS PROPOSED	CYCLE REQUIRED	CYCLE PROPOSED
0 TO 40 SQ.M.	6	6	6	2	2	6	6
40 TO 80 SQ.M.	4	16	16	4	4	8	8
TOTAL	10	22	22	6	6	14	14
VISITORS(5%)		2	2	1	1	1	1
TOTAL		24	24	7	7	15	15



GROUND/PARKING FLOOR PLAN
SCALE 1: 100



TYPICAL FIRST/SECOND/THIRD FLOOR PLAN
SCALE 1: 100



FOURTH FLOOR PLAN
SCALE 1: 100



SITE PLAN
SCALE 1: 100

LOCATION PLAN
SCALE 1: 10,000





STAMP OF APPROVAL

APPROVED
The Plans amended in...
As per the conditions Mentioned in the accompaning commencement
Certificate No. A1/30/862 dated 15/05/2017

Executive Engineer
TOWN PLANING
Nashik Municipal Corporation
Nashik



COMPOUND WALL SECTION
SCALE 1:100





RAIN WATER HARVESTING

CERTIFICATE OF THE AREA
CERTIFIED THAT PLOT UNDER REFERENCE WAS SURVEYED BY ME ON 01/01/2014 AND DIMENSION OF ALL SIDES ETC. OF THE PLOT STATED ON PLAN ARE MEASURED ON SITE AND AREA SO WORKED OUT TALLIES WITH AREA STATED IN DOCUMENT OF OWNERSHIP / T.P. ACT. LAND RECORDS DEPARTMENT/CITY SURVEY RECORDS

SIGNATURE OF ARCHITECT

OWNERS DECLERATION
I/WE UNDERSIGNED HEREBY CONFIRM THAT I/WE ABIDE BY PLANS SANCTIONED BY NASHIK MUNICIPAL CORPORATION. I/WE WOULD EXECUTE THE STRUCTURE AS PER SANCTIONED PLANS. ALSO I/WE WOULD EXECUTE THE WORK UNDER SUPERVISION OF PROPER TECHNICAL PERSON SO AS TO ENSURE THE QUALITY AND SFFETY AT THE WORK SITE.

OWNERS NAME AND SIGNATURE

ARCHITECTS NAME AND SIGNATURE

AREA STATEMENT

	SQM
AREA OF THE PLOT (AS PER 7/12 EXTRACT)	405.46
F.S.I. BASIC FSI	1.10
TOTAL PERMISSIBLE BUP AREA	446.00
FIRST FLOOR AREA	124.55
SECOND FLOOR AREA	124.55
THIRD FLOOR AREA	124.55
FOURTH FLOOR AREA	69.62
TOTAL BUILT UP AREA PROPOSED	443.27

SCHEDULE OF OPENINGS

D = 1.20x2.10
D1 = 0.90x2.10
D2 = 0.75x2.10
W1= 1.80 x 1.50
W2= 1.80 x 0.90
W= 3.00x1.20
V = 0.60 X 0.75

ARCHITECTS SIGN
ARCHITECT
A.V. MALPURE

R.C.C. CONSULTANT

OWNER SIGN
S.D. Ruidawan

PROFORMA I

PROPOSED RESIDENTIAL COMPLEX ON PLOT NO.3A, S.NO.482/2+3/3A, F.P.NO.6, TPS II, OF VILLAGE MAUJE NASHIK.

AREA STATEMENT

		SQ.M.
1	AREA OF THE PLOT MINIMUM AREA OF 8.00 TO BE CONSIDERED	
	a) AS PER OWNERSHIP DOCUMENT(7/12,CTS EXTRACT)	405.46
	b) AS PER MEASUREMENT SHEET	405.46
	c) AS PER SITE	405.46
2	DEDUCTION FOR	
	a) PROPOSED D.P./D.P. ROAD WIDENING AREA	-
	b) ANY D.P. RESERVATION AREA	-
	(TOTAL a+b)	-
3	GROSS AREA OF THE PLOT (1 - 2)	405.46
4	RECREATIONAL OPEN SPACE	
	a) REQUIRED	-
	b) PROPOSED	-
5	AMINITY SPACE	
	a) REQUIRED	-
	b) PROPOSED	-
6	SERVICE ROAD AND HIGHWAY WIDENING	-
7	INTERNAL ROAD AREA	-
8	NET AREA OF THE PLOT (3 - 5,6)	405.46
9	BUILTUP AREA WITH REFERENCE TO BASIC FSI AS PER FRONT ROAD WIDTH (SR. NO.6 X 1.1)	446.00
10	ADDITIONS OF AREA FOR FSI	
	a) IN SITU AREA AGAINST D.P. ROAD (1.65 X SR.NO.2(a))	-
	b) IN SITU AREA AGAINST AMINITY SPACE (2.00 OR 1.65 X SR.NO.5(b))	-
	c) PREMIUM FSI AREA (SUBJECT TO MAXIMUM OF 0.3 OF SR.NO.8)	-
	d) TDR AREA	-
	e) ADDITIONAL FSI AREA UNDER CHAPTER (11)	-
	(TOTAL a+b+c+d+e)	-
11	TOTAL AREA AVAILABLE (9+10)	446.00
12	MAXIMUM UTILIZATION OF FSI PERMISSIBLE AS PER ROAD WIDTH (AS PER REGULATION NO. 15.4)	2.25
13	TOTAL BUILTUP AREA PROPOSAL (EXCLUDING AREA UNDER SR.NO. 15b)	
	a) EXISTING BUILTUP AREA	0.00
	b) PROPOSED BUILTUP AREA	443.27
	c) EXCESS BALCONY AREA COUNTED IN FSI	0.00
	d) EXCESS DOUBLE HEIGHT TERRACE AREA COUNTED IN FSI	-
	(TOTAL a+b+c+d)	443.27
14	FSI CONSUMED (13/8) SHOULD NOT MORE THAN SR.NO. 12	1.09
15	AREA FOR INCLUSIVE HOUSING IF ANY	-
	a) REQUIRED (20% OF SR.NO.8)	-
	b) PROPOSED	-

LAND OWNER	SHRI.RADHAMADAN GOPAL CONSTRUCTION AND DEVELOPERS
TITLE	REVISED BUILDING PERMISSION DRAWING
PROJECT	PROPOSED RESI. BUILDING IN S.NO.482/2+3/3A,P. NO.3A, AT NASHIK SHIWAR, A/P.NASHIK, TAL&DIST.NASHIK.
CONSULTING ARCHITECT	LOGICAL SPACES AR. ABHIJIT V. MALPURE SUKHA HEIGHTS, YEOLEKAR MALA, COLLEGE ROAD, NASHIK-7 CELL 9423479935

SCALE	1:100
DATE	23/04/2017
DELT BY	AVM
CHKD BY	AVM
JOB NO.	JF3
DRG NO.	M 1