



1/3

NASHIK MUNICIPAL CORPORATION

NO:LND/BP/ A3/274/3671/13

OFFICE OF NASHIK MUNICIPAL CORPORATION
DATE :- 25/11/2013

SANCTION OF BUILDING PERMIT AND COMMENCEMENT CERTIFICATE

TO,

M/s Sairaj Builders & developers Partnership Firm, Partner Shri Prakash

V. Ochani & other, C/o Er. / Str. Er. Ravi Amrutkar of Nashik

Sub : - Sanction of Building permit & commencement certificate in Plot No.2+3+6+7 S.No.773/2+3+6+7 at Nashik Shiwar.

Ref : - Your Application & plan dated 01/06/2013 inward No. A1/BP/1345

Sanction of building permit & commencement certificate is hereby granted under section 45 & 69 of the Maharashtra Regional and Town Planning Act 1966 (Mah. Of 1966) to carry out development work / and building permits under section 253 of The Bombay Provincial Municipal Corporation Act. 1949 (Bombay Act.No.LIX of 1949) to erect building for **Residential + Amalgamation** purpose as per plan duly amended in ----- subject to the following conditions.

CONDITIONS (1 to 41)

- 1) The land vacated in consequence of enforcement of the set-back rule shall form part of public street.
- 2) No new building of part thereof shall be occupied or allowed to be occupied or permitted to be used by any person until completion certificate, under sec. 263 of the Bombay Provincial Municipal Corporation Act, 1949 is duly granted.
- 3) The commencement certificate Building permit shall remain valid for a period of one year commencing from date of its issue & thereafter it shall become invalid automatically unless otherwise renewed in stipulated period Construction work commenced after expiry of period for which commencement certificate is granted will be treated as unauthorised development & action as per provisions laid down in Maharashtra Regional & Town Planning Act 196 & under Bombay Provisional Municipal Corporation Act. 1949 will be taken against such defaulter which should please be clearly noted.
- 4) This permission does not entitles you to develop the land which does not vest to you.
- 5) The date of commencement of the construction work should be intimated to this office **WITHIN SEVEN DAYS.**
- 6) Permission required under the provision of any other Act, for the time being in force shall be obtained from the concerned authorities before commencement of work [viz punder provision of Urban Land Ceilling & Regulation Act & under appropriate sections of Maharashtra Land Revenue Code 1965 etc.]
- 7) After completion of plinth certificate of planning authority to the effect that the plinth is constructed as per sanctioned plan should be taken before commencement of superstructure.

(2)

2/3

- 8) The building permission is granted on the strength of affidavit & indemnity bond with reference to the provisions of Urban Land [Ceilling & Regulation] Act, 1976. In case a statement made in affidavit & indemnity bond found incorrect or false the permission shall stand cancelled.
- 9) The drains shall be lined out & covered up properly to the satisfaction of Municipal Authorities of Nashik Municipal Corporation.
The effluent from septic tank, kitchen, bath, etc, should be properly connected to Municipal drain in the nearest vicinity invert levels of the effluent of the premises should be such that the effluent gets into the Municipal drain by gravity self cleaning velocity.
- In case if there is no Municipal drain within 60 meters should be connected to a soakpit to be provided by the owner.
- The size of soakpit should be properly worked out on the basis of tenements% a pigeon hole circular brick wall should be constructed in the centre of the soak pit. Layers of stone boulders, stone metals and pebbles should be properly laid.
- 10) The balconies, ottas & verendas should not be enclosed and merged into adjoining room or rooms unless they are counted into built up area of FSI calculation as given on the building plan. If the balcony ottas & verendas are covered or merged into adjoining room the construction shall be treated as unauthorised and action shall be taken.
- 11) At least FIVE trees should be planted around the building in the open space of the plot. Completion certificate shall not be granted if trees are not planted in the plot as provided under section 19 of the Preservation of Tree Act, 1975.
- 12) The construction work should be strictly carried out in accordance with the sanctioned plan enclosed herewith.
- 13) Copy of approved plan should be kept on site so as to facilities the inspection of the site by Municipal Corporation's staff from time to time and necessary information in respect of construction work should be furnished whenever required by the undersigned.
- 14) Stacking of building material debris on public road is strictly prohibited. If building material of debris is found on public road the same will be removed by the Authority and cost incurred in the removal of such material shall be recovered from the owner.
- 15) All the conditions should be strictly observed and breach of any of the conditions will be dealt with in accordance with the provision of Maharashtra Regional & Town Planning Act, 1966 and Bombay Provincial Municipal Corporation Act, 1949.
- 16) Nashik Municipal Corporation will not supply water, electricity, road etc, which will be provided by the applicant Colony / Society etc, on their own accord as per the specifications of N.M.C. Applicant should make necessary arrangement for water supply as per the undertaking given. Similarly street lights will not be provided by Municipal Corporation till Electric supply Mains of M.S.E.B. is available at site.
- 17) There is no objection to obtain electricity connection for construction purpose from M.S.E.B.
- 18) N. A. order No. 124/98 dated 15/12/1998 submitted with the application.
- 19) Adequate space from the plot u/r should be reserved for transformer in consultation with M.S.E.B. office before actually commencing the proposed construction.
- 20) A) **Rs. 287500+ 418732** is paid for development charges w.r.t. the proposed construction
Vide R.No./ B.No. 21/503, 21/536 Dated 15/01/2013, 31/10/2013
- 20) B) **Rs. --** is paid for land development charges w.r.t. the proposed construction
vide R.No./ B.No. -- dated --

CC:- Plot No.2+3+6+7 S.No.773/2+3+6+7 at Nashik Shiwar.

3/3

- 22) Tree plantation shall be made as per the guidelines of Tree Officer of N.M.C. & NOC shall be obtained before occupation certificate.

Sum of Rs.11410/- Deposited vide R.No./B.No. 39/2153 Dated 15/01/2013
As per Order No.137, dt.18/03/2000

- 23) Septic tank & soak pit shall be constructed as per the guidelines of Health Officer of N.M.C. & NOC shall be produced before occupation certificate.
- 24) A) Before commencing the construction on site the owner/ developer shall install "Display Board" on the conspicuous place on site indicating following details.
- a) Name & Address of the owner / developer, Architect / Engineer and Contractor.
 - b) Survey Number / City survey Number / Ward Number of land under reference alongwith description of its boundaries.
 - c) Order Number and date of grant of development permission / redevelopment permission issued by the Planning Authority or any other authority.
 - d) F.S.I. permitted.
 - e) Number of Residential / Commercial flats with their areas.
 - f) Address where copies of detailed approved plans shall be available for inspection.
- B) A notice in the form of an advertisement giving all the details mentioned in 24 (A) above, shall also be published in two widely circulated newspapers one of which should be in regional language.
- 25) Proper arrangement in consultation with Telecom Deptt. To be done for telephone facilities to be provided in the proposed construction.
- 26) Drainage charges Rs. 32000+8000 is paid vide R.No./B.No. 90/6643, 68/8073 Dt. 15/01/2013, 31/10/2013
- 27) Welfare cess charges Rs.203870+297100 is paid w.r.t. the proposed construction vide R.No./B.No. 07/6669,084/8073 Dt.15/01/2013, 31/10/2013
- 28) Nashik Municipal Corporation shall not be responsible for the ownership & boundaries of the land.
- 29) Fly ash bricks and fly ash based and related materials shall be used in the construction of buildings.
- 30) The Rain Water Harvesting system to be made on site.
- 31) NMC vacant plot tax receipt to be produced before completion.
- 32) Layout is tentatively approved vide letter No.123, dt.11/03/2003
- 33) Sale deed copy & 7/12 Extract of D.P.Road area in the name of NMC is enclosed herewith.
- 34) The amalgamated 7/12 Extract to be produced before completion.
- 35) This Permission is given on the strength of DRC No.611,dt.13/02/2013,'C'zone, Area 915.00 Sqm area is utilized from the same.
- 36) This Permission is given on the basis of affidavit given by applicant dt.16/11/2013 regarding N.M.C. supplied water and public source of water not be use for construction purpose. Also after obtaining occupancy certificate decision of NMC regarding drinking water supply connection shall be binding on applicant.
- 37) NMC shall not supply water for construction purpose.
- 38) The provisional Fire NOC from CFO is obtained vide letter No.NMC/FIRE/WS/II/168/2013, dt. 05/10/2013 is enclosed herewith & final NOC should be produced before completion.
- 39) Prev. approved B.P.No. B3/BP/589/5492,dt.16/01/2013 is hereby cancelled.
- 40) This permission is given on the basis of affidavit given by applicant dt.16/11/2013 for disposal of excavated debris material on his own at the prescribed site.
- 41) LBT Reg. No.NSK604684, Undertaking for LBT dt.16/11/2013 is given by the owner.

Executive Engineer
(Town Planning)

Nashik Municipal Corporation, Nashik

No.LND/BP
Nashik, Dt. / /200
Copy to : Divisional Officer,
Division
Nashik Municipal Corporation, Nashik