PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

FLOOR WISE FSI STATEMENT : A B (BUILDING)

FLOORS	FSI AREA				BALCONY			PASSAGE	STAIR		LIFT		TERRACE	LIFT M/C ROOM	TENE.	TOTAL
	COMM.	RESI.	IND.	SPEC.	PERM.	PROP.	EXCESS		NORMAL STAIR	FIRE STAIR	FREE OF FSI					FSI AREA
GROUND FLOOR	264,60	0,00	0,00	0,00	35,69	0,00	0,00	0,00	0,00	0,00	0,00		0,00	-	0	264,60
FIRST FLOOR	0,00	401,47	0,00	0,00	66,67	49,02	0,00	3,60	39,15	0,00	6,48		74,13	-	8	404,47
SECOND FLOOR	0,00	377,52	0,00	0,00	56,63	73,66	17,20	3,60	39,15	0,00	0,00		7,78	-	8	377,52
THIRD FLOOR	0,00	384,81	0,00	0,00	57,72	73,66	15,91	3,60	39,15	0,00	0,00		7,28	-	8	384,81
FOURTH FLOOR	0,00	399,09	0,00	0,00	59,86	73,66	13,80	17,88	39,15	0,00	0,00		7,28	-	8	399,09
FIFTH FLOOR	0,00	377,52	0,00	0,00	56,63	73,66	17,20	3,60	39,15	0,00	0,00		7,28	-	8	377,52
SIXTH FLOOR	0,00	377,52	0,00	0,00	56,63	73,66	17,20	3,60	39,15	0,00	0,00		7,78	-	8	377,52
SEVENTH FLOOR	0,00	324,87	0,00	0,00	48,73	62,76	14,03	3,60	39,15	0,00	0,00		55,72	-	8	324,87
TOTAL	264,60	2645,80	0,00	0,00	436,56	480,09	49,53	39,48	267,26	0,00	6,48		171,21	0,00	56	2915,40

FLOOR WISE FSI STATEMENT : C D (BUILDING)

FLOORS	FSI AREA				BALCONY			PASSAGE	STAIR		LIFT		TERRACE	LIFT M/C ROOM	TENE.	TOTAL
	COMM.	RESI.	IND.	SPEC.	PERM.	PROP.	EXCESS		NORMAL STAIR	FIRE STAIR	FREE OF FSI					FSI AREA
GROUND FLOOR	0,00	0,00	0,00	0,00	0,00	0,00	0,00	0,00	0,00	0,00	0,00		0,00	-	0	0,00
FIRST FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	6,48		0,00	-	10	433,35
SECOND FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	0,00		0,00	-	10	433,35
THIRD FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	0,00		0,00	-	10	433,35
FOURTH FLOOR	0,00	433,83	0,00	0,00	65,07	62,24	0,00	19,87	30,27	0,00	0,00		20,00	-	10	433,83
FIFTH FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	0,00		0,00	-	10	433,35
SIXTH FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	0,00		0,00	-	10	433,35
SEVENTH FLOOR	0,00	433,35	0,00	0,00	65,00	62,24	0,00	15,70	30,27	0,00	0,00		0,00	-	10	433,35
TOTAL	0,00	3033,83	0,00	0,00	455,07	435,71	0,00	114,10	212,59	0,00	6,48		20,00	0,00	70	3033,83

BUILDING WISE FSI STATEMENT

BUILDING	FSI AREA				BALCONY			PASSAGE	STAIR	LIFT	TERRACE	LIFT M/C ROOM	TENE.	TOTAL
	COMM.	RESI.	IND.	SPEC.	PERM.	PROP.	EXCESS							FSI AREA
A B-1 (BUILDING)	264,60	2645,80	0,00	0,00	436,56	480,09	49,53	39,48	267,26	6,48	171,21	21,78	56	2915,40
C D-1 (BUILDING)	0,00	3033,83	0,00	0,00	455,07	435,71	0,00	114,10	212,59	6,48	20,00	23,88	70	3033,83
TOTAL	264,60	5679,63	0,00	0,00	891,63	915,80	49,53	153,58	479,84	12,96	191,21	45,67	126	5949,23

PARKING CALCULATION

TYPE	CARPET AREA FSI (NO)	TENEMENT (NOS)		CAR (NOS)		SCOOTER (NOS.)		CYCLE (NOS.)	
		UNIT	PROP.	BY RULE	REQD.	BY RULE	REQD.	BY RULE	REQD.
RESIDENTIAL	0 - 60	4	112	1	28	4	112	4	112
RESIDENTIAL	60.00 - 90	1	14	1	14	4	56	2	28
RESIDENTIAL	90.00 - 120	1	6	2	9	2	6	2	9
RESIDENTIAL	> 120.00	1	6	3	9	2	6	2	9
COMMERCIAL	247.23	100	3	2	6	4	12	4	12
VISITOR				5% (Car)	3	5% (SC)	9	5% (CY)	9
TOTAL	REQUIRED	-	-	-	61	-	189	-	159
TOTAL	PROPOSED	-	-	-	91	-	203	-	189

WATER REQUIREMENT

TANK		OCCUPANT LOAD / FACT		CONS / DAY (LIT)	REQD. CAP.(LIT)	PROP. CAP.(LIT)
OHWT	RESI.REQMT.	126	3	630	113	85000
	COMLREQMT.	265	3	5.9	45	4000
		0	0	0	45	0
	INDUSTOMT.	- NA -		- NA -	- NA -	- NA -
	SPECIEMT.	- NA -		- NA -	- NA -	- NA -
						89000
	FIRE REQMT.					0
					89055	174793
UGWT		1.5			33.53	175250

TERRACE CALCULATIONS: C D (BUILDING)

FLOOR	SIZE	AREA	TOT. AREA
FOURTH FLOOR	5.10 X 2.50 / 2 + 2	20.00	20.00
TOTAL	-	-	20.00

OPENING SCHEDULE: A B (BUILDING)

NAME	WIDTH	HEIGHT	NOS.
D1	0,75	2,10	142
D2	0,90	2,10	75
D3	0,80	2,10	128
MD	1,00	2,10	56
MD	1,05	2,10	56
RS	2,00	2,10	01
RS	2,75	2,10	02
RS	2,95	2,10	02
RS	3,00	2,10	02
RS	3,60	2,10	02

OPENING SCHEDULE: A B (BUILDING)

NAME	WIDTH	HEIGHT	NOS.
V	0,60	0,60	56
V	0,60	1,20	110
W1	1,10	1,20	51
W	1,20	1,20	27
W	1,23	1,20	14
W3	1,45	1,20	13
W3	1,50	1,20	13
W3	1,55	1,20	07
W	1,64	1,20	27
W2	1,80	1,20	15
W	1,80	1,20	82
W	1,85	1,20	14

OPENING SCHEDULE: C D (BUILDING)

NAME	WIDTH	HEIGHT	NOS.
V	0,60	1,20	180
W1	1,45	1,20	26
W	1,50	1,20	72
W3	1,80	1,20	18
FD	1,85	2,10	08
FD	2,60	2,10	14

BUILDING WISE COVERAGE TABLE

BUILDING	AREA
A B-1 (BUILDING)	460,91
C D-1 (BUILDING)	411,60





LOCATION PLAN
SCALE 1:10,000



ELEVATION WING A,B



WING A,B SECTION B-B
SECTION B-B WING A,B



TYPICAL - 3& 5 FLOOR PLAN



GROUND FLOOR PLAN



FIRST FLOOR PLAN



TYPICAL - 2& 6 FLOOR PLAN

STAMP OF APPROVAL 1/4 A0

A) AREA STATEMENT

	SQ.M.
1. AREA OF PLOT	2661.00
2. DEDUCTIONS FOR:	
(a) ROAD WIDENING AREA	0.00
(b) PROPOSED D.P. ROAD	0.00
(c) ANY RESERVATION	0.00
(d) PANNING AREA	0.00
TOTAL (a+b+c+d)	0.00
3. GROSS AREA OF PLOT (1-2) :	2661.00
4. RECREATIONAL OPEN SPACE	
(a) REQUIRED AREA	266.10
(b) PROPOSED AREA	0.00
5. AMENITY SPACE	
(a) REQUIRED AREA	0.00
(b) PROPOSED AREA	0.00
6. SERVICE ROAD AND HIGHWAY WIDENING	0.00
7. INTERNAL ROAD AREA	0.00
8. NET AREA OF PLOT (3-4(a))	2661.00
9. BASIC PERMISSIBLE F.S.I. 1.1000	2927.10
10. ADDITION OF AREA FOR F.S.I.	
(a) ROAD WIDENING AREA (1.85 X 2(b))	0.00
(b) DP ROAD AREA (1.85 X 3(b))	0.00
(c) AMENITY SPACE (2.0 or 1.85 X 5(a))	0.00
(c) PREMIUM F.S.I. AREA	1330.50
(d) TDR AREA	1729.65
(f) ADD. F.S.I AREA UNDER CHAPTER VIII	0.00
TOTAL (a+b+c+d+e+f)	3060.15
11. TOTAL AREA (9+10) :	5987.25
12. MAX. UTILIZATION OF F.S.I. AS PER ROAD WIDTH	2.25
13. PROPOSED BUILT UP AREA	
(a) EXISTING FLOOR AREA	0.00
(b) PROPOSED RESIDENTIAL AREA	5679.73
(c) PROPOSED COMMERCIAL AREA	264.60
(d) PROPOSED INDUSTRIAL AREA	0.00
(e) PROPOSED SPECIAL FSI AREA	0.00
(g) EXCESS BALCONY AREA TAKEN IN F.S.I.	24.13
(h) EXCESS TERRACE AREA TAKEN IN F.S.I.	0.00
(i) LIFT AREA	6.48
(j) ARCH PROJECTION AREA	0.00
(k) EXISTING FLOOR AREA	0.00
TOTAL BUILT UP AREA (a to k) (Excluding Area 15(b))	5974.94
14. F.S.I. CONSUMED (13/8) :	2.25 00
15. AREA FOR INCLUSIVE HOUSING, If Any	
(a) REQUIRED (20% of 8)	000.00
(b) PROPOSED	000.00

B) BALCONY STATEMENT

(a) PERMISSIBLE BALCONY AREA	891.63
(b) PROPOSED BALCONY AREA	915.76
(c) EXCESS BALCONY AREA (TOTAL)	24.13

C) PARKING STATEMENT

	CARS	CARS SCOOTER	CYCLE
(a) PARKING REQUIRED BY RULE	2.5	2.5	1.67
(b) PARKING PROVIDED	2.42	2.5	2.03

CERTIFICATE OF AREA

CERTIFIED THAT THE FOOT PRINT/ENTERANCE WAS SUBMITTED BY SELOW AND THE DIMENSIONS OF BRICK ETC. OF PLOT BOUNDARY PLAN ARE AS PRESENTED ON SITE AND THE AREA AS SHOWN BOTH WITH THE AREA STATED IN DOCUMENT OF OWNERSHIP, TP SCHEME RECORD / LAND RECORD COPY / CITY SURVEYED RECORDS.

Sign of Architect/Licensed Engineer/Supervisor

OWNER'S DECLARATION

I/We undersigned hereby confirm that I/We would abide by all the rules and regulations framed by Rajkot Municipal Corporation. I/We would like to secure person so as to ensure the quality and safety as the work who.

Owner's Sign

LEGEND

PLOT BOUNDARY SHOWN BLACK
PROPOSED WORK SHOWN RED
EXISTING BUILDING SHOWN HATCHED
SHADED AREA SHOWN AS DOTTED
SETBACKS SHOWN BLUE
DEDUCTION SHOWN PROPOSED YELLOW

OWNER'S NAME: OWNER'S SIGN.

MAHESHWAR ENTERPRISES PARTNERSHIP FIRM THR. PARTNER MR. MILESH D. GAJIPARA

PROJECT Building Permission

PLOT NO. 1 CTS NO.
FINAL PLOT NO. SURVEY NO. 328/1/1
VILLAGE : Pathardi

ARCHITECT/ENGINEER/SURVEYOR'S NAME: SIGN.

Sandeep Mothabhai Jagtap
1, Rishabh Apt., Kalpna Nagar, College Road
Nasik

JOB NO.	DRG.NO.	SCALE	DRAWN BY	CHECKED BY
		1:100		

AWARD NO. : NMC/TP/DP/other/BP/0264/2019
KEY NO.. :
DATE : 11-12-2019 SHEET NO. : 1 / 4

THIS IS A SYSTEM GENERATED DRAWING (APPROVED COPY) AS PER THE SOFT COPY SUBMITTED BY THE ARCHITECT/ LICENSE ENGINEER

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT