PLOT AREA CALCULATION S.NO. 146/1.

1.	10.33	X 0.21	X 0.50	=	1.08 SQ.M.	
2.	10.52	X 2.49	X 0.50	=	13.09 SQ.M.	
TOTAL AREA				=	14.17 SQ.M.	
AS PER P-LINE AREA				=	**14.15 SQ.M.**	

AREA UNDER NOT IN POSSESSION CALCULATION S.NO. 146/1

K.	7.25	X 0.15	X 0.50	=	0.54 SQ.M.	
L.	12.08	X 4.02	X 0.50	=	24.28 SQ.M.	
M.	12.44	X 8.42	X 0.50	=	52.37 SQ.M.	
N.	12.44	X 11.24	X 0.50	=	69.91 SQ.M.	
O.	12.05	X 3.19	X 0.50	=	19.25 SQ.M.	
TOTAL AREA				=	166.35 SQ.M.	
AS PER P-LINE AREA				=	**166.35 SQ.M.**	

TOTAL PLOT AREA CALCULATION S.NO. 146/1

TOTAL AREA	= 14.15 + 166.35	=	180.50 SQ.M.	
TOTAL AREA		=	**180.50 SQ.M.**	

PLOT AREA CALCULATION S.NO. 149/3

3.	13.36	X 8.66	X 0.50	=	57.85 SQ.M.	
4.	19.76	X 4.17	X 0.50	=	41.20 SQ.M.	
5.	27.90	X 3.38	X 0.50	=	47.15 SQ.M.	
6.	27.90	X 1.49	X 0.50	=	20.79 SQ.M.	
7.	28.34	X 1.49	X 0.50	=	21.11 SQ.M.	
8.	27.16	X 11.28	X 0.50	=	153.18 SQ.M.	
9.	15.50	X 5.65	X 0.50	=	43.79 SQ.M.	
10.	15.04	X 7.16	X 0.50	=	53.84 SQ.M.	
11.	56.34	X 10.67	X 0.50	=	300.57 SQ.M.	
12.	37.78	X 15.86	X 0.50	=	299.60 SQ.M.	
13.	19.22	X 3.22	X 0.50	=	30.94 SQ.M.	
14.	20.00	X 15.00	X 0.50	=	150.00 SQ.M.	
15.	29.36	X 5.04	X 0.50	=	73.98 SQ.M.	
16.	35.68	X 1.76	X 0.50	=	31.39 SQ.M.	
17.	35.68	X 21.97	X 0.50	=	391.94 SQ.M.	
18.	42.34	X 16.28	X 0.50	=	344.64 SQ.M.	
19.	27.86	X 7.79	X 0.50	=	108.51 SQ.M.	
20.	27.86	X 5.83	X 0.50	=	81.21 SQ.M.	
21.	27.73	X 10.73	X 0.50	=	148.77 SQ.M.	
TOTAL AREA				=	2400.46 SQ.M.	
AS PER P-LINE AREA				=	**2400.42 SQ.M.**	

PLOT AREA CALCULATION S.NO. 154/3

1.	40.98	X 21.10	X 0.50	=	432.34 SQ.M.	
2.	40.98	X 8.19	X 0.50	=	167.81 SQ.M.	
TOTAL AREA				=	600.15 SQ.M.	
AS PER P-LINE AREA				=	**600.15 SQ.M.**	

PLOT AREA CALCULATION S.NO. 412/1

22.	42.55	X 13.11	X 0.50	=	278.92 SQ.M.	
23.	70.47	X 35.11	X 0.50	=	1237.10 SQ.M.	
24.	70.47	X 20.24	X 0.50	=	713.16 SQ.M.	
25.	49.09	X 2.69	X 0.50	=	66.02 SQ.M.	
26.	51.42	X 6.40	X 0.50	=	164.54 SQ.M.	
27.	55.93	X 4.38	X 0.50	=	122.49 SQ.M.	
28.	55.93	X 12.90	X 0.50	=	360.75 SQ.M.	
29.	21.67	X 12.98	X 0.50	=	140.64 SQ.M.	
30.	13.28	X 6.26	X 0.50	=	41.56 SQ.M.	
TOTAL AREA				=	3125.18 SQ.M.	
AS PER P-LINE AREA				=	**3125.17 SQ.M.**	

AREA UNDER NOT IN POSSESSION CALCULATION S.NO. 412/1

A.	11.99	X 5.28	X 0.50	=	31.65 SQ.M.	
B.	13.67	X 6.32	X 0.50	=	43.20 SQ.M.	
C.	18.67	X 11.77	X 0.50	=	109.87 SQ.M.	
D.	32.11	X 0.30	X 0.50	=	4.82 SQ.M.	
E.	31.61	X 3.80	X 0.50	=	60.06 SQ.M.	
F.	27.42	X 10.86	X 0.50	=	148.89 SQ.M.	
G.	18.11	X 2.74	X 0.50	=	24.81 SQ.M.	
H.	19.98	X 2.75	X 0.50	=	27.47 SQ.M.	
I.	13.83	X 2.12	X 0.50	=	14.66 SQ.M.	
J.	8.34	X 2.34	X 0.50	=	9.76 SQ.M.	
TOTAL AREA				=	475.19 SQ.M.	
AS PER P-LINE AREA				=	**475.19 SQ.M.**	

TOTAL PLOT AREA CALCULATION S.NO. 412/1

TOTAL AREA = 3125.17 + 475.19	=	3600.36 SQ.M.
TOTAL AREA	=	**3600.36 SQ.M.**

PARKING STATEMENT (EXISTING - BUILDING NO. - 1)

	DESCRIPTION	NO OF PARKING
1.	1 CAR PARKING SPACE FOR EVERY 50.00 SQ.MT. OR FRACTION THERE OF SUBJECT TO A MINIMUM OF TWO SPACES. B/UP AREA FOR EVERY 50.00 SQ.MT. (TOTAL B/UP AREA = 12679.81 SQ.MT.) 12679.81 / 50 = 254 NOS.	254 NO'S.
	TOTAL PARKING REQD. (AS PER SANCTION)	254 NO'S.
	TOTAL PARKING PROVIDED (AS PER SANCTION)	254 NO'S.
2.	1 TWO WHEELER PARKING SPACE FOR EVERY 100.00 SQ.MT. PARKING REQUIRED = 12679.81/100 = 127 NOS.	127 NO'S.
	TOTAL PARKING PROVIDED (AS PER SANCTION)	140 NO'S.

PARKING STATEMENT (EXIST + PROPOSED)

DESCRIPTION	PARKING PROVIDED	
	CAR	TWO WHEELER
EXISTING PARKING (AS PER SANCTION)	271 NO'S.	140 NO'S.
PARKING PROPOSED (AS PER UDCPR)	1146 NO'S.	368 NO'S.
TOTAL PARKING (EXIST + PROPOSED)	**1417 NO'S.**	**508 NO'S.**
LOADING / UNLOADING	05 NO'S.	

PLOT AREA DIAGRAM
SCALE = 1 : 1000

PLOT AREA CALCULATION S.NO. 414/1/C/2

33.	21.98	X 2.32	X 0.50	=	25.50 SQ.M.	
34.	33.31	X 9.39	X 0.50	=	156.39 SQ.M.	
35.	56.80	X 6.27	X 0.50	=	178.07 SQ.M.	
36.	156.49	X 31.13	X 0.50	=	2435.76 SQ.M.	
37.	172.22	X 14.70	X 0.50	=	1265.82 SQ.M.	
38.	172.22	X 14.53	X 0.50	=	1251.18 SQ.M.	
39.	158.93	X 32.93	X 0.50	=	2616.78 SQ.M.	
40.	66.60	X 3.05	X 0.50	=	101.56 SQ.M.	
41.	56.79	X 13.45	X 0.50	=	381.91 SQ.M.	
42.	67.63	X 8.68	X 0.50	=	293.51 SQ.M.	
43.	70.79	X 22.43	X 0.50	=	793.91 SQ.M.	
44.	70.79	X 17.80	X 0.50	=	630.03 SQ.M.	
45.	60.52	X 24.83	X 0.50	=	751.36 SQ.M.	
46.	27.55	X 5.95	X 0.50	=	81.96 SQ.M.	
47.	13.09	X 4.26	X 0.50	=	27.88 SQ.M.	
48.	16.42	X 4.63	X 0.50	=	38.02 SQ.M.	
49.	26.79	X (10.59+6.68)	X 0.50	=	231.33 SQ.M.	
50.	69.72	X 28.29	X 0.50	=	986.18 SQ.M.	
51.	29.53	X 6.75	X 0.50	=	99.66 SQ.M.	
52.	68.23	X 2.09	X 0.50	=	71.30 SQ.M.	
53.	68.21	X 6.58	X 0.50	=	224.41 SQ.M.	
54.	66.76	X 4.85	X 0.50	=	161.89 SQ.M.	
55.	66.94	X 3.51	X 0.50	=	117.47 SQ.M.	
56.	66.94	X 7.86	X 0.50	=	263.07 SQ.M.	
57.	113.38	X 27.61	X 0.50	=	1565.21 SQ.M.	
58.	87.99	X 1.17	X 0.50	=	51.47 SQ.M.	
59.	86.88	X 4.13	X 0.50	=	179.41 SQ.M.	
60.	80.75	X 2.33	X 0.50	=	94.07 SQ.M.	
61.	78.60	X 9.40	X 0.50	=	369.42 SQ.M.	
62.	68.65	X 10.00	X 0.50	=	343.25 SQ.M.	
63.	62.04	X 7.60	X 0.50	=	235.75 SQ.M.	
64.	58.88	X 5.04	X 0.50	=	148.38 SQ.M.	
65.	56.37	X 2.63	X 0.50	=	74.13 SQ.M.	
66.	56.37	X 5.38	X 0.50	=	151.63 SQ.M.	
67.	35.43	X 11.42	X 0.50	=	202.33 SQ.M.	
TOTAL AREA				=	16598.73 SQ.M.	
AS PER P-LINE AREA				=	**16598.71 SQ.M.**	

AMENITY AREA CALCULATION S. NO. 414/1/C/2

i.	47.03	X 8.48	X 0.50	=	199.40 SQ.M.	
ii.	71.88	X 41.07	X 0.50	=	1476.05 SQ.M.	
iii.	71.88	X 2.88	X 0.50	=	103.50 SQ.M.	
iv.	70.38	X 2.53	X 0.50	=	89.03 SQ.M.	
v.	70.10	X 3.54	X 0.50	=	124.07 SQ.M.	
vi.	69.69	X 3.31	X 0.50	=	115.33 SQ.M.	
vii.	70.17	X 8.85	X 0.50	=	310.50 SQ.M.	
viii.	70.80	X 3.29	X 0.50	=	116.46 SQ.M.	
ix.	71.75	X 4.56	X 0.50	=	163.59 SQ.M.	
x.	72.81	X 3.80	X 0.50	=	138.33 SQ.M.	
TOTAL AREA				=	2836.26 SQ.M.	
AS PER P-LINE AREA				=	**2836.26 SQ.M.**	

AREA UNDER NOT IN POSSESSION CALCULATION S.NO. 414/1/C/2.

P.	11.03	X 3.75	X 0.50	=	20.68 SQ.M.	
Q.	21.36	X 6.98	X 0.50	=	74.55 SQ.M.	
R.	26.20	X 8.36	X 0.50	=	109.52 SQ.M.	
S.	26.20	X 12.59	X 0.50	=	164.93 SQ.M.	
T.	33.67	X 4.67	X 0.50	=	78.62 SQ.M.	
U.	57.11	X 3.45	X 0.50	=	98.51 SQ.M.	
V.	57.11	X 6.44	X 0.50	=	183.89 SQ.M.	
W.	48.35	X 7.86	X 0.50	=	190.01 SQ.M.	
TOTAL AREA				=	920.71 SQ.M.	
AS PER P-LINE AREA				=	**920.71 SQ.M.**	

TOTAL PLOT AREA CALCULATION S.NO. 414/1/C/2.

TOTAL AREA = 16598.71 + 2836.26 + 920.71	=	20355.68 SQ.M.
TOTAL AREA	=	**20355.68 SQ.M.**

GRAND TOTAL PLOT AREA CALCULATION S.NO. 146/1, 149/3, 154/3, 412/1, 414/1/C/1, 414/1/C/2.

TOTAL AREA
= 180.50 + 2400.42 + 600.15 + 3600.36 + 20355.68
= 27137.11 SQ.M.

TOTAL AREA	=	**27137.11 SQ.M.**

S.NO. 414/1/C/1 (ROAD HANDEDOVER) = 1240.00 SQ.M.
TOTAL AREA (27137.11 + 1240.00) = **28377.11 SQ.M.**

PROPOSED MULTILEVEL CAR PARKING FOR EXISTING BLDG. NO. 1 (ITE)

SR. NO.	FLOOR LEVEL	CAR PARKING PROP.	TWO WHEELER PARKING PROP.
1	OPEN PARKING	6 NO'S.	----
	MULTILEVEL CAR PARKING		
2	GROUND FLOOR	13 NO'S.	140 NO'S.
3	1ST TO 6TH FLOOR	36 X 6 FL = 216 NO'S.	----
4	TERRACE FLOOR	36 NO'S.	----
TOTAL PARKING		265 NO'S.	140 NO'S.
TOTAL PARKING PROPOSED		271 NO'S.	140 NO'S.
TOTAL PARKING REQUIRED (AS PER SANCTION)		254 NO'S.	127 NO'S.

PROPOSED PARKING STATEMENT

BLDG.NO. 2 (COMMERCIAL)

SR. NO.	FLOOR LEVEL	CAR PARKING PROP.	TWO WHEELER PARKING PROP.
1	BASEMENT LEVEL	51 NO'S.	47 NO'S.
2	LOWER GROUND LEVEL	94 NO'S.	29 NO'S.
3	GROUND FLOOR	-----	-----
4	COMM. PODIUM (P1)	-----	-----
5	COMM. PODIUM (P2)	15 NO'S.	22 NO'S.
6	COMM. PODIUM (P3)	50 NO'S.	24 NO'S.
7	COMM. STILT		12 NO'S.
TOTAL PARKING...(A)		210 NO'S.	134 NO'S.

BLDG. NO. 3 , 4 & 5

SR. NO.	FLOOR LEVEL	CAR PARKING PROP.	TWO WHEELER PARKING PROP.
1	LOWER GROUND LEVEL	275 NO'S.	30 NO'S.
2	GROUND FLOOR	156 NO'S.	61 NO'S.
3	PODIUM (P1)	164 NO'S.	63 NO'S.
4	RESI. PODIUM (P2)	171 NO'S.	40 NO'S.
5	RESI. PODIUM (P3)	168 NO'S.	40 NO'S.
6	STILT LEVEL	02 NO'S.	-----
TOTAL PARKING...(B)		936 NO'S.	234 NO'S.
TOTAL PARKING PROVIDED (A+B)		1146 NO'S.	368 NO'S.
TOTAL PARKING REQUIRED		412 NO'S.	183 NO'S.
LOADING/ UNLOADING PARKING PROVIDED		05 NO'S.	

BUILT UP AREA DIAGRAM OF GR FLOOR PLAN
MULTI LEVEL CAR PARKING
SCALE - 1 : 200

BUILT UP AREA CALCULATION OF GR FLOOR PLAN

MULTI LEVEL CAR PARKING

BLOCK T						
A.	15.382	X 5.66	X 1	=	87.06 SQ.M.	
			TOTAL	=	87.06 SQ.M.	
LESS						
1.	9.32	X 2.41	X 1	=	22.46 SQ.M.	
2.	0.44	X 3.38	X 1	=	1.49 SQ.M.	
D1.	0.47	X 2.95	X 1	=	1.39 SQ.M.	
LI.	1.80	X 1.90	X 2	=	6.84 SQ.M.	
TOTAL AREA				=	32.18 SQ.M.	
B/UP AREA (87.06 SQ.M. - 32.18 SQ.M.)				=	54.88 SQ.M.	
AS PER P-LINE AREA				=	**54.89 SQ.M.**	

BUILT UP AREA DIAGRAM OF SECURITY CABIN
SCALE - 1 : 200

BUILT UP AREA CALCULATION OF SECURITY CABIN

BLOCK SC					
A.	10.70 X 9.95	X 1	=	106.46 SQ.M.	
		TOTAL	=	106.46 SQ.M.	
AS PER P-LINE AREA			=	106.46 SQ.M.	

6 SQ.M. BUILT UP AREA ALLOWED FREE OF FSI AS PER REG. NO. 6.8 (i)
B/UP AREA OF SECURITY CABIN = 106.46 - 6.00 SQ.M.
= **100.46 SQ.M.**

6.00M WIDE DRIVEWAY
MULTI LEVEL CAR PARKING
GROUND FLOOR PLAN
SCALE - 1 : 200

MULTILEVEL CAR PARKING

SR. NO.	FLOOR LEVEL	CAR PARKING PROP.	TWO WHEELER PARKING PROP.
1	GROUND FLOOR	13 NO'S.	140 NO'S.

GROUND FLOOR PLAN OF SECURITY CABIN
SCALE - 1 : 100

20% FSI PROVISION FOR I TO R REQUIREMENT :

a.	TOTAL BUILT-UP AREA	= 48270.29 SQ.M.
b.	PROPOSED COMMERCIAL BUILT-UP	= 12087.96 SQ.M.
c.	EXISTING BUILT-UP AREA	= 12679.81 SQ.M.
d.	BALANCE AREA (a - b - c)	= 23502.52 SQ.M.
e.	REQUIRED 20% OF 23502.52 SQ.M.	= 4700.50 SQ.M.
f.	**PROVIDED = 4723.20 SQ.M.**	

PARKING STATEMENT [BLDG.NO.2 (COMM.), BLDG. - 3, 4, & 5.]

AREA OF FLAT	NO. OF FLATS	CAR PARKING REQD.	SCOOTER PARKING REQD.
BELOW 30 M2	NIL	NIL	(-- / 2) X 2 = -- NO'S
30 M2 TO 40 M2	NIL	-- / 2 = -- NO'S.	(-- / 2) X 2 = -- NO'S.
40 M2 TO 80 M2	184 NO'S.	184 / 2 = 92 NO'S.	(184 / 2)X2 = 184 NO'S
80 M2 TO 150 M2	64 NO'S.	64 X 1 = 64 NO'S.	(64 / 1) X 1 = 64 NO'S
ABOVE 150 M2	NIL	-- X 2 = -- NO'S.	-- X 3 = -- NOS.
PARKING REQD		156 NO'S.	248 NO'S.
ADD FOR VISITORS 05%		08 NO'S.	12 NO'S.
BLDG.NO.2 (COMM.) SHOP - (2 CAR PARKING FOR EVERY 100M2. CARPET AREA) (6 SCOOTER PARKING FOR EVERY 100M2 CARPET AREA)		(1355.51 /100)X 2 = 27 NOS. (1355.51 /100)X 6 = 81 NOS.	
OFFICE - (3 CAR PARKING FOR EVERY 200M2. CARPET AREA) (11 SCOOTER PARKING FOR EVERY 200M2 CARPET AREA)		(7983.03 /200)X 3 = 120 NOS. (7983.03 /200)X 11 = 439 NOS.	
TOTAL PARKING REQD. (AS PER UDCPR)		311 NO'S.	780 NO'S.
OUT OF 780 SCOOTERS, 600 SCOOTERS ARE CONVERTED IN CAR PARKING (AS PER REG. NO. 8.1.1. V.) I.E. 600/6 = 100 NO'S. TOTAL PARKING REQD.		= 311 + 100 NO'S. = 411 NO'S.	= 780 - 600 NO'S. = 180 NO'S
50% EXTRA PARKING PERMISSIBLE (AS PER REG. NO. 8.2.1 (v))		= 50% OF 411 NO'S. = 206 NO'S	-----
TOTAL PARKING PERMISSIBLE		= 411 + 206 NO'S. = 617 NO'S.	180 NO'S.
TOTAL PARKING PROVIDED [AS PER REG. NO. 8.2.1 (v) (ii)]		1146 NO'S.	368 NO'S.
LOADING UNLOADING SPACES [AS PER REG. NO. 8.1.1 (viii)] (1 PARKING FOR EACH 1000M2. CARPET AREA) **SUBJECT TO MAXIMUM REQUIREMENT OF 4 FOR OFFICE BUILDING**		(9338.54 /1000)X 1 = 09 NOS.	

FLATS RESERVED AS PER I TO R

BLDG. NO.	FLOOR	FLAT NO.	B/UP AREA
BLDG. NO.-3	1ST, 3RD TO 6TH, 8TH TO 11TH, 13TH TO 16TH,18TH TO 21ST, 23RD TO 26TH, 28TH, TO 31ST, 33RD TO 36TH & 38TH TO 40TH FLR.	101, 301 TO 601, 801 TO 1101, 1301 TO 1601,1801 TO 2101, 2301 TO 2601, 2801 TO 3101, 3301 TO 3601 & 3801 TO 4001.	49.96 SQ.M. X 32 FLATS = 1598.72 SQ.M.
		102, 302 TO 602, 802 TO 1102, 1302 TO 1602,1802 TO 2102, 2302 TO 2602, 2802 TO 3102, 3302 TO 3602 & 3802 TO 4002	49.96 SQ.M. X 32 FLATS = 1598.72 SQ.M.
TOTAL FOR BLDG. NO. -3		TOTAL NO. OF FLATS = 32 + 32 FLATS = 64 NOS.	= 1598.72 + 1598.72 = **3197.44 SQ.M.**
BLDG. NO.-3	1ST TO 8TH	103A TO 803A	45.98 SQ.M. X 8 FLATS = 367.84 SQ.M.
	1ST TO 8TH	103B TO 803B	49.38 SQ.M. X 8 FLATS = 395.04 SQ.M.
	1ST TO 8TH	106A TO 806A	49.38 SQ.M. X 8 FLATS = 395.04 SQ.M.
	1ST TO 8TH	106B TO 806B	45.98 SQ.M. X 8 FLATS = 367.84 SQ.M.
TOTAL FOR BLDG. NO. -3		TOTAL NO. OF FLATS = 8 + 8 + 8 + 8 FLATS = 32 NOS.	= 367.84 + 395.04 + 395.04 + 367.84 = **1525.76 SQ.M.**

TOTAL FOR BLDG. NO. -3 + 4
TOTAL FLAT = 64 + 32 = **96 NOS.**
TOTAL BUILT-UP AREA= 3197.44 + 1525.76 = **4723.20 SQ.M.**

PROPOSED BLDG.NO.2 (COMM.), BLDG. NO. - 3, 4 & 5

PROPOSED COMMERCIAL & RESIDENTIAL DEVELOPMENT ON INDUSTRIAL PLOT BEARING S.NO. 146/1, 149/3, 154/3, 412/1, 414/1/C/1, 414/1/C/2 VILLAGE : MAJIWADA, THANE. | Drawing Sheet No. 3/20

CONTENT OF SHEET
PLOT AREA DIAG & CALCULATION.
SECURITY CABIN DIAG & CALCULATION.
PARKING STATEMENT (EXISTING & PROPOSED)
MULTILEVEL CAR PARKING
GROUND FLOOR PLAN, AREA DIAG & CALCULATION.
SECURITY CABIN DIAG & CALCULATION.

STAMP OF APPROVAL OF PLANS:

Plans are approved Subject to conditions
Prescribed in Permit No. VP/SK/01/32/23 (2007/87)
TMC/TD-DP/TP/ 1445/23 Dated. 1/8/2023

Deputy Engineer (TDD) — Executive Engineer (TDD)
Thane Municipal Corporation
The City of Thane

सावधान
"मंजूर नकाशानुसार बांधकाम न करणे तसेच विकास नियंत्रण नियमावलीनुसार आवश्यक त्या परवानग्या न घेता बांधकाम वापर करणे, महाराष्ट्र प्रादेशिक ने नगर रचना अधिनियम,१९६६ कलम ५२ अनुसार दंडात्मक गुन्हा आहे. त्यासाठी जास्तीत जास्त ३ वर्षे कैद पे रु १,०००/- पेक्षा दंड होऊ शकतो"

Owner's Declaration -
I/We undersigned hereby confirm that I/We would abide by plans approved by Authority / Collector. I/We would execute the structure as per approved plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site.

For Fermenta Biotech Limited,
P.O.A. Holder thru,
Mextech Property Developers LLP thru,
Rajesh Patel
2403-"A" Wing, Marathon Futurex,
Mafatlal Mill Compound,
NM Joshi Marg, Lower Parel,
Mumbai - 400013

Owner (s) name and signature

Architect/ Licensed Engineer/ Supervisor name and signature

SUVARNA GHOSH
ARCHITECT & INT. DESIGNERS
301, ARIHANT, AGYARI LANE,
JAMLI NAKA, THANE (W).
TEL :- 2540 6310

Job No.	Dwg No.	Scale	Drawn by	Checked by	Date	Registration No. Of Architect/License no.
		AS SHOWN	G.S.		16.03.2023	CA/91/14324

C:\plan\temp data\Office Work\Fermenta Biotech Limited\4. MUNICIPAL SANCTION DRAWG. FS NW REVISED MINCIPAL CPC BLDG. NO. 1 FLOOR PLAN 19-07-2023.txt, REVISED MUNICIPAL CTO BLDG. NO. 1 FLOOR PLAN (FOR BASIC) RES FSI(2016) _18-07-2023.dwg