

CONTENTS OF SHEET

2ND PODIUM FLOOR PLAN WITH BUILT UP AREA LINE DIAGRAM & CALCULATION & PODIUM AREA LINE DIAGRAM & CALCULATION ETC.

STAMP OF APPROVAL OF PLAN


साधधान
 "मंत्रुत मज्झसुत्तार वीथिखमम म चरमो तवेध
 पिकाम विपेयम विपभाक्कीनुत्तर आधरथक म्म
 पत्थममम म पेत्त वीथिखमम वारम वरम, मरुत्तपु
 प्रवेदिक्क म मरुत्त त्थमम अविचिदमम पेत्थम ५२
 अनुत्तर दम्मममम मुत्ता अरुत्त, त्थमममि ज्ञास्सीत्त
 ममम ३ वी वेत्त व म ५०००/- वरुत्त त्थमम अरुत्तम

PARKING AREA CALCULATION OF 2ND FLOOR PLAIN				
A	B	C	D	E
A	89.25	A	81.85	7223.26
			TOTAL	7223.26
DEDUCTIONS				
1	5.65	X	7.70	43
2	9.05	X	47.20	387.04
3	1.98	X	13.60	26.93
4	15.20	X	9.15	123.88
5	33.00	X	10.70	362.73
6	23.25	X	8.05	191.90
7	3.35	X	2.85	9.56
8	4.45	X	2.15	18.93
9	9.30	X	16.85	175.31
			TOTAL DEDUCTIONS - (a)	1435.64
DUCT AREA CALCULATIONS				
D1	1.15	X	0.15	4
D2	2.15	X	0.70	2
D3	0.80	X	2.90	2
			TOTAL DEDUCTIONS - (c)	18.66
NET AREA				
			7223.26 - (a)	5787.62
			5787.62 - (c)	5768.96
NET AREA OF 2ND FLOOR PLAIN				
			5768.96	5768.96

B UP AREA CALCULATION OF 2ND POOLUUM FLOOR (COMMON)						
A	83.19	X	31.85	= 2649.65		
B	13.35	X	18.85	= 2517.75		
TOTAL				2964.91		
DEDUCTIONS:						
1	13.35	X	11.80	= 157.50		
2	13.35	X	2.40	= 32.04		
3	15.90	X	2.45	= 38.97		
4	15.90	X	18.85	= 2998.15		
5	33.20	X	21.15	= 702.24		
6	15.30	X	18.80	= 286.74		
7	15.30	X	4.85	= 73.99		
8	15.30	X	7.70	= 117.81		
9	1.10	X	11.80	= 12.98		
TOTAL DEDUCTIONS (-)				1421.33		
NET AREA CALCULATIONS:						
B1	5.45	X	5.35	X	2	= 23.14
D1	0.85	X	2.75	X	4	= 9.34
E1	0.85	X	2.75	X	4	= 9.34
F1	2.80	X	1.21	X	2	= 6.82
G1	5.80	X	0.75	=	7.05	
H1	5.80	X	0.50	=	2.90	
D2	0.85	X	2.25	=	1.91	
TOTAL DUST AREA (+)				94.62		
LET AREA CALCULATIONS:						
L1	2.00	X	1.80	X	4	= 14.40
TOTAL LET AREA (+)				14.40		
TOTAL AREA (+)				3064.13		
TOTAL PROPOSED UP AREA OF 2ND POOLUUM FLOOR						
LOAF						
TOTAL UP AREA PER FLOOR						

AREA LINE DIAGRAM OF 2ND PODIUM FLOOR (COMM)
SCALE: 1/200

AREA LINE DIAGRAM OF 2ND PODIUM FLOOR PLAN
SCALE - 1/200



2ND PODIUM FLOOR PLAN
SCALE - 1:200

DOOR WINDOW SCHEDULE

TYPE	SIZE	DESCRIPTION
D	1.05 X 2.10	T.W. FRAMED WITH PANNELLED DOOR
D1	0.90 X 2.10	T.W. FRAMED WITH PANNELLED DOOR
D2	0.75 X 2.00	T.W. FRAMED WITH PANNELLED DOOR
RS	AS PER SITE X 40	ROLLING SHUTTER
W	2.20 X 2.10	T.W. FRAMED WITH GLAZE WINDOW
W1	1.50 X 1.20	T.W. FRAMED WITH GLAZE WINDOW
W2	1.20 X 1.20	T.W. FRAMED WITH GLAZE WINDOW
W3	1.00 X 1.20	T.W. FRAMED WITH GLAZE WINDOW
W4	2.20 X 1.20	T.W. FRAMED WITH GLAZE WINDOW
V	0.60 X 0.90	T.W. FRAMED WITH LOUVERS

DESCRIPTION OF PROPOSAL

PROPOSED DEVELOPMENT UNDER ACCOMMODATION RESERVATION
POLICY ON PLOT BEARING S.NO- 46, 47, 48, 49, 50/1, 51A/1, 67/1, 115/1,
116, 117/A/1, 118/A/1, 119/A,120A, 121, 122 AT VILLAGE MUMBRA,THANE

NAME AND ADDRESS OF OWNER/ P.O.A.H.

YES REALTY
S.NO-55,CENTRAL EMPIRE, OPP CENTRAL HEIGHTS, NEXT TO KAUSA TMC
STADIUM KAUSA MUMBARA, DISTRICT THANE-400612

NAROTTAM NAGAR CO. OPERATIVE HOUSING SOCIETY

SIGNATURE OF OWNER / P.O.A.H. SIGNATURE OF ARCHITECT

ARCHITECTS



2ND FLOOR, NAKSHATRA, A WING,
NEAR TMC, ALMEIDA ROAD,
PANCHPAKHADI, THANE (W). 400 602
PHONE - 2537 8701, TELEFAX - 2536 470
E MAIL - saakaarachitects@yahoo.co