REHAB BLDG. (WING - B) 06/06

NOTE :- ALL WALL THICKNESS 0.15 MT. & LIFT WALL THICKNESS 0.25 MT.

FORM - II

CONTENT OF SHEET

* 19TH FLOOR PLAN & BUILT UPA AREA DAIGRAM & CALCULATION
* SECTION C-C. * TERRACE FLOOR PLAN.

CERTIFICATE OF AREA

CERTIFIED THAT I HAVE SURVEYED THE PLOT UNDER REFERENCE ON AND THAT THE DIMENSIONS OF SIDES, ETC. OF PLOT STATED ON THE PLAN ARE AS MEASURED ON SITE AND THE AREA SO WORKED OUT IS .....SQUAREMETERS AND TALLIES WITH THE AREA STATED IN THE DOCUMENT OF OWNERSHIP/TOWN PLANNING SCHEME RECORDS.

SIGNATURE OF LICENSED SURVEYOR/ARCHITECT/ ENGINEER/ STRUCTURAL ENGINEER/ SUPERVISOR

ARCHITECT DESCRIPTION OF PROPOSAL & PROPERTY

PROPOSED BUILDING ON PLOT BEARING C.T.S. NO. 396, 396 / 1 TO 59, PANJABI CHAWAL, SUBHASH ROAD, JANTA MARKET, BHANDUP (W) MUMBAI 400 078.

NAME OF SOCIETY

AMRUT SRUSTHI CO-OP HOUSING SOCIETY (LTD)

NAME & SIGN. OF OWNER


M/S JAYSHREE BUILDERS

STAMP OF DATE OF RECEIPT OF PLANS	STAMP OF DATE OF APPROVAL OF PLANS

REVISION	DATE	DESCRIPTION	SIGNATURE

DRN.BY	
CHK.BY	
SCALE	AS SHOWN
NORTH	


S.S. ASSOCIATES
ARCHITECT AND INT. DESIGNER
1103, 11TH FLOOR, OPAL SQUARE,
NEAR MIDC, WAGLE ESTATE,
THANE (W). 022 20813369



SECTION C-C ("B" WING)


SCALE= 1:100

(REHAB "B" WING)




TERRACE FLOOR PLAN ("B" WING)

SCALE= 1:100



19TH FLOOR PLAN ("B" WING)

SCALE= 1:100



BUILT UP AREA LINE DIAGRAM 19TH FLOOR "B" WING

SCALE= 1:100

BUILT UP AREA CALCULATION

19TH FLOOR						
A	25.65	X	20.35	X 1 NO	=	521.98 SQ.MT.
				TOTAL ADDITION	=	521.98 SQ.MT. X

DEDUCTIONS

1	0.85	X	15.15	X 1 NO	=	12.88 SQ.MT.
2	1.80	X	13.90	X 1 NO	=	25.02 SQ.MT.
3	2.45	X	6.65	X 1 NO	=	16.29 SQ.MT.
4	1.10	X	1.45	X 1 NO	=	1.60 SQ.MT.
5	1.10	X	1.05	X 1 NO	=	1.16 SQ.MT.
6	1.55	X	1.10	X 1 NO	=	1.71 SQ.MT.
7	0.85	X	1.10	X 1 NO	=	0.94 SQ.MT.
8	3.06	X	3.15	X 1 NO	=	9.64 SQ.MT.
9	23.00	X	6.30	X 1 NO	=	144.90 SQ.MT.
10	1.80	X	6.85	X 1 NO	=	11.81 SQ.MT.
11	0.85	X	5.20	X 1 NO	=	4.42 SQ.MT.
				TOTAL DEDUCTION	=	230.17 SQ.MT. Y1
				TOTAL BUILT UP AREA (X-Y1)	=	291.81 SQ.MT. X1

STAIRCASE AREA CALCULATION

19TH FLOOR						
ST1	5.31	X	3.45	X 1 NO	=	18.32 SQ.MT.
ST2	1.50	X	3.30	X 1 NO	=	4.95 SQ.MT.
ST3	2.43	X	2.66	X 1 NO	=	5.46 SQ.MT.
ST4	2.26	X	2.58	X 1 NO	=	5.83 SQ.MT.
ST5	2.48	X	2.60	X 1 NO	=	5.96 SQ.MT.
TOTAL STAIRCASE AREA PER FL (19TH FLOOR)					=	40.52 SQ.MT. Y2

FUNGIBLE AREA CALCULATION

19TH FLOOR						
F1	2.26	X	0.87	X 1 NO	=	1.97 SQ.MT.
F2	2.43	X	0.79	X 1 NO	=	1.92 SQ.MT.
TOTAL FUNGIBLE AREA PER FL (19TH FLOOR)					=	3.89 SQ.MT. Y3

NET BUILT UP AREA (PTC AREA) (X1 -(Y2+Y3))	=	247.40 SQ.MT.

This cancels Approval to the Previous Plans sanctioned under no. .....
Dated.....

Approved Subject to the condition Mentioned in this office permisson Letter no.
Dt. 17 JUL 2024
Executive Engineer
Slum Rehabilitation Authority