



BLOCK PLAN
SCALE - 1:500



LOCATOIN PLAN
SCALE - 1:4000



PLOT AREA DIAGRAM
SCALE - 1:500

PLOT AREA CALCULATION								
1	1/2	x	14.80	x	1.15	x 1 NO	=	8.51 SQ.MT.
2	1/2	x	15.20	x	4.09	x 1 NO	=	31.08 SQ.MT.
3	1/2	x	15.20	x	3.30	x 1 NO	=	25.08 SQ.MT.
4	1/2	x	15.38	x	3.52	x 1 NO	=	27.07 SQ.MT.
5	1/2	x	18.06	x	5.14	x 1 NO	=	46.41 SQ.MT.
6	1/2	x	23.01	x	15.10	x 1 NO	=	173.73 SQ.MT.
7	1/2	x	20.01	x	4.76	x 1 NO	=	47.62 SQ.MT.
8	1/2	x	16.65	x	6.03	x 1 NO	=	50.20 SQ.MT.
						TOTAL ADDITION	=	409.70 SQ.MT. X

SUMMARY OF BUILT UP AREA


FLOOR	COMMERCIAL B.U.A. PER FLR	RESIDENTIAL B.U.A. PER FLR	TOTAL B.U.A. PER FLR
GROUND FLOOR	68.98 SQ.MT.	NIL	68.98 SQ.MT.
1ST FLOOR	68.98 SQ.MT.	1.31 SQ.MT.	70.29 SQ.MT.
2ND FLOOR	NIL	31.15 SQ.MT.	31.15 SQ.MT.
3RD FLOOR	NIL	132.82 SQ.MT.	132.82 SQ.MT.
4TH FLOOR	NIL	135.98 SQ.MT.	135.98 SQ.MT.
5TH FLOOR	NIL	129.94 SQ.MT.	129.94 SQ.MT.
6TH FLOOR	NIL	129.94 SQ.MT.	129.94 SQ.MT.
7TH FLOOR	NIL	129.94 SQ.MT.	129.94 SQ.MT.
COLUMN COUNT IN F.S.I.	NIL	0.60 SQ.MT.	0.60 SQ.MT.
TOTAL	137.96 SQ.MT.	691.68 SQ.MT.	829.64 SQ.MT.

STAIR & LIFT LOBBY PREMIUM AREA STATEMENT


FLOOR	TOTAL STAIR & LIFT LOBBY AREA PER FLOOR
GROUND FLOOR	NIL
1ST FLOOR	24.32 SQ.MT.
2ND FLOOR	24.32 SQ.MT.
3RD FLOOR	24.32 SQ.MT.
4TH FLOOR	24.32 SQ.MT.
5TH FLOOR	24.32 SQ.MT.
6TH FLOOR	24.32 SQ.MT.
7TH FLOOR	24.32 SQ.MT.
TOTAL	170.24 SQ.MT.

TENEMENT STATEMENT


FLOOR	PER FLR TENEMENT
GROUND FLOOR	NIL
1ST FLOOR	NIL
2ND FLOOR	1 NOS.
3RD FLOOR	2 NOS.
4TH FLOOR	2 NOS.
5TH FLOOR	2 NOS.
6TH FLOOR	2 NOS.
7TH FLOOR	2 NOS.
TOTAL	11 NOS.




GROUND FLOOR PLAN
SCALE - 1:100



1ST FLOOR PLAN
SCALE - 1:100




PIT LVL. FLOOR PLAN
SCALE - 1:100



GROUND & 1ST FLOOR AREA DIAGRAM (COMERCIAL)
SCALE - 1:100

BUILT UP AREA CALCULATION

GROUND FLOOR (COMMERCIAL)								
A	7.75	X	8.90	X	1 NO	=	68.98	SQ.MT.
					TOTAL ADDITION	=	68.98	SQ.MT. X



1ST FLOOR AREA DIAGRAM (RESIDENTIAL)
SCALE - 1:100

BUILT UP AREA CALCULATION

1ST FLOOR								
A	8.90	X	6.95	X	1 NO	=	61.86	SQ.MT.
					TOTAL ADDITION	=	61.86	SQ.MT. X

DEDUCTIONS

1	0.60	X	3.45	X	1 NO	=	2.07	SQ.MT.
2	1.25	X	1.70	X	1 NO	=	2.13	SQ.MT.
ST	1.25	X	1.75	X	1 NO	=	2.19	SQ.MT.
					TOTAL DEDUCTION	=	6.39	SQ.MT. Y1
TOTAL BUILT UP AREA [X - Y1]						=	55.47	SQ.MT. X1

STAIRCASE & LIFT AREA

1ST FLOOR								
S1	7.05	X	3.45	X	1 NO	=	24.32	SQ.MT.
TOTAL STAIR, & LIFT AREA PER FL, (TYPICAL FLOOR)						=	24.32	SQ.MT. Y2

FITNESS CENTER AREA CALCULATION

1ST FLOOR								
F1	2.91	X	2.45	X	1 NO	=	7.13	SQ.MT.
F2	2.60	X	1.05	X	1 NO	=	2.73	SQ.MT.
TOTAL WELFARE CENTER AREA (TYPICAL FLOOR)						=	9.86	SQ.MT. Y3

SOCIETY OFFICE AREA CALCULATION

1ST FLOOR								
SO1	5.05	X	3.50	X	1 NO	=	17.68	SQ.MT.
SO2	0.94	X	2.45	X	1 NO	=	2.30	SQ.MT.
TOTAL SOCIETY OFFICE AREA						=	19.98	SQ.MT. Y4

NET BUILT UP AREA [X1 - (Y2+Y3+Y4)]	=	1.31 SQ.MT.

FUNGIBLE COMPENSATORY PREMIUM STATEMENT

SR.	PARTICULARS	SQ.MT.
1	B.U.A. PERMISSIBLE	614.55
2	B.U.A. PROPOSED	614.55
	(a) RESIDENTIAL	512.36
	(b) COMMERCIAL	102.19
3	PERMISSIBLE FUNGIBLE FSI	
	(a) RESIDENTIAL (2a X 35%)	179.32
	COMMERCIAL (2b X35%)	35.77
4	PROPOSED FUNGIBLE FSI	
	(a) RESIDENTIAL (2a X 35%)	179.32
	(b) COMMERCIAL (2b X 35%)	35.77
5	EXISTING BUILT UP AREA	
	(i) RESIDENTIAL	176.76
	(ii) COMMERCIAL	45.23
6	FUNGIBLE FSI	
A	(i) WITHOUT CHARGING PREMIUM RESIDENTIAL (5i X 35%)	22.85
	(ii) WITHOUT CHARGING PREMIUM COMMERCIAL (5ii X 35%)	15.83
B	(i) BY CHARGING PREMIUM RESIDENTIAL (4a-6A i)	156.47
	(ii) BY CHARGING PREMIUM COMMERCIAL (4b-6A ii)	19.94

NOTE : ADDITIONAL PARKING AS PER CONCESSION GRANTED.

CAR PARKING STATEMENT FOR SHOP

CAR PARKING FOR SHOP					
PROPOSED AREA	=			137.96	SQ.MT.
UPTO 800 SQ.MT.	=	1/FOR 40 SQ.MT.	=	3.45	NOS.
ABOVE 800 SQ.MT.	=	1/FOR 80 SQ.MT.	=	0.00	NIL
TOTAL			=	3.45	NOS.
ADD 10% VISITORS PARKING			=	0.35	NOS.
MINIMUM VISITORS PARKING			=	2.00	NOS.
TOTAL COMMERCIAL PARKING REQUIRED (3.45 + 2.00)			=	5.45	NOS.


CAR PARKING STATEMENT

CARPET AREA IN SQ.M.	NOS. OF TENEMENTS	PARKING PERMISSIBLE AS PER D.C.R.	PARKING REQUIRED
UP TO 45	01.00 NO.	1 PARKING / 4 TENANTS	0.25 NOS.
BETWEEN 45 & 60	NIL	1 PARKING / 2 TENANTS	NIL
BETWEEN 60 & 90	10.00 NOS.	1 PARKING / 1 TENANTS	10.00 NOS.
90 ABOVE	NIL	2 PARKING / 1 TENANTS	NIL
TOTAL	11.00 NOS.		10.25 NOS.
ADD 10% VISITORS PARKING			1.02 NOS.
TOTAL RESIDENTIAL PARKING REQUIRED			11.27 NOS.

TOTAL PARKING REQUIRED (COM. + RES.) (5.45 + 11.27 = 16.72) SAY	=	17.00	NOS.
TOTAL PARKING PROVIDED	=	24.00	NOS.
SMALL PARKING	=	01.00	NO.
BIG PARKING	=	23.00	NOS.

CARPET AREA STATEMENT

FLOOR	FLAT NO. 01	FLAT NO. 02
GROUND FLOOR	NIL	NIL
1ST FLOOR	NIL	NIL
2ND FLOOR	27.67 SQ.MT.	NIL
3RD FLOOR	60.36 SQ.MT.	60.88 SQ.MT.
4TH FLOOR	60.36 SQ.MT.	61.42 SQ.MT.
5TH FLOOR	60.36 SQ.MT.	60.36 SQ.MT.
6TH FLOOR	60.36 SQ.MT.	60.36 SQ.MT.
7TH FLOOR	60.36 SQ.MT.	60.36 SQ.MT.



INDEX	
PROPOSED WORK	
ROAD	

THIS PLAN IS DIGITALLY SIGN AND PHYSICAL SING NOT REQUIRED

APPROVED SUBJECT TO CONDITIONS MENTIONED

THIS OFFICE LETTER UNDER NO.P-14484 / 2023 / (179) / H / W WARD / FP DT. 21/04/2023

SHAHBAJ ALIMODDIN PEERZADE	SHAIKH ASIF MUSA	Vijay Shankarrao Tawde
S.E.(B.P.),K / WS2	A.E.B.P. (H) WARD	EXECUTIVE ENGINEER, BUILDING PROPOSAL(W.S)-I 'H' WARD

FILE NO :- P-14484 / 2023 / (179) / H / W WARD / FP 1/3

PROFORMA 'A'

A	AREA STATEMENT	SQ.MT.
1	AREA OF THE PLOT	409.70
2	DEDUCTION FOR	
	(a) ROAD SET BACK AREA	0.00
	(b) PROPOSED ROAD	-
	(c) ANY RESERVATION	-
	TOTAL [2(a)+(b)+(c)+(d)+(e)]	409.70
3	BALANCE AREA OF PLOT (1 - 2)	409.70
	(a) 15% RECREATIONAL OPEN SPACE	
	(b) 10% AMENITY SPACE	
4	NET PLOT AREA	409.70
5	F.S.I. PERMISSIBLE	ONE
6	TOTAL AREA (4x5) BASE FSI	409.70
7	ADDITIONS FOR F.S.I PURPOSE (REG. 30 TABLE 12- DCPR-2034)	
	(A) FOR SET-BACK (200%) [DCR 32(1)]	0.00
	(B) FOR D.P. ROAD/ RESERVATION	-
	(C) OTHER FSI [DCR 33]:	-
	(D) EXTERNAL 100% SLUM TDR CLAIMED EARLIER PERMISSIBLE AS PER REG.32(8) OF DCPR-2034	-
	(i) SLUM TDR (MIN. 20% - MAX. 50%)	-
	(ii) RESERVATION TDR / ADD.FSI (MAX 50%)	-
	(E) GOVERNMENT FSI (0.50) PERMISSIBLE	204.85
	TOTAL [7]	204.85
8	PERMISSIBLE FLOOR AREA [6+7]	614.55
9	TOTAL BUILT UP AREA (EXISTING + PROPOSED)	
	(A) EXISTING BUILT UP AREA	-
	(B) PROPOSED BUILT UP AREA	
	(a) RESIDENTIAL BUILT UP AREA	512.36
	(b) NON - RESIDENTIAL BUILT UP AREA	102.19
	TOTAL BUILT-UP PROPOSED (9)	614.55
10	F.S.I. CONSUMED ON NET HOLDING (9/4)	1.50
B	DETAILS OF FUNGIBLE FSI AVAILED AS PER DCR 31(3)	
1	FUNGIBLE B.U.A. COMPONENT PROPOSED VIDE DCR 31 (3) FOR PURELY RESIDENTIAL = OR < (9a X 0.35)	179.32
2	FUNGIBLE B.U.A. COMPONENT PROPOSED VIDE DCR 31 (3) FOR PURELY NON-RESIDENTIAL = OR < (9b X 0.35)	35.77
3	TOTAL FUNGIBLE B.U.A. VIDE DCR 31 (3) = (B.1 + B.2)	215.09
4	TOTAL GROSS BUILT -UP AREA PROPOSED (9 + B)	829.64
C	TENEMENT STATEMENT	
	(i) PROPOSED AREA (ITEM B-4 ABOVE)	829.64
	(ii) LESS DEDUCTION FOR NON-RESI. AREA (shops etc.)	137.96
	(iii) AREA AVAILABLE FOR TENEMENTS (i - ii)	691.68
	(iv) TENEMENTS PERMISSIBLE (450 / HECTOR)	31.12
	(v) TENEMENTS PROPOSED	11.00
	(vi) TENEMENTS EXISTING	-
	TOTAL TENEMENTS ON THE PLOT	-
D	PARKING STATEMENT	
	(i) PARKING REQUIRED BY REGULATIONS FOR	
	CAR	AS PER STATEMENT
	SCOOTER / MOTOR CYCLE	
	OUTSIDERS (VISITORS)	
	(ii) COVERED GARAGES PERMISSIBLE	
	(iii) COVERED GARAGES PROVIDED	
	CAR	
	SCOOTER / MOTOR CYCLE	
	OUTSIDERS (VISITORS)	
	(iv) TOTAL PARKING PROVIDED	
E	TRANSPORT VEHICLES PARKING	
	(i) SPACES FOR TRANSPORT VEHICLES PARKING REQUIRED BY REGULATIONS	
	(ii) TOTAL NO. OF TRANSPORT VEHICLES PARKING SPACES PROVIDED	

CONTENTS OF SHEET

BLOCK & LOCATION,STILT FLOOR PLAN,PLOT AREA DIAGRAM
BUILT UP AREA STATEMENT,CARPET AREA STATEMENT
FUNGIBLE AREA STATEMENT,CAR PARKING STATEMENT
STILT FLOOR & BASEMENT FLOOR PLAN

DESCRIPTION OF PROPOSAL & PROPERTY:

PROPOSED REDEVELOPMENT OF BUILDING ON PLOT BEARING C.T.S. NO. E/375 OF VILLAGE BANDRA-F, F.P. NO. 179 TPS BANDRA III AT 18.30 MTR. WATERFIELD ROAD, BANDRA (WEST),MUMBAI IN H/W WARD.

F CERTIFICATE OF AREA

CERTIFIED THAT I HAVE SURVEYED THE PLOT UNDER REFERENCE AND THAT THE DIMENSIONS OF THE SIDES, ETC. OF THE PLOT STATED ON THE PLAN ARE AS MEASURED ON SITE AND THE AREA SO WORKED OUT IS 409.70 SQ. MTS. AND TALLIES WITH THE AREA STATED IN THE DOCUMENT OF OWNERSHIP \ PROPERTY REGISTER CARD

Yomesh Narayan Rao — Digitally signed by Yomesh Narayan Rao Date: 2023.04.12 12:00:56 +05'30'

SIGNATURE OF LICENSED SURVEYOR

NOTES

BOUNDARY OF PLOT SHOWN THICK BLACK
PROPOSED WORK SHOWN RED WASH
DRAINAGE LINE SHOWN RED DOTTED
RECREATION GROUND SHOWN GREEN WASH
EX. STRUCTURES TO BE RETAINED SHOWN HATCHED BLACK
EX. STRUCTURES TO BE DEMOLISHED SHOWN HATCHED YELLOW
SETBACK AREA SHOWN BURNT SIENNA
ALL DIMENSION IN METERS

NAME, ADDRESS OF OWNER	SIGNATURE OF OWNER
RUSSELL C DREGO. CA TO OWNERS 602 EKEN HEIGHTS CORNER OF 21ST AND 33RD RAOD BANDRA WEST MUMBAI 400050	RUSSELL DREGO — Digitally signed by RUSSELL DREGO Date: 2023.04.12 11:58:05 +05'30'

DRAWING No.	SCALE	JOB NO.	DATE	DRAWN BY	CHECK BY
1	AS SHOWN	PR-	12-04-2023	MANGESH.B	SANJAY B.

NAME, ADDRESS & SIGNATURE OF LICENSED SURVEYOR:-

Yomesh Narayan Rao — Digitally signed by Yomesh Narayan Rao Date: 2023.04.12 12:00:41 +05'30'

YOMESH RAO
LS/R-151
BE-CIVIL


yms CONSULTANTS LIMITED

202, SHREE-PRASAD HOUSE, PLOT NO 517, 35TH ROAD TPS III, OFF LINK ROAD, BANDRA (W), MUMBAI - 400 050.

FILE NO :- P-14484 / 2023 / (179) / H / W WARD / FP | 2/3

CONTENTS OF SHEET

3RD, 4TH, 5TH TO 7TH FLOOR PLAN.BUILT UP AREA CALCULATION



2ND FLOOR AREA DIAGRAM (RESIDENTIAL)

SCALE - 1:100

BUILT UP AREA CALCULATION

2ND FLOOR (RESIDENTIAL)								
A	8.90	X	6.95	X	1 NO	=	61.86	SQ.MT.
					TOTAL ADDITION	=	61.86	SQ.MT. X


DEDUCTIONS

1	0.60	X	3.45	X	1 NO	=	2.07	SQ.MT.
2	1.25	X	1.70	X	1 NO	=	2.13	SQ.MT.
ST	1.25	X	1.75	X	1 NO	=	2.19	SQ.MT.
					TOTAL DEDUCTION	=	6.39	SQ.MT. Y1
TOTAL BUILT UP AREA [X - Y1]						=	55.47	SQ.MT. X1

STAIRCASE & LIFT AREA

2ND FLOOR (RESIDENTIAL)								
S1	7.05	X	3.45	X	1 NO	=	24.32	SQ.MT.
TOTAL STAIR. & LIFT AREA PER FL. (1ST FLOOR)						=	24.32	SQ.MT. Y2

NET BUILT UP AREA [X1 - Y2]	=	31.15 SQ.MT.



3RD FLOOR AREA DIAGRAM

SCALE - 1:100

BUILT UP AREA CALCULATION

3RD FLOOR								
A	8.90	X	18.85	X	1 NO	=	167.77	SQ.MT.
					TOTAL ADDITION	=	167.77	SQ.MT. X


DEDUCTIONS

1	0.60	X	3.45	X	1 NO	=	2.07	SQ.MT.
2	5.30	X	0.80	X	1 NO	=	4.24	SQ.MT.
3	1.25	X	1.70	X	1 NO	=	2.13	SQ.MT.
ST	1.25	X	1.75	X	1 NO	=	2.19	SQ.MT.
					TOTAL DEDUCTION	=	10.63	SQ.MT. Y1
TOTAL BUILT UP AREA [X - Y1]						=	157.14	SQ.MT. X1

STAIRCASE & LIFT AREA

3RD FLOOR								
S1	7.05	X	3.45	X	1 NO	=	24.32	SQ.MT.
TOTAL STAIR. & LIFT AREA PER FL.						=	24.32	SQ.MT. Y2

NET BUILT UP AREA [X1 - Y2]	=	132.82 SQ.MT.



4TH AREA DIAGRAM

SCALE - 1:100

BUILT UP AREA CALCULATION

4TH FLOOR								
A	8.90	X	18.85	X	1 NO	=	167.77	SQ.MT.
					TOTAL ADDITION	=	167.77	SQ.MT. X


DEDUCTIONS

1	0.60	X	3.45	X	1 NO	=	2.07	SQ.MT.
2	1.35	X	0.80	X	1 NO	=	1.08	SQ.MT.
3	1.25	X	1.70	X	1 NO	=	2.13	SQ.MT.
ST	1.25	X	1.75	X	1 NO	=	2.19	SQ.MT.
					TOTAL DEDUCTION	=	7.47	SQ.MT. Y1
TOTAL BUILT UP AREA [X - Y1]						=	160.30	SQ.MT. X1

STAIRCASE & LIFT AREA

4TH FLOOR								
S1	7.05	X	3.45	X	1 NO	=	24.32	SQ.MT.
TOTAL STAIR. & LIFT AREA PER FL.						=	24.32	SQ.MT. Y2

NET BUILT UP AREA [X1 - Y2]	=	135.98 SQ.MT.



5TH TO 7TH AREA DIAGRAM

SCALE - 1:100

BUILT UP AREA CALCULATION

5TH TO 7TH FLOOR								
A	8.90	X	18.05	X	1 NO	=	160.65	SQ.MT.
					TOTAL ADDITION	=	160.65	SQ.MT. X


DEDUCTIONS

1	0.60	X	3.45	X	1 NO	=	2.07	SQ.MT.
2	1.25	X	1.70	X	1 NO	=	2.13	SQ.MT.
ST	1.25	X	1.75	X	1 NO	=	2.19	SQ.MT.
					TOTAL DEDUCTION	=	6.39	SQ.MT. Y1
TOTAL BUILT UP AREA [X - Y1]						=	154.26	SQ.MT. X1

STAIRCASE & LIFT AREA


5TH TO 7TH FLOOR								
S1	7.05	X	3.45	X	1 NO	=	24.32	SQ.MT.
TOTAL STAIR. & LIFT AREA PER FL. (5TH TO 7TH FL.)						=	24.32	SQ.MT. Y2

NET BUILT UP AREA [X1 - Y2]	=	129.94 SQ.MT.




2ND FLOOR PLAN

SCALE - 1:100




3RD FLOOR PLAN

SCALE - 1:100



4TH FLOOR PLAN

SCALE - 1:100



5TH TO 7TH FLOOR PLAN

SCALE - 1:100

THIS PLAN IS DIGITALLY SIGN AND PHYSICAL SING NOT REQUIRED

APPROVED SUBJECT TO CONDITIONS MENTIONED

THIS OFFICE LETTER UNDER NO.P-14484 / 2023 / (179) / H / W WARD / FP DT. 21/04/2023

SHAHBAJ ALIMODDIN PEERZADE	SHAIKH ASIF MUSA	Vijay Shankarrao Tawde
S.E.(B.P.),K / WS2	A.E.B.P. (H) WARD	EXECUTIVE ENGINEER, BUILDING PROPOSAL(W.S)-I 'H' WARD

DESCRIPTION OF PROPOSAL & PROPERTY:

PROPOSED REDEVELOPMENT OF BUILDING ON PLOT BEARING C.T.S. NO. E/375 OF VILLAGE BANDRA-E, F.P. NO. 179 TPS BANDRA III AT 18.30 MTR. WATERFIELD ROAD, BANDRA (WEST),MUMBAI IN H/W WARD.

NAME, ADDRESS OF OWNER	SIGNATURE OF OWNER
RUSSELL C DREGO. CA TO OWNERS 602 EKEN HEIGHTS CORNER OF 21ST AND 33RD RAOD BANDRA WEST MUMBAI 400050	RUSSELL DREGO Digitally signed by RUSSELL DREGO Date: 2023.04.12 11:58:27 +05'30'

DRAWING No.	SCALE	JOB NO.	DATE	DRAWN BY	CHECK BY
2	AS SHOWN	PR-	12-04-2023	MANGESH.B	SANJAY B.

NAME, ADDRESS & SIGNATURE OF LICENSED SURVEYOR:-

Yomesh Narayan Rao — Digitally signed by Yomesh Narayan Rao, Date: 2023.04.12 12:01:09 +05'30'

YOMESH RAO
LSR-151
BE-CIVIL

yms

202, SHREE-PRASAD HOUSE, PLOT NO 517, 35TH ROAD TPS III, OFF LINK ROAD, BANDRA (W), MUMBAI - 400 050.


INDEX

PROPOSED WORK

FILE NO :- P-14484 / 2023 / (179) / H / W WARD / FP	3/3


CONTENTS OF SHEET

8TH TO 10TH FLOOR PLAN.BUILT UP AREA
CALCULATION ,TERRACE FLOOR PLAN & SECTION AT A-A




TERRACE FLOOR PLAN

SCALE - 1:100




SECTION B-B

SCALE - 1:100




SECTION A-A

SCALE - 1:100



DETAILS SECTION OF SERVICE SLAB

SCALE : 1:50



DETAIL SECTION OF CHAJJA X-X

SCALE : 1:50

THIS PLAN IS DIGITALLY SIGN AND PHYSICAL SING NOT REQUIRED

APPROVED SUBJECT TO CONDITIONS MENTIONED
THIS OFFICE LETTER UNDER NO.P-14484 / 2023 / (179) / H / W WARD / FP DT. 21/04/2023

SHAHBAJ ALIMODDIN PEERZADE	SHAIKH ASIF MUSA	Vijay Shankarrao Tawde
S.E.(B.P.).K / WS2	A.E.B.P. (H) WARD	EXECUTIVE ENGINEER, BUILDING PROPOSAL(W.S).'H' WARD

DESCRIPTION OF PROPOSAL & PROPERTY:

PROPOSED REDEVELOPMENT OF BUILDING ON PLOT BEARING C.T.S. NO. F/375 OF VILLAGE BANDRA-F, F.P. NO. 179 TPS BANDRA III AT 18.30 MTR. WATERFIELD ROAD, BANDRA (WEST),MUMBAI IN H/W WARD.

NAME, ADDRESS OF OWNER	SIGNATURE OF OWNER
RUSSELL C DREGO. CA TO OWNERS 602 EKEN HEIGHTS CORNER OF 21ST AND 33RD RAOD BANDRA WEST MUMBAI 400050	RUSSEL L DREGO Digitally signed by RUSSELL DREGO Date: 2023.04.12 11:58:42 +05'30'

DRAWING No.	SCALE	JOB NO.	DATE	DRAWN BY	CHECK BY
3	AS SHOWN	PR-	12-04-2023	MANGESH.B	SANJAY B.

NAME, ADDRESS & SIGNATURE OF LICENSED SURVEYOR:-

Yomesh Narayan Rao
Digitally signed by Yomesh Narayan Rao
Date: 2023.04.12 12:01:23 +05'30'

YOMESH RAO
LSR-151
BE-CIVIL

INDEX
PROPOSED WORK

202, SHREE-PRASAD HOUSE, PLOT NO 517, 35TH ROAD TPS III,
OFF LINK ROAD, BANDRA (W), MUMBAI - 400 050.