



PROPOSED RESIDENTIAL LAYOUT PLAN IN SURVEY NO. 51, IN MAUZA- RENKAPUR, TAH. SAMUDRAPUR & DIST. WARDHA



AREA STATEMENT		
AREA UNDER SRY. NO. 51	---	25000.00 Sq.mtr.
AREA UNDER OPEN SPACE	---	2520.70 Sq.mtr.
AREA AMENITY PLOT NO. 119	---	1144.20 Sq.mtr.
AREA AMENITY PLOT NO. 120	---	1174.30 Sq.mtr.
NET AREA UNDER PLOTS	---	12556.43 Sq.mtr.
AREA UNDER ROADS	---	7104.37 Sq.mtr.



Scale : 1:5000
LOCATION PLAN

हा कार्यावाचे पत्र क्र.अकृषि/सिनांकन/मौज/२०२०/५१
ता.अमरापूर/स.नं. ५१
संसन्ध ५/८/२०२३ री. २०/०२/२०२३ मध्ये नमूद
अटीनुसार प्रयोजनार्थ सिनांकनापी (Recommended
for demarcation) सिफारस करण्यात येत आहे.
सहायक संचालक
नगर स्वच्छता, वार्डा

SCALE : 1:500
LAYOUT MAP

Proforma - I : Area Statement		
Sr. No.	Area Statement	Area (In Sqm)
1	Area Of Plot (Minimum area of a, b, c to be considered)	
a)	As per Ownership Documents (7112, CTS Extract)	25000.00
b)	As per Measurement Sheet	---
c)	As per Site	---
2	Deduction for	
a)	Proposed D.P./D.P. Road Widening Area/Service Road/Highway Widening/TOT PLOT	0.00
b)	Any D.P. Reservation Area	0.00
	Total Deduction (a + b)	0.00
3	Balance Area of Plot (1-2)	25000.00
4	Amenity Space (If applicable)	
a)	Required	2500.00
b)	Adjustment of 2 (b) , If any	0.00
c)	Balance Proposed	2518.50
5	Net Plot Area (3-4 (c))	22481.50
6	Recreational Open Space (If applicable)	
a)	Required	2500.00
b)	Proposed	2520.70
7	Internal Road Area	7404.37
8	Service Road & Highway Widening	
9	Plotable Area	12556.43
10	Pro - rata factor for FSI Calculation on layout Plots = (50)	1.79
11	Area of Inclusive Housing	
a)	Required	
b)	Proposed	

Certificate of Area:
Certified that the plot under reference was surveyed by me on _____ and the dimensions of sites etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in document of Ownership/T.P. Scheme Records/

Signature
(Licensed Engineer)

Owner's Signature : _____
SHASHANK R. GHUDE
Civil Engineer
WARDHA
Reg. No. TFWD/29/2016-22
Mob. 997595453

Statement of Distribution of FSI on each Plot										
Plot No.	Plot area (m.)	Rounding area of Road (Sq.m.)	Remaining plot area (B-C) (Sq.m.)	Pro - rata FSI Factor	Built up area on prorata basis i.e. (D x E)	Front Road Width (m.)	Basic FSI	Permissible Built up area on Basic FSI (E x G) (Sq.m.)	No. of Plots	Total Plot Area
A	B	C	D	E	F	G	H	I	J	F
1	111.75		111.75	1.79	200.03	12	1.10	220.04	1	111.75
2	112.50		112.50	1.79	201.38	12	1.10	221.51	1	112.50
3	132.00	6.05	125.95	1.79	225.45	12	1.10	248.00	1	125.95
4	162.35		162.35	1.79	290.61	9	1.10	319.67	1	162.35
5	160.96		160.96	1.79	288.12	9	1.10	318.93	1	160.96
6	159.58		159.58	1.79	285.65	9	1.10	314.21	1	159.58
7	158.20		158.20	1.79	283.16	9	1.10	311.50	1	158.20
8	157.01		157.01	1.79	281.05	9	1.10	309.15	1	157.01
9	155.43		155.43	1.79	278.22	9	1.10	306.04	1	155.43
10	152.67		152.67	1.79	273.28	9	1.10	300.81	1	152.67
11	149.52		149.52	1.79	266.57	9	1.10	293.22	1	149.52
12	145.16		145.16	1.79	259.84	9	1.10	285.82	1	145.16
13	142.80	4.35	138.45	1.79	247.83	9	1.10	272.81	1	138.45
14 To 24	107.10		107.10	1.79	191.71	9	1.10	210.88	11	1178.10
25	144.50	4.35	140.15	1.78	260.87	9	1.10	275.08	1	140.15
26	144.50	6.06	138.45	1.79	247.83	12	1.10	272.81	1	138.45
27 To 37	107.10		107.10	1.79	191.71	12	1.10	210.88	11	1178.10
38	142.80	6.05	136.75	1.79	244.78	12	1.10	269.26	1	136.75
39	123.00	6.05	116.95	1.79	209.34	12	1.10	230.27	1	116.95
40 To 52	90.00		90.00	1.79	161.10	12	1.10	177.21	13	1170.00
53 To 57	112.50		112.50	1.79	201.38	12	1.10	221.51	5	962.50
58	114.00		114.00	1.79	204.06	12	1.10	224.47	1	114.00
59	112.50		112.50	1.79	201.38	9	1.10	221.51	1	112.50
60 To 64	112.50		112.50	1.79	201.38	9	1.10	221.51	5	962.50
65 To 77	80.00		80.00	1.79	161.10	9	1.10	177.21	13	1170.00
78 To 79	123.00	4.35	118.65	1.79	212.38	9	1.10	233.62	2	237.30
80 To 82	90.00		90.00	1.79	161.10	9	1.10	177.21	13	1170.00
83 To 87	123.00		123.00	1.79	220.17	9	1.10	242.19	5	915.00
88	111.00		111.00	1.79	198.69	9	1.10	218.58	1	111.00
89	104.75		104.75	1.79	187.50	12	1.10	206.25	1	104.75
100 To 104	112.50		112.50	1.79	201.38	12	1.10	221.51	5	962.50
105 To 117	90.00		90.00	1.79	161.10	12	1.10	177.21	13	1170.00
118	123.00	6.05	116.95	1.79	209.34	12	1.10	230.27	1	116.95
TOTAL										12556.43