




DEMARCATED RESIDENTIAL LAYOUT PLAN IN SURVEY
NO.-599/1, IN MAUZA- KELZAR, TAH.-SELOO , DIST.-WARDHA



Statement of Distribution of FSI on each Plot										
Plot No.	Plot area (m.)	Corner Rounding area of Road (Sq.m.)	Remaining plot area (B-C) (Sq.m.)	Pro - rata FSI Factor	Built up area on prorata basis i.e. (D x E)	Front Road Width (m.)	Basic FSI	Permissible Built up area on Basic FSI (F x H) (Sq.m.)	No. of Plots	Total Plot Area
A	B	C	D	E	F	G	H	I	J	K
1	162.08		162.08	1.41	228.53	9	1.10	251.39	1	162.08
2	158.92	4.35	154.57	1.41	217.94	9	1.10	239.74	1	154.57
3	90.00		90.00	1.41	126.90	9	1.10	139.59	1	90.00
4	116.25		116.25	1.41	163.91	9	1.10	180.30	1	116.25
5	95.70		95.70	1.41	134.94	9	1.10	148.43	1	95.70
6 to 9	90.00		90.00	1.41	126.90	9	1.10	139.59	4	360.00
10	157.50	4.35	153.15	1.41	215.94	9	1.10	237.54	1	153.15
11	94.75		94.75	1.41	133.60	9	1.10	146.96	1	94.75
12	85.00		85.00	1.41	119.85	9	1.10	131.84	1	85.00
13	106.65	4.35	102.30	1.41	144.24	9	1.10	158.67	1	102.30
14	129.41	4.35	125.06	1.41	176.33	9	1.10	193.97	1	125.06
15 to 16	77.00		77.00	1.41	108.57	9	1.10	119.43	2	154.00
17	129.49		129.49	1.41	182.58	9	1.10	200.84	1	129.49
18	748.05	6.05	742.00	1.41	1046.22	12	1.10	1150.84	1	742.00
19	530.72	6.05	524.67	1.41	739.78	12	1.10	813.76	1	524.67
20	497.86		497.86	1.41	701.98	12	1.10	772.18	1	497.86
21	462.05	10.40	451.65	1.41	636.83	12	1.10	700.51	1	451.65
22	532.77		532.77	1.41	751.21	12	1.10	826.33	1	532.77
TOTAL									22	4571.30

AREA STATEMENT	
1) TOTAL AREA AS PER 7/12	- 7200.00 Sqm.
2) NET AREA UNDER AMENITY PLOT NO.-23	- 761.87 Sqm.
3) NET AREA UNDER OPEN SPACE	- 721.60 Sqm.
4) NET AREA UNDER PLOT	- 4571.30 Sqm.
5) NET AREA UNDER ROAD	- 1145.23 Sqm.

Proforma - I : Area Statement		
Sr. No.	Area Statement	Area (In Sqm)
1	Area Of Plot (Minimum area of a, b, c to be considered)	
a)	As per Ownership Documents (7/12, CTS Extract)	7200.00
b)	As per Measurement Sheet	---
c)	As per Site	---
2	Deduction for	
a)	Proposed D.P./D.P. Road Widening Area/Service Road/Highway Widening	0.00
b)	Any D.P. Reservation Area	0.00
Total Deduction (a + b)		0.00
3	Balance Area of Plot (1-2)	7200.00
4	Amenity Space (if applicable)	
a)	Required	720.00
b)	Adjustment of 2 (b), if any	0.00
c)	Balance Proposed	761.87
5	Net Plot Area (3-4 (c))	6438.13
6	Recreational Open Space (if applicable)	
a)	Required	720.00
b)	Proposed	721.60
7	Internal Road Area	1145.23
8	Service Road & Highway Widening	
9	Plotable Area	4571.30
10	Pro - rata factor for FSI Calculation on layout Plots = (5/9)	1.41
11	Area of Inclusive Housing	
a)	Required	
b)	Proposed	

CERTIFICATE OF AREA:
CERTIFIED THAT THE PLOT UNDER REFERENCE WAS SURVEYED BY ME ON
AND THE DIMENSIONS OF THE SIDES ETC. OF PLOT STATED ON PLAN ARE AS MEASURED
ON SITE AND THE AREA SO WORKED OUT TALLIES WITH THE AREA STATED IN DOCUMENTS
OF OWNERSHIP / T.P. SCHEME RECORDS / LAND RECORDS / DEPARTMENT/CITYSURVEY RECORDS.

SIGNATURE
(NAME OF LICENSED ENGINEER/SUPERVISOR)

Pramod Kolhe.

OWNER'S SIGNATURE :-

NIRANJAN KANDE
Civil Engineer
Reg. No. TP 4/090/201
Kelkarwadi Wardha
Cell 8806803882
SIGNATURE
(NAME OF LICENSED ENGINEER/SUPERVISOR)

APPROVED
(Subject to correction in red
Non-Agricultural permission granted
vide order dated 03/01/2023 of the
Tahsildar Seloo in the Revenue



या कार्यालयाचे पत्र क्र.अकृषि/अंतिम संजुर्ही/मौजा ५९९/१
ता. सेलू /स.नं. ५९९/१ /सं.नं. ३०२०
दि. २८/१२/२०२२ मध्ये नमूद अटीनुसार गोवाली
प्रयोजनार्थ विमांकीत अभिन्यासास अंतिम संजुर्हीची शिफारस
करण्यात येत आहे. (Recommended for Sanction)

सहायक संचालक
नगर रचना, वर्धा