

3RD FLOOR PLAN

SCALE 1:100



4TH & 5TH FLOOR PLAN

SCALE 1:100



6TH FLOOR PLAN

SCALE 1:100



TERRACE FLOOR PLAN

SCALE 1:100



<<< S.A.ROAD >>>

LOWER GROUND FLOOR PLAN

SCALE 1:100



UPPER GROUND FLOOR PLAN

SCALE 1:100



1ST FLOOR PLAN

SCALE 1:100



2ND FLOOR PLAN

SCALE 1:100



<<< S.A. ROAD >>>

SITE PLAN

SCALE 1:200

OFFICE OF THE CORPORATION OF THE CITY NAGPUR.

Building Permit No.. 2657/BP/ATP/19 Dt.

Date. 02/08/2019

SANCTIONED

subject to conditions mentioned in the building permit

Assistant Director
Town Planning
Nagpur Municipal Corporation

The Rain Water Harvesting is required to be provided as per Direction of Govt. of Maharashtra No. TPB 4320/1745/CR-230/01/UD-13 dated 16th March, 2005 as per schedule for every 100 sq.mts. built-up area. The provision may be by open well / bore dia / recharge chamber for every 300 sq.mts. built-up area. other options mentioned in the schedule may be adopted a) The Municipality may impose a levy of Rs. per annum for every 100 sq.mts. of built-up area, for failure of the owner of the building.

Provision of Solar Water Heating Systems / Solar Photovoltaic Lighting System shall be installed in the building as per the capacity

Type

The person

person,

person.

ations as to use is made, the Municipal

certificate

AREA STATEMENT

NET PLOT AREA	= 557.418 SQ.M.
ADD FSI (30%)	= 167.225 SQ.M.
TDR(1.15 %)	=597.064 SQ.M.
NET PERMISSIBLE B/UP AREA	= 1321.707 SQ.M.
B/UP AREA CALCULATIONS :-	
PROPOSED B/UP AREA ON LOWER .G.F.= 000 SQ.M	
PROPOSED B/UP AREA ON UP.G.F.	= 167.137 SQ.M
PROPOSED B/UP AREA ON 1ST.F.	= 194.362 SQ.M
PROPOSED B/UP AREA ON 2ND.F.	= 194.358 SQ.M
PROPOSED B/UP AREA ON 3RD.F.	= 194.358 SQ.M
PROPOSED B/UP AREA ON 4TH.F.	= 188.567 SQ.M
PROPOSED B/UP AREA ON 5TH.F.	= 188.567 SQ.M
PROPOSED B/UP AREA ON 6TH.F.	= 194.358 SQ.M
TOTAL B/UP AREA	= 1321.707 SQ.M.

PREMIUM AREA CALCULATIONS:-

PERMISSIBLE PREMIUM AREA = 30% X1321.707= 396.512 SQ.M

PROPOSED PREMIUM AREA ON LOW.G.F. = 21.772 SQ.M

PROPOSED PREMIUM AREA ON UP.G.F. = 29.869 SQ.M

PROPOSED PREMIUM AREA ON 1ST.F. = 24.409 SQ.M

PROPOSED PREMIUM AREA ON 2ND.F. = 24.409 SQ.M

PROPOSED PREMIUM AREA ON 3RD.F. = 24.409 SQ.M

PROPOSED PREMIUM AREA ON 4TH.F. =31.23 SQ.M

PROPOSED PREMIUM AREA ON 5TH.F. = 31.23 SQ.M

PROPOSED PREMIUM AREA ON 6TH.F. = 24.409 SQ.M

TOTAL PREMIUM AREA	= 212.737 SQ.M

PARKING AREA STATMENT :-

PARKING REQUIRED FOR 2 UNITS HAVING CARPET AREA BETWEEN 40 TO 100 SQ.M SQ.M.

1 CAR 4 SCOOTER 2 CYCLE

THEREFORE FOR 10 UNITS HAVING CARPET AREA BETWEEN 40 TO 100 SQ.M SQ.M. PARKING REQUIRED

5 CAR 20 SCOOTER 10 CYCLE

PARKING REQUIRED FOR COMMERCIAL AREA HAVING CARPET AREA UPTO 100 SQ.M SQ.M.

2 CAR 4 SCOOTER 4 CYCLE

THEREFORE FOR COMMERCIAL AREA CARPET AREA UPTO 350 SQ.M SQ.M. PARKING REQUIRED

7 CAR 14 SCOOTER 14 CYCLE

AS PER RULE DOUBLE PARKING REQUIRED

14 CAR 28 SCOOTER 28 CYCLE

TOTAL PARKING REQUIRED

19 CAR 48 SCOOTER 38 CYCLE

PROVIDED PARKING

19 CAR 48 SCOOTER 38 CYCLE

PROJECT

SHEET NO. :-1

PROPOSED BUILDING PLAN OF COMMERCIAL CUM RESIDENTIAL CONSTRUCTION ON PLOT NO.9 ,IN CIVIL STATION EXPANSION SCHEME,KH.NOS. 3AND 5 ,MOUZA:-AJANI , CORPORATION HOUSE NO.398,.CITY SURVEY NO.2 AND SHEET NO.13(86A)TAHSIL - NAGPUR. DIST.- NAGPUR.

BELONGING TO -

SHRI. DAYASHANKAR NATHULAL DIXIT THROUGH P.O.A. HOLDER M/S SHREE CONSTRUCTION PROPRIETOR SHRI. SACHIN A. KHARE

A. AREA STATEMENT-

No.		Area Statement	Sq. Mt.
A			
	1	Area Of Plot	557.418
	2	Deductions for	-
	3	Deductions for (Amenity Space/Recreational Ground)	-
	4	Net Balance Plot Area (1-2-3)	557.418
	5	Addition For Net Plot Area (2)	557.418
	6	Net Plot Area (4+5)	557.418
	7	Permissible (Basic FSI)	1
	8	Permissible (Add.30%Paid FSI)	167.225
	9	Utilized (Add. 30%Paid FSI)	167.225
	10	Permissible T.D.R.	641.03
	11	Utilized T. D. R. Area (N.M.C.&R.A.N.P.) Vide Center No. ..... Dt.	597.064
	12	Total B/U Area Proposed (7+9+11)	1321.707
	13	Permissible F. S.I. (7+9+11)	2.37
	14	Proposed B/U Area	
		a) Resi.	693.262
		b) Comm	200.085
		c) Special	-
		Total	905.347
	15	Excess Balcony Area Taken In FSI	451.36
	16	Existing B/S Area	-
	17	Total B/UP Up Area	1321.707
	18	Consumed F. S. I.	-
B- BALCONY STATEMENT			
	1	Permissible	135.949
		Proposed	551.31
		Excess	415.36
		Enclosed	361.905
C- ALTERNATE TERRACE STATEMENT			
	2	Permissible	-
		Permissible	-
D- TENEMENT STATEMENT			
		Permissible	34
		Proposed	30
E- REFERENCE			
		LAYOUT AS PER S. - ICTION'S DEVELOPMENT PLAN	
		LOC - F PLOT	
		20'-	
		PROP. BUILD. ISE SUBMITTED AS PER PLAN	
		PLOT BOUNDRY SHOWN IN THUS	
		PROPOSED CONSTRUCTION SHOWN IN THUS	
		EXISTING CONST. TO BE RETAINED IN THUS	
		EXISTING CONSTRUCTION DEMOLISHED SHOWN IN THUS	
F- NAME OF OWNER			SINGL
G- ARCHITECTS SING			DIRECTION
H- PREVIOUS SACTION PERMITTING.			
I- DRAWING SHEET NO.			1

SCHEDULE OF OPENINGS

TYPE	SIZE	DESCRIPTION
D	1.2X2.1	T.W. DOOR
D1	1.0X2.1	T.W. DOOR
D2	0.75X2.2	T.W. DOOR
W	1.5X1.2	ALLUMIUM WINDOW
W1	1.2X1.5	ALLUMIUM WINDOW
W2	1.2X0.9	ALLUMIUM WINDOW
W3	3.0X1.8	GLASSING WINDOW
W4	7.0X1.8	GLASSING WINDOW
LD	1.0X2.2	LIFT DOOR
LD1	2.0X2.1	SLIDING DOOR
V	0.60X0.60	M.S.VENTILATOR

INDEX

PLOT BOUNDARY SHOWN IN	
PROPOSED CONSTRUCTION SHOWN IN	
EXISTING CONST. TO BE DEMOLISHED	

ARCHITECT

SAURABH JAGDALE & ASSOCIATES ARCHITECT

CA/2003/31187 M.U.T.S.-1783 M.M.C.R/ 1997

OWNER

THROUGH P.O.A. HOLDER

SHRI.SACHIN A. KHARE

NORTH

SCALE 1:100,200

DATE 7/8/2019

SAURABH JAGDALE & ASSOCIATES
ARCHITECT INTERIORS PLANNERS
PLOT NO. - 16, NISHAD APTS., FIRST FLOOR
DONGRE LAYOUT, SHRADHANAND PETH , NAGPUR.
email :sjassociates10@gmail.com +91 9422112579