PARKING AREA STATEMENT

SR. NO.	BUILDING	UNIT\AREA	REQUIRED CAR	REQUIRED SCOOTER	UNIT\AREA	PROPOSED CAR LARGE	PROPOSED CAR SMALL	PROPOSED SCOOTER
1	WING-A	FOR EVERY 2 TENEMENTS WITH EACH HAVING CARPET AREA EQUAL TO OR ABOVE 40SQ.M. BUT LESS THEN 80SQ.M.	1	5	80/2 = 40	40		200
		TOTAL			=	40		200
		5 % VISITORS PAKING				2.00		10
						2		10
		TOTAL			=	42		210
2	SHOP	FOR EVERY 100SQ.M. CARPET AREA OR FRACTION THEREOF	2	6	109.959/100 = 1.100	2.20		6.6
		5 % VISITORS PAKING				0.10		0.35
						0		0
		TOTAL			=	2		7
		TOTAL PARKING OF WING A			=	44		217
		MULTIPLYING FACTOR FOR NAGPUR REGION	0.7		=	30.8		151.9
		TOTAL REQUIRED PARKING			=	31		152
		TOTAL PROPOSED PARKING			=	16	15	152
						2.5X5X16	2.3X4.5X15	1X2X152
		TOTAL PARKING AREA				200.000	155.250	304.000
								659.250

SR. NO.	BUILDING	UNIT\AREA	REQUIRED CAR	REQUIRED SCOOTER	UNIT\AREA	PROPOSED CAR LARGE	PROPOSED CAR SMALL	PROPOSED SCOOTER
1	WING-B	FOR EVERY 2 TENEMENTS WITH EACH HAVING CARPET AREA EQUAL TO OR ABOVE 40SQ.M. BUT LESS THEN 80SQ.M.	1	5	44/2 = 22	22		110
		TOTAL			=	22		110
		5 % VISITORS PAKING				1.10		5.5
						1		6
		TOTAL			=	23		116
		MULTIPLYING FACTOR FOR NAGPUR REGION	0.7		=	16.1		81.2
		TOTAL REQUIRED PARKING			=	16		81
		TOTAL PROPOSED PARKING			=	8	8	81
						2.5X5X8	2.3X4.5X8	1X2X81
		TOTAL PARKING AREA				100.000	82.800	162.000
								344.800

SR. NO.	BUILDING	UNIT\AREA	REQUIRED CAR	REQUIRED SCOOTER	UNIT\AREA	PROPOSED CAR LARGE	PROPOSED CAR SMALL	PROPOSED SCOOTER
1	WING-C	FOR EVERY 2 TENEMENTS WITH EACH HAVING CARPET AREA EQUAL TO OR ABOVE 40SQ.M. BUT LESS THEN 80SQ.M.	1	5	44/2 = 22	22		110
		TOTAL			=	22		110
		5 % VISITORS PAKING				1.10		5.5
						1		6
		TOTAL			=	23		116
		MULTIPLYING FACTOR FOR NAGPUR REGION	0.7		=	16.1		81.2
		TOTAL REQUIRED PARKING			=	16		81
		TOTAL PROPOSED PARKING			=	8	8	81
						2.5X5X8	2.3X4.5X8	1X2X81
		TOTAL PARKING AREA				100.000	82.800	162.000
								344.800

SR. NO.	BUILDING	UNIT\AREA	REQUIRED CAR	REQUIRED SCOOTER	UNIT\AREA	PROPOSED CAR LARGE	PROPOSED CAR SMALL	PROPOSED SCOOTER
1	WING-D	FOR EVERY 2 TENEMENTS WITH EACH HAVING CARPET AREA EQUAL TO OR ABOVE 40SQ.M. BUT LESS THEN 80SQ.M.	1	5	40/2 = 20	20		100
		TOTAL			=	20		100
		5 % VISITORS PAKING				1.00		5
						1		5
		TOTAL			=	21		105
		MULTIPLYING FACTOR FOR NAGPUR REGION	0.7		=	14.7		73.5
		TOTAL REQUIRED PARKING			=	15		74
		TOTAL PROPOSED PARKING			=	8	7	74
						2.5X5X8	2.3X4.5X7	1X2X74
		TOTAL PARKING AREA				100.000	72.450	148.000
								320.450

SR. NO.	BUILDING	UNIT\AREA	REQUIRED CAR	REQUIRED SCOOTER	UNIT\AREA	PROPOSED CAR LARGE	PROPOSED CAR SMALL	PROPOSED SCOOTER
1	WING-E	FOR EVERY 2 TENEMENTS WITH EACH HAVING CARPET AREA EQUAL TO OR ABOVE 40SQ.M. BUT LESS THEN 80SQ.M.	1	5	80/2 = 40	40		200
		TOTAL			=	40		200
		5 % VISITORS PAKING				2.00		10
						2		10
		TOTAL			=	42		210
2	SHOP	FOR EVERY 100SQ.M. CARPET AREA OR FRACTION THEREOF	2	6	102.912/100 = 1.029	2.06		6.17
		5 % VISITORS PAKING				0.10		0.35
						0		0
		TOTAL			=	2		6
		TOTAL PARKING OF WING A			=	44		216
		MULTIPLYING FACTOR FOR NAGPUR REGION	0.7		=	30.8		151.2
		TOTAL REQUIRED PARKING			=	31		151
		TOTAL PROPOSED PARKING			=	16	15	151
						2.5X5X16	2.3X4.5X15	1X2X151
		TOTAL PARKING AREA				200.000	155.250	302.000
								657.250

N.M.R.D.A. L.S. No. NMRDA/LS/2001/2784/2324 L.S. Valid Up to. 31/12/2024

OFFICE OF THE NAGPUR METROPOLITAN REGION DEVELOPMENT AUTHORITY
Building Permit No. BP(NMRDA)/South Hyp(E)/No-302019/3580/2020/3241013/2533/364
SANCTIONED
Dt. 23/12/2020
Assistant Engineer
Nagpur Metropolitan Region Development Authority
Occupation Certificate Shall be issued only after payment of full Premium amount

The Previous Building Permit No.BP(NMRDA)/East/Kamptee South Hyp(E) No-/11181/19 dated 22/12/2020 Is/Are Cancelled

This sanction is subject to conditions of N.A. order No. 197/1999 dt. N.A.T.P. order dt.

Subject to Condition of N.O.C from Airport Authority Dt. 23/12/2020

This Sanction is Subject to Condition that Plan shall be leased as per Condition No. (Lease) in Development Agreement Dt. 31/12/2020

Subject to the condition that Developer/ Applicant shall construct sewage treatment plant (STP) as per the required norms of Maharashtra Pollution Control Board and shall submit the NOC from MPCB with compliance of same occupation not be issued

Occupancy Certificate Shall be issued only after fulfillment of Premium amount

This Sanction is Subject to Conditions Mentioned In Development Agreement Dt. 31/12/2020

Subject to the condition laid down by Directorate of Maharashtra Fire service vide Letter No. mfs/si/2021/820, dated 23/12/2020

Subject to the provisions of structural drawings submitted by applicant.

Subject to terms and condition of Government circular dated 30-01-2016 that Developer have to construct the temporary sheds, toilet and arrangement o drinking water for the labours.

Necessary arrangement for rain water harvesting shall be done

SUBJECT TO THE PROVISIONS OF STRUCTURAL DESIGN SUFFICIENCY CERTIFICATE DATED 22.12.20 22.OF STRUCTURAL DESIGNER AND APPLICANT.

Subject to Compliance of terms and Conditions of Environment clearance) otter dated 1/12/2020

STP

ADJOING SANCTIONED LAYOUT KH.NO. 131/1-A

RAIN WATER HARWASTING

SOLAR WATER HEATING SYSTEM

AREA STATEMENT OF B/UP AREA FSI & NON FSI AREA CALCULATION

SR.NO.	BUILDING BLOCK	B/UP AREA AS PER P- LINE (EXIST. /PROP.)	STILT PARKING AREA	PODIUM PARKING AREA	STAIRCSE TOWER AREA ON TERRACE	OVER HEAD WATER TANK & LIFT MACHINE	PARKING RAMP	NON APPROCHABLE TERRACE AREA ON FIRST FLOOR	E.S.S.	S.T.P.	UNDER GROUND WATER TANK	TOTAL FSI & NON FSI AREA
1	BUILDING (Wing A, Wing B, Wing C, Wing D & Wing E)	27887.401	4152.403	4442.670	135.670	179.770	244.400	2204.800	25.000	25.000	200.000	39497.114

PARKING STATEMENT

TOTAL PARKING REQUIRED (WING A,B,C,D & E):- 109 CARS + 539 SCOOTER)

TOTAL PARKING PROVIDED:- (WING A,B,C,D & E):- 109 CARS + 560 SCOOTER)
20% ELECTRIC VEHICLE PROVIDED :- 22 CARS + 112 SCOOTERS
OUT OF THIS 30% ELECTRIC VEHICLE IS USE TO COMMON ELECTRIC VEHICLE CHARGING POINT :- 17 CARS + 56 SCOOTERS

KH.NO. 150/2

TOTAL B/UP AREA OF EXISTING & PROPOSED

WING - A	(G.F. TO 11 TH FLOOR)	=	6948.412	SQ.MT
WING - B	(G.F. TO 12 TH FLOOR)	=	4697.878	SQ.MT
WING - C	(G.F. TO 12 TH FLOOR)	=	4697.878	SQ.MT
WING - D	(G.F. TO 11 TH FLOOR)	=	4602.317	SQ.MT
WING - E	(G.F. TO 11 TH FLOOR)	=	6940.916	SQ.MT
	TOTAL	=	27887.401	SQ.MT



SITE PLAN

SCALE - 1:200

SHEET NO. - 01\18

SITE PLAN

REVISED PROPOSED MULTY - FAMILY RESIDENTIAL BUILDING PLAN ON KH. NO.-150/1,MOUZA- PIPLA, TAL.- NAGPUR (GRAMIN), DIST. - NAGPUR

BELONGING TO :-
1) MR. NARENDRA S. MALLELWAR
2) MR. RAHUL B. MALLELWAR
3) MR. MANOJ B. SURAMWAR
4) MR. CHANDRAKANT B. SURAMWAR
5) MR. MANGESH A. MALLELWAR
6) MR. RAJU B. CHANNAWAR

TOTAL BUILT UP AREA

GROUND FLOOR	=	725.153	Sq.m.
FIRST FLOOR	=	294.486	Sq.m.
WING A (2ND TO 11 TH)	=	6740.377	Sq.m.
WING B (2ND TO 12 TH)	=	4607.444	Sq.m.
WING C (2ND TO 12 TH)	=	4607.444	Sq.m.
WING D (2ND TO 11 TH)	=	4172.120	Sq.m.
WING E (2ND TO 11 TH)	=	6740.377	Sq.m.
TOTAL B/UP AREA	=	**27887.401**	**Sq.m.**

kh. NO. 150/1, Mouza:- PIPLA
F.S.I. Calculation As per Proforma - I of UDCPR - 2020 :- Built-up Area Calculation

	Permissible (Ratio/Area in sq. m.)	Exist./Prop. (Ratio / Area in sq. mt.)
a) Net plot area for FSI Calculation (clause No.3.9 of UDCPR-2020):-		8370.062 sq.mt.
b) Existing B/UP Area as per privious sanctioned		388.903
c) Net Proposed P- Line built up area :-		27498.498 sq.m.
d) Total area of Existing & proposed P-line B/up area		27887.401 sq.mt.
e) Dividing Factor 1.6 to arrive Basic FSI =Premium FSI = TDR:-P.line area/(1.6):- 27498.498 / 1.6 :-		**17186.561 sq.m.**
f) Permissible ancillary FSI :- (clause No.6.3, Table No.6-G, Note-(i) of UDCPR):- (c- e) =	10311.936	**10311.936 sq.m.**
g) Permissible Basic F.S.I./B/u area :- (1.1xa)	9207.068	9207.068
h) Permissible Basic F.S.I. on premium (0.3x a) :-	0.30/2511.019	0.299/2509.357
i) Permissible In-situ FSI/TDR :- (Table No. 6-G & Proforma - I of UDCPR)		
i) In situ area against D.P. for Road Widening with compliance of Clause No. 7.2 & as per previous sanctioned dated:- 28/08/2020 :- (1.850 X 1429.938)	2645.385	2645.385 sq.mt.
ii) TDR Area as per certificate No.---- :-		3213.658 sq.mt.
iii) Total In-situ / TDR loading proposed (i+ii) :-		5859.043 sq.mt.
iv) Permissible TDR :- 0.70 of 8370.062 sq.m. =		0.70/5859.043 sq.mt.
k) Total entitlement of FSI :- (f+g+h+i (iv)) :-	27889.063	27887.401
l) Maximum Building Potential on load :- 1.5 1/(Excluding Ancillary FSI)	8370.062 sq.m. x 2.1 = 17577.130	(k- f) 2,099/17575.465 sq.mt.

TOTAL EXISTING B/UP AREA

GROUND FLOOR (WING A ,B ,C)	=	293.339	SQ.MT
FIRST FLOOR (WING A ,B ,C)	=	95.564	SQ.MT
TOTAL	=	388.903	SQ.MT
TOTAL PROPOSED P-LINE B/UP AREA	=	27887.401	SQ.MT
(-) EXISTING B/UP AREA	=	388.903	SQ.MT
NET PROPOSED B/UP AREA	=	27498.498	SQ.MT

LEGEND:
PLOT BOUNDRY SHOWN IN
PROPOSED CONSTRUCTION SHOWN IN
EXISTING CONSTRUCTION SHOWN IN

SUBMISSION DRAWING

ARCHITECT

ARCHITECT C. D. Giripunje C.A. / 2011 / 27832 N.I.T. No.1321 N.M.C. No.R-193 M. No. 9422103220

Date	
Dwg. No.	SUB./01
Dealt by	CHANDU SIR
Scale	1:200

North

OWNER
1) MR. NARENDRA S. MALLELWAR
2) MR. RAHUL B. MALLELWAR
3) MR. MANOJ B. SURAMWAR
4) MR. CHANDRAKANT B. SURAMWAR
5) MR. MANGESH A. MALLELWAR
6) MR. RAJU B. CHANNAWAR

V I S T A A R
ARCHITECT,INTERIOR DESIGNER, PLANNER FLAT NO. 106,GROUND FLOOR,BHRILA APARTMENT, BEHIND BATUKBHAI JEWELLERS,KHARE TOWN,DHARAMPETH,NAGPUR-440010. PH.NO.(0712)-2546183