NIT
L.S. No. 2140
Serial No.
Valid upto 31/12/2020

SHEET NO. 1/2

JOB TITLE
PLAN SHOWING PROPOSED CONSTRUCTION FOR MULTI FAMILY RESIDENTIAL DWELLING UNIT ON PLOT NO.01, KH NO.180/6,P.S.K. NO.44 MOUZA -NARA IN MALIK MAKBUJA LAYOUT , TAH-DIST-NAGPUR.

BELONGING
1) MR. RAKESH MADHAVDAS LALWANI
2) MR. RAJKUMAR GOPICHAND RUGHWANI
3) MR. MUJAHID IKBAL MOHD ISMILE

NO.	AREA STATEMENT	Sq.Mt.
	A - AREA STATEMENT	
1	**Area Of Plot**	**1791.013**
2	Deductions For	
	Tangent	0.000
	Road Widening	0.000
3	Deductions For	
	Amenity Space	0.000
	Recreational Ground	0.000
	Internal Roads	0.000
4	**Net Balance Plot Area (1-2-3)**	1791.013
5	Addition For Net Plot Area (2)	0.000
6	**Net Plot Area (4+5)**	1791.013
7	**Permissible (Basic FSI)**	1.250
8	Permissible Built up Area (6 x 7)	2238.766
9	FSI on payment of Premium 50% of plot area	895.507
10	Permissible T.D.R. 90%/2 = 45%	0.000
11	Poposed T.D.R. 45%	0.000
12	**Total Proposed F.S.I. (8+9+11) (1.75)**	**3134.273**
13	Permissible Ancillary area 60% of proposed fsi	1880.564
14	Proposed Ancillary area 60% of proposed fsi	1880.564
15	**Total Permissible Built up Area (12+14)**	**5014.837**
16	**Proposed B/U Area**	
	a). Resi.	4997.764
	b).Comm.	0.000
	c).Industrial	0.000
	d).Special	0.000
	Total	4997.764
17	Existing B/U Area	0.000
18	**Total Built Up Area (16+17)**	**4997.764**

SCHEDULE OF OPENINGS :

CODE	SIZE	SILL LVL.	LTL. LVL.	REMARKS
W	1500 x 1500	600	2100	M.S FRAMED WINDOW
W1	715 x 900	1200	2100	M.S FRAMED WINDOW
W2	600 x 900	1200	2100	M.S FRAMED WINDOW
V	600 x 600	1500	2100	M.S FRAMED WINDOW
D	1100 x 2100	——	2100	T.W. DOOR
D1	1500 x 2100	——	2100	CONCRETE FRAMED
D2	915 x 2100	——	2100	GRANITE FRAMED VENT
D3	765 x 2100	——	2100	CONCRETE FRAMED
D4	1450 x 2100	——	2100	T.W. DOOR
SD	1500x 2100	——	2100	SLIDING DOOR

PARKING AREA STATEMENT
Table No. 8B(UDCPR)

NORMS FOR RESIDENTIAL	CAR (NOS.)	SCOOTERS (NOS.)	
For every two tenement with each tenement having carpet area equal to or above 40sq.mt. but less than 80 sq.mt.	1	5	5% Vistors Parking
REQUIRED PARKING			
REQUIRED FOR 56 TENEMENTS BETWEEN 40 TO 80 SQ.MT	56	28	140
TOTAL PARKING (A)		28	140
5% VP (B)		1	7
TOTAL REQUIRED(D=A+B)		29	147
as per table no.8c Multiplying Factor = (0.9XD)		26	132
TOTAL PROPOSED PARKING		26	132

VEHICLE TYPE	VEHICLE AREA	NOS.	AREA (SQ.M)
CAR BIG- 2.5 X 5m	12.500	14	175.000
CAR SMALL- 2.3 X 4.5m	10.350	12	124.200
SCOOTER - 1 X 2m	2.000	132	264.600
TOTAL STILT PARKING AREA PROVIDED			563.800

FRONT ELEVATION
SCALE -1:100

SECTION A-A
SCALE -1:100

FLOOR WISE FSI STATEMENT : - BUILDING 1

FLOOR'S	PROPOSED B/U AREA (sq.m) COMMA	RESI.	SPECL.	INDUL.	PROPOSED TENEMENTS	TOTAL BUILT UP AREA
GROUND FLOOR	0.0000	505.3990	0.000	0.000	0	505.3990
1st FLOOR	0.0000	665.2990	0.000	0.000	8	665.2990
2nd FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
3rd FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
4th FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
5th FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
6th FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
7th FLOOR	0.0000	704.5120	0.000	0.000	8	704.5120
TOTAL	0.0000	4997.7640	0.0000	0.0000	56	4997.7640



SOLAR WATER SYSTEM
TO BE INSTALLED ON TERRACE FLOOR

ROOF RAINWATER HARVESTING SYSTEM
SHOULD BE PROVIDED WITHIN PLOTAREA

9.00 MT WIDE ROAD

OFFICE OF THE NAGPUR IMPROVE...
Building Permit No. R.E.N.D.C.No. BUI-G...089/...
Date ...To No:2020705637
SANCTIONED
Building Engineer
Nagpur Improvement Trust



STILT FLOOR PLAN
SCALE -1:100



BUILT UP AREA KEY PLAN FOR GROUND FLOOR PLAN
SCALE 1:200

BUILT UP AREA ON GROUND FLOOR

SR. NO.	NO.	DIMENSIONS			AREA
BLOCK	1	X	9.850 X	15.855	156.172
TOTAL					156.172
DEDUCTIONS					
D1	1	X	1.815 X	7.100	12.887
D2	1	X	1.785 X	7.100	12.674
D3	1	X	9.850 X	1.345	13.248
D4	1	X	4.200 X	2.850	11.970
TOTAL					50.779
TOTAL B/UP AREA ON GROUND FLOOR					105.393

COMPOUND WALL SECTION

COMPOUND WALL ELEVATION (N.T.S.)



<<<<<<<<<< 9.00 MT. WIDE ROAD >>>>>>>>>>



<<<<<<<<<< 9.00 MT. WIDE ROAD >>>>>>>>>>

SITE PLAN
SCALE -1:200

REFERENCE :

PLOT BOUNDARY SHOWN IN THUS
PROPOSED CONSTRUCTION SHOWN IN THUS

DRAWING TITLE
SUBMISSION DWG.

Architect's Sign.

Ar. LOKESH KADU
CA/ 2007/ 39381
NMC R.402, NIT-2140
Ar. LOKESH W. KADU
C.O.A. No : CA / 2007/ 39381

Client's Sign.

1) MR. RAKESH MADHAVDAS LALWANI
2) MR. RAJKUMAR GOPICHAND RUGHWANI

C.O.A. REG. NO	N.I.T. REG. NO	N.M.C. REG. NO
CA /2007/ 39381	2140	R-402
SCALE 1 : 100 & 1 : 200		DEALT BY SHILPA
DATE 05/03/2021		CHECKED BY

Note - ALL DIMENSIONS ARE IN MM.

Ar. LOKESH W. KADU
Architecture, Planning, Interior's
Block No. 11, 11A, 12, A- Wing (J.B Wing), Mengalwari Complex, Sadar, Nagpur - 440010. (M.S.), India.
cell: +91 9823872384,+ 91 7276384238,
mail us: emanatsdesign9@gmail.com, web: www.emanatsdesign.in