PROPOSED SITED.P.SHEET NO - 19



FRONT ELEVATION
(SCALE 1:100)



SECTION B-B
(SCALE 1:100)



SECTION A-A



SITE PLAN
SCALE 1:200

OFFICE OF THE CORPORATION OF THE CITY MAGPUR.
SANCTIONED

MARGINAL RELAXATION.

1) WEST SIDE - RESIDENTIALS
a) GROUND FLOOR = 16.80 X 2.12 = 35.192 SQ.M.
b) 2 NO. TO 11 TH. FLOOR = 16.80 X 2.12 = 351.92 SQ.M.
TOTAL RESIDENTIALS RELAXATION = 387.112 SQ.M.
COMMERCIAL RESIDENTIALS
c) 1 ST. FLOOR = 16.80 X 2.12 = 35.192 SQ.M.
2) SOUTH SIDE - RESIDENTIALS
a) GROUND FLOOR = 23.998 X 0.62 = 14.852 SQ.M.
b) 2 NO. TO 11 TH. FLOOR = 23.998 X 0.62 = 148.527 SQ.M.
TOTAL RESIDENTIALS RELAXATION = 163.379 SQ.M.
COMMERCIAL RESIDENTIALS
c) 1 ST. FLOOR = 23.998 X 0.62 = 14.852 SQ.M.
TOTAL RESIDENTIALS RELAXATION =
= 387.112 + 163.379 = 550.491 SQ.M.
TOTAL COMMERCIAL RELAXATION =
= 35.192 + 14.852 = 50.044 SQ.M.



12.00 M.W. ROAD

GROUND FLOOR PLAN

P.LINE AREA G.F. = 68.426 SQ.M.

FIRST FLOOR PLAN

P.LINE AREA F.F. = 425.436 SQ.M.



TYPICAL FLOOR PLAN
2 ST TO 7 th FLOOR & 9 TH TO 11 th FLOOR

P.LINE AREA S.F. = 415.761SQ.M.X 10 = 4157.61 SQ.M.



8 TH FLOOR PLAN

P.LINE AREA 8 th .F. = 415.761 SQ.M.

PARKING STATEMENT

OCCUPANCY	OPEN PARKING SPACE FOR EVERY	UNIT / AREA	REQUIRED PARKING			PROVIDED PARKING		
			CAR	SC	CY	CAR	SC	CY
RESIDENTIAL	HIGH LUXURY SCHEME (1 CAR PARKING FOR EVERY 2 UNITS)		21	21	42	21	23	42	21
SHOP AND OFFICE (COMMERCIAL AREA)	100.00 SQ.M.		2	4	4	2	4	4
TOTAL			23	49	25	24	49	25

SR.	DETAILS	PERMISSIBLE AREA	PROPOSED AREA
1	PLOT AREA	1840.797	
2	AMENITY SPACE	NIL	NIL
3	NET AREA (PLOT)	1840.797	1840
4	FAR 1.5 (2.00)	2297.616	
5	TDR / F.S.I (1.00)	1840.000	NIL
6	PREMIUM F.S.I (0.00)	0.000	NIL
7	T.D.R (LOADING) (0.00)	0.000	NIL
8	LABEST (a) + (b) + (c)	3681.797	NIL
	ANCILLARY (0.15) (TDR) (d) + (e)	2.04.969	NIL
10	TOTAL P.LINE 7.8.9 (d) + (e) +	5886.036	4837.972

SR.	FLOOR	PLINE MAP AREA		MECHANICAL AREA	TOTAL BUILT AREA
		COMMERCIAL	RESIDENTIAL		
	A	B	C	D	E
1	G.F.	68.426	------	------	68.426
2	1 ST.	73.622	348.814	------	422.436
3	2 ND.	0.000	415.761	------	415.761
4	3 RD.	0.000	415.761	------	415.761
5	4 TH.	------	415.761	------	415.761
6	5 TH.	------	415.761	------	415.761
7	6 TH.	------	415.761	------	415.761
8	7 TH.	------	415.761	------	415.761
9	8 TH.	------	415.761	------	415.761
10	9 TH.	------	415.761	------	415.761
11	10 TH.	------	415.761	------	415.761
12	11 TH.	------	415.761	------	415.761
TOTAL		142.048	4977.131	------	4837.972

CERTIFICATE OF AREA

CERTIFIED THAT THE PLOT UNDER REFERANCE WAS SURVEYED BY ME ON ---- AND THE AREA SO MEASURED OUT TO BE ---- SQ.M. AS PER 7/12 EXTRACT IS ---- SQ.M. AND THE AREA SO MEASURED OUT LESS/(+) MORE THE AREA STATED IN DOCUMENT OF OWNERSHIP / T.P.SCHEME / RECORDS / LAND RECORDS DEPARTMENT / CITY SURVEY RECORD.

SIGNATURE
NAME OF ARCHITECTS/LICENSED ENGINEER/ SUPERVISOR :

Owner's Declaration :-

I/WE UNDERSIGNED HEREBY CONFIRM THAT I/WE SHOULD MADE BY PLANS APPROVED BY AUTHORITY / COLLECTOR / I/WE SHOULD ASSIST BY THE STRUCTURE AS PER AGREEMENT.

ALSO I/WE SHOULD ASSIGN TO THE WORK UNDER SUPERVISION OF PROPER TECHNICAL PERSON DO NO TO ENSURE THE QUALITY AND SAFELY AT THE WORK SITE.

SMT. PARVESH ASHOK AGRAWAL

Owner's Name And Signature

ARCHITECTS/LICENSED ENGINEER/ SUPERVISOR NAME & SIGN :

Orig. No.	Date	Drawing by	Checked by
-	1:100 1:200	VIRAJ ARCHITECTS GANPATI	SHRI. B.GUPTA

PLOT BOUNDRY SHOWN :-
PROPOSED CONSTRUCTION SHOWN :-
EXISTING TO BE DEMOLISH SHOWN.

PROFORM - I AREA STATEMENT

(AT RIGHT HAND TOP CORNER OF PLOT)

DRAWING SHEET NO. XY

PROPOSED RESIDENTIAL & COMMERCIAL AND TY FAMILY BUILDING PLAN ON BEING IN M.C.I. HOUSE NO. 345/ 57 , PLOT NO. 107, 47/A/2 , 21/2, WARD NO.-23, SHEET NO. - 7/3, CTS NO. 134 BEHIND - MAGPUR SECTION - 19 CENTRAL ROAD UNDER DEMARCATION ZONE - I, ZUNI DIST. THA.& DIST. NAGPUR

STAMP OF APPROVAL OF PLANS	
AREA STATEMENT	
1) AREA OF PLOT - (Minimum area of S.I.I.) to be considered -	1840.797 SQ.M.
(a) As per ownership document / 7/12 / CTS extract -	1840.797 SQ.M.
(b) As per measurement sheet	
(c) As per site	1840.797 SQ.M.
2) DEDUCTIONS FOR-	
(a) Proposed D.P. / D.P. Road widening Area Reccive Road / Highway Widening	21.645 SQM
(b) Any D.P. - Reservation Area / AMENITY SPACE AREA)	0.00
(TOTAL a + b)	
3) Balance area of plot (1-2)	1807.972 SQM
4) Amenity Space / P.Agriculture)	N.A
(a) Required	(NIL)
(b) Adjustment of 20% if any	(NIL)
(c) Balance Proposed	(NIL)
5) Net Plot Area (3-4) (c)	1620.797 SQM
6) Transational Claim Space (if applicable)	N.A
(a) Required	(NIL)
(b) Proposed	(NIL)
7) Internal Road Area	(NIL)
8) Chowki Area (if applicable)	(NIL)
9) Built area with reference to basic F.S.I (as per front road HEIGHT WISE) - (w.r.to. Between the) (1807.972 X 2.00) (30% INC. SCUR)	3615.944 SQ.M
10) Addition of F.S.I. on payment of premium	(NIL)
(a) Maximum permissible premium F.S.I. (based on road width) And zone	(NIL)
(b) Proposed F.S.I. on payment of premium	(NIL)
11) In - SITU / TDR building	(NIL)
(a) Area upto approx B.P. (max 2.5 w.r.w. no 2) (as per) (3.00 X 1.00) + 1.00) = 76.800 SQM.	76.800 SQ.M
(b) R only area against Amenity Space if handed over (3.00 m 1.00 m w.r.t to) and / or as	(NIL)
(c) TDR area	76.800 SQ.M
(d) Total in-situ / TDR building proposed (11 (a) + (c))	76.800 SQ.M
12) Additional FSI area under Chapter no. 7	(NIL)
13) Total entitlement of FSI in the proposed	
(a) (9 + 10 (b) + 11 (d) or 12 whichever is applicable)	SQ.M
(b) Ancillary Area FSI up to 60% or 80% with payment of charges	SQ.M
(c) Total entitlement (a + b)	3692.972 SQM
14) (a) Maximum utilization limit of the (building potential) permissible as per clasification (as per regulation no. 6) (2 & 3) or 5) or 6) or applicable or 7.8 or 7.9)	3686.528 SQ.M
15) TDR/ Built up Area to proposed (excluding area at sr. no 11) -	
(a) EXISTING BUILT UP AREA	0.00
(b) PROPOSED BUILT UP AREA (AS PER PLINE)	4837.972 SQ.M.
(c) Total (a + b)	
16) TB Consumed (13 / 15) (shall not be more than serial no. 14 above)	4837.972 SQ.M.
17) Area for Inclusive Housing, if any	
(a) Required (30 % of sr. no. 9)	
(b) Proposed	