

PROPOSED FORTH FLOOR PLAN

SCALE - 1:100.



PROPOSED FIFTH FLOOR PLAN

SCALE - 1:100.



PROPOSED TERRACE FLOOR PLAN

SCALE - 1:100.

...rovisions for Solar Water Heating Systems
solar Water Heating System should be installed
on the Building for the following area at the per
capita capacity mentioned" as under.

Type of Buildings	Per Capita Capacity recommended
1) Hospitals	...(100 Ltrs./day)/person.
2) Hotels	...(100 Ltrs./day)/person.
3) Hostels & other such buildings	...(25 Ltrs./day)/person.
4) Residential	...(25 Ltrs./day)/person.

if the provisions as above is not made, the occupancy certificate will not be issued from NMC

(Rain Water Harvesting is required to be provided as per Direction of Govt. of Maharashtra No. TPB 432001/2133 CR - 230/01/UD-11, dated 10th March, 2005 as per schedule for every 300 sq.mtrs. built-up area The system may be by open well 1 mtr. dia 6 mtrs. deep with filteration chamber for every 300 sq.mtr. built-up area Other provisions mentioned in the schedule may be adopted.
a) The authority may impose a fine of Rs. 5,000/- and Rs. 1000/- per annum for every 100 sq.mts. of built-up area, for failure of the owner of the building.

OFFICE OF THE CORPORATION OF THE CITY NAGPUR.
Building Permit No. 511/ESR/NAGPW/2022 Date 26/4/22
SANCTIONED
subject to conditions mentioned in the building permit
Assistant Director Town Planning
Nagpur Municipal Corporation



SITE PLAN

SCALE 1:200.



SOLAR WATER HEATING SYSTEM



RAINWATER HARVESTING DETAIL

PLAN SHOWING PROPOSED CONSTRUCTION FOR COMMERCIAL & MULTI FAMILY DWELLING UNIT ON PLOT NO. 539 , HOUSE NO. 1119/ 539 , MOUZA :- NAGPUR , CITY SURVEY NO. 115 , SHEET NO. 323 , 145 , TAH. & DIST. NAGPUR. BELONGING TO

SHRI. KAMALKISHOR KISANLAL JAISWAL .

Stamps of Approval of Plans:

AREA STATEMENT

PLOT AREA		
AS PER SELL DEED	15.240 X 33.536	= 511.150 SQMT.
AS PER SITE	14.634 X 33.536	= 490.765 SQMT.
AS PER CITY SURVEY		= 484.500 SQMT.
AS PER LEESE DEED		= 510.990 SQMT.
BASIC FSI 1.10	484.50 X 1.10	= 532.950 SQMT.
FSI FOR PREMIUM 50 % X 484.50 SQMT		= 242.250 SQMT.
NET TOTAL PLOT AREA		= 775.200 SQMT.
ANCILLARY AREA 60 % X 775.20 SQMT		= 465.120 SQMT.
NET TOTAL PERMISSIBLE FSI AREA		= 1240.320 SQMT.

AREA STATEMENT	
1. Area of plot	
(Minimum area of a, b, c to be considered)	484.500 SQMT.
(a) As per ownership document (7/12, CTS extract)	484.500 SQMT.
(b) as per measurement sheet	511.150 SQMT.
(c) as per site	490.765 SQMT.
2. Deductions for	----
(a) Proposed D.P./ D.P. Road widening Area/ Service Road / Highway widening	----
(b) Any D.P. Reservation area	----
(Total a+b)	----
3. Balance area of plot (1-2)	----
4. Amenity Space (if applicable)	----
(a) Required -	----
(b) Adjustment of 2(b), if any -	----
(c) Balance Proposed -	----
5. Net Plot Area (3 - 4 (c))	----
6. Recreational Open space (if applicable)	----
a) (a) Required -	----
b) (b) Proposed -	----
7. Internal Road area	----
8. Plotable area (if applicable)	----
9. Built up area with reference to Basic F.S.I. as per front road width	----
(Sr. No. 5xbasic FSI)	1.10 FSI
10. Addition of FSI on payment of premium	50 %
(a)Maximum permissible premium FSI - based on road width / TOD Zone.	----
(b) Proposed FSI on payment of premium.	242.250 SQMT.
11. In-situ FSI / TDR loading	----
(a) In-situ area against D.P. road [2.0 x Sr. No. 2 (a)], if any	----
(b) In-situ area against Amenity Space if handed over	----
[2.00 or 1.85 x Sr. No. 4 (b) and /or (c)].	----
(c) TDR area	----
(d) Total In-situ / TDR loading proposed (11 (a)+(b)+(c))	----
12. Additional FSI area under Chapter No. 7	----
13. Total entitlement of FSI in the proposal	----
(a) [9 + 10(b)+11(d)] or 12 whichever is applicable.	----
(b) Ancillary Area FSI upto 60% or 80%with payment of charges. 60 %	465.120 SQMT.
(c) Total entitlement (a+b)	----
14. Maximum utilization limit of F.S.I. (building potential) Permissible as per Road width ((as per Regulation No. 6.1 or 6.2 or 6.3 or 6.4 as applicable) x 1.6 or 1.8)	----
15. Total Built-up Area in proposal. (excluding area at Sr.No.17 b)	1240.320 SQMT.
(a) Existing Built-up Area.	----
(b) Proposed Built-up Area (as per 'P-line')	1239.940 SQMT.
(c) Total (a+b)	----
16. F.S.I. Consumed (15/13) (should not be more than serial No.14 above.)	99.96 %
17. Area for inclusive Housing, if any	
(a) Required (20% of Sr.No.5)	
(b) Proposed	1239.940 SQMT.

Certificate of Area:
Certified that the plot under reference was surveyed by me on L. B. Kukde and the dimensions of sides etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in the document of Ownership / T.P. Scheme Records / Land Record Department / City Survey Records

Signature
(Name of Architect/ Licensed Engineer/ Supervisor.)

Owner's Declaration –
I/We undersigned hereby confirm that I/We would abide by Authority / Collector I/We would execute the structure as approved plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site.

Owner (s) name and signature

SCHEDULE FOR OPENING

S. NO.	TYPE	SIZE	DESCRIPTION
1	RS1	2.75 X 2.75	M.S. ROLLING SHUTTER
2	D	1.20 X 2.25	T. W. DOOR & PANNEL
3	D1	1.05 X 2.25	T. W. DOOR & PANNEL
4	D2	0.75 X 2.25	T. W. DOOR & PANNEL
5	W	2.10 X 1.80	T. W. WINDOW & (GLAZED)
6	W1	1.50 X 1.50	T. W. VENTILATOR
	V	0.60 X 0.60	T. W. VENTILATOR

PLOT BOUNDRY SHOWN THUS
EXISTING CONST. SHOWN THUS
PROPOSED CONST. SHOWN THUS
TEMP. CONS. TO BE DEMOLISHED

PARKING AREA STATEMENT

SHOP
FOR EVERY 100.00 SQMT. CARPET AREA OF FRACTION
THEREOF 2 CAR + 6 SCOOTER
HENCE REQUIRED PARKING 2 CAR + 6 SCOOTER

OFFICE
FOR EVERY 200.00 SQMT. CARPET AREA OF FRACTION
THEREOF 3 CAR + 11 SCOOTER
PROPOSED 196.168 SQMT. CARPET AREA
HENCE REQUIRED PARKING 3 CAR + 11 SCOOTER

FOR EVERY TWO TENAMENT WITH EACH TENAMENT HAVING CARPET AREA LESS THAN 30.00 SQMT
0 CAR + 4 SCOOTER
PROPOSED EIGHT TENAMENT LESS THAN 30.00 SQMT
HENCE REQUIRED PARKING 0 CAR + 16 SCOOTER

FOR EVERY TWO TENAMENT WITH EACH TENAMENT HAVING CARPET AREA EQUAL TO OR ABOVE 30 SQMT BUT LESS THAN 40 SQMT CARPET AREA
HENCE REQUIRED 1 CAR + 2 SCOOTER
TWO TENAMENT 30 TO 40 SQMT
HENCE REQUIRED PARKING 1 CAR + 2 SCOOTER

FOR EVERY TWO TENAMENT WITH EACH TENAMENT HAVING CARPET AREA EQUAL TO OR ABOVE 40 SQMT. BUT LESS THAN 80 SQMT CARPET AREA
HENCE REQUIRED 1 CAR + 5 SCOOTER
FOUR TENAMENT 40 TO 80 SQMT
HENCE REQUIRED PARKING 2 CAR + 10 SCOOTER

TOTAL PARKIG AREA
8 CAR + 45 SCOOTER

2.50 X 5.00 X 04	=	50.00 SQMT.
2.30 X 4.50 X 04	=	41.40 SQMT.
1.00 X 2.00 X 45	=	90.00 SQMT.
		181.50 SQMT.
VISITORS PARKING 5% 181.500 X 5%	=	9.075 SQMT
TOTAL REQUIRED PARKING AREA	=	190.575 SQMT.
PROPOSED STILT PARKING AREA	=	223.094 SQMT
PROPOSED OPEN PARKING AREA	=	69.780 SQMT
NET TOTAL PARKING AREA	=	292.874 SQMT

Architect/ Licensed Engineer/ Supervisor name and signature

Job No.	Drawing No.	Scale	Drawn by	Checked by
	120	1:100, 1:200	PRASHANT	S.K.

Registration No. of Architect/ License no. of Licensed Engineer/ Supervisor



PROPOSED GROUND FLOOR PLAN

SCALE - 1:100.



PROPOSED FIRST FLOOR PLAN

SCALE - 1:100.



PROPOSED SECOND FLOOR PLAN

SCALE - 1:100.



PROPOSED THIRD FLOOR PLAN

SCALE - 1:100.