N.M.R.D.A.
L.S. No. 33
L.S. Valid
Up to 31/12/2023



LAYOUT PLAN / SITE PLAN
SCALE 1:200

LAYOUT / SITE PLAN	01/17

PROJECT :
PROPOSED MULTIFAMILY RESIDENTIAL BUILDING PLAN FOR GROUP HOUSING SCHEME ON KH. NO. :- 174/2, P.H. NO. 12A MOUZA: BHOKARA , TAH. NAGPUR (R) DIST. :- NAGPUR.

BELONGING TO :-
M/S SUPREME URBAN REALITIES PVT.LTD.
THROUGH ITS AUTHORIZED
DIRECTOR MR. MURTAZA HAMZA KOTHAWALA

FINAL AREA STATEMENT

A)	NET PLOT AREA AREA FOR F.S.I. CALCULATION (Clause no.3.5 of UDCPR-2020) or as per layout plan	= 19733.315 SQ.MT	
B)	NET P-Line Built up Area (Clause no.6.6 of UDCPR-2020)	= 60991.532 SQ.MT	
C)	Dividing Factor 1.6 / 1.8 to arrive Basic FSI + Premium FSI = TDR :- P-line Area / 1.6 or 1.8	= 38119.707 SQ.MT	
D)	Permissible Ancillary FSI:- (Clause no.6.3, Table No.6G , Note-(i) of UDCPR-2020) (B-C)	= 22871.825 SQ.MT	PERMISSIBLE 22871.825 SQ.M.
E)	Permissible Basic FSI/Bup Area :- (1.1 x A) (1.10 X 19733.315) (Clause no.6.3, Table No.6G of UDCPR-2020)	= 21706.646 SQ.MT	1.1/21706.646 SQ.M.
F)	Permissible Additional FSI on premium :- (0.30 x A)(0.30 X 19733.315) (Clause no.6.3, Table No.6G of UDCPR-2020)	= 5919.994 SQ.MT	0.33/4573.072 SQ.M.
G)	Permissible TDR :- (A X Permissible TDR) (Clause no.6.3, Table No.6G of UDCPR-2020) 0.60 X 19733.315 = 11839.989 SQ.MT		0.60/11839.989 SQ.M.
H)	Permissible TDR for Road Widening with compliance of Clause no.7.2 & proforma - I of UDCPR-2020)	= 0.000 SQ.MT	NIL
I)	Total entitlement of FSI (D+E+F+G)	= 62338.454 SQ.MT	60991.532 SQ.M.
J)	maximum Building Potential on Plot/Land	= 63146.608 SQ.MT	60991.532 SQ.M.

TOTAL AREA STATEMENT

WING	B/UP AREA	NET B/UP AREA
TYPE 1 WING A	7111.972	7111.972
TYPE 1 WING B	7111.972	7111.972
TYPE 2 WING A	9759.367	9759.367
TYPE 2 WING B	9759.367	9759.367
TYPE 3 WING A	7023.732	7023.732
TYPE 4 WING A	10496.702	10496.702
TYPE 5 WING A	5111.893	5111.893
TYPE 6 WING A	4616.527	4616.527
TOTAL	60991.532	60991.532

REQUIRED PARKING AREA CALCULATION

TYPE OF TENAMENTS	NO. OF TENEMENTS	NO.OF CARS	NO.OF SCOOTERS
1) FOR 2 TENEMENTS HAVING **CARPET** AREA **ABOVE 40 SQ.M. AND UPTO 80 SQ.M.** (1 : 5)	486	243	1215
2) FOR EVERY TENEMENTS HAVING **CARPET** AREA **ABOVE 80 SQ.M. AND UPTO 150 SQ.M.**	118	118	354
TYPE4 WING A & TYPE3 WING A & TYPE-6A (1 : 3) 26 NOS 52 NOS 46 NOS TOTAL	604	361	1569
3) FOR EVERY 100 SQ.MT. **CARPET** AREA FOR SHOP AREA (2 : 6)	218.366	4	13
ADD 5% FOR VISITOR PARKING		18	79
TOTAL REQUIRED PARKING		383	1661
AS PER 8C TOTAL PARKING REQUIRED(0.7) FACTOR		268.1	1163
TOTAL PROVIDED PARKING		269	1170

TOTAL CONSTRUCTION AREA STATEMENT

WINGS	PROPOSED B/UP AREA	COVERED PARKING AREA SLAB	DEDUCTION B/UP+METER ROOM+TOILET+DUCT	NET COVERED PARKING SLAB	STAIRCASE TOWER & LIFT ROOM	WATER TANK O.H.W.T. & U.W.T.	PARKING SLAB AT PODIUM FLOOR	REFUGE AREA	STP AREA + WATCHMAN CABIN+E.S.S.+ O.W.C.+ D.G. SET	B/UP AREA FREE FROM FSI	TOTAL
EXISTING TYPE-1 WING - A & B	14223.944	1482.908	116.598	1366.310	118.368	405.197	0.000	39.356	485.3160	192.210	16345.3853
PROPOSED TYPE-2 WING - A & B	19518.734	4994.059	499.598	4494.462	274.918	332.951	3439.280	272.942		320.000	46482.371
PROPOSED TYPE-3 WING - A	7023.732									147.659	
PROPOSED TYPE-4 WING - A	10496.702									160.991	
PROPOSED TYPE-5 WING - A	5111.893	453.266	105.404	347.862	67.306	48.513	0.000	14.588		115.030	5705.222
PROPOSED TYPE-6 WING - A	4616.527	415.043	116.598	298.446	71.921	46.731	0.000	18.885		111.373	5163.883
TOTAL	60991.532	7345.307	838.197	6507.110	532.512	833.393	3439.280	345.771	485.316	1047.263	74182.178

TOTAL COVERED AREA :-

PROPOSED CONSTRUCTION AREA ON AMENITY SPACE = 4194.832 M²
PROPOSED CONSTRUCTION OF RESIDENTIAL = 74182.178 M²

TOTAL PROPOSED CONSTRUCTION AREA = 78377.010 M²

TOTAL NO. OF TENEMENTS

TYPE-1 WING-A = 80 NOS.
TYPE-1 WING-B = 80 NOS.
TYPE-2 WING-A = 104 NOS.
TYPE-2 WING-B = 104 NOS.
TYPE-3 WING-A = 52 NOS.
TYPE-4 WING-A = 104 NOS.
TYPE-5 WING-A = 40 NOS.
TYPE-6 WING-A = 40 NOS.

TOTAL NO OF FLATS = 604 NOS.

LEGEND :
PLOT BOUNDRY SHOWN AS
PROPOSED CONSTRUCTION SHOWN AS
EXISTING CONSTRUCTION SHOWN AS

NOTE :
ALL DIMENTIONS ARE IN METERUNLESS MENTIONED.

OWNER :
For Supreme Urban Realities Pvt. Ltd.
Director/Authorised Signatory
M/S SUPREME URBAN REALITIES PVT.LTD.
THROUGH ITS AUTHORIZED
DIRECTOR MR. MURTAZA HAMZA KOTHAWALA

ARCHITECT / ENGINEER :
Pawan Rajmangal Gupta
B.E. (Civil)
PLANNING BUILDING ENVIRONMENT
Lic No.N.A.T. BBL/A/R.D.A. BL.N.M.C./BS
Off. Shop No.1/15 Ground Floor,
Shriram Bhakti Tower, Datte Nagpur-440033
E-mail ID :pawan_r_gupta @yahoo.co.in
MOB. No.9823432949.

EMAIL ID - pawan_r_gupta@yahoo.co.in		MOBILE NO.9823432949	
DRG.NO.	SCALE	DATE	DRAWN BY
SUB-01	1 : 200	15/11/2022	P.GUPTA