





LAYOUT PLAN
SCALE - 1:500

PROPOSED LAYOUT OF
KH.NO.- 613/2



LOCATION PLAN
SCALE - NTS

NOTE:-


- x AREA UNDER LAYOUT SHOWN THUS
- x AREA UNDER OPEN SPACE SHOWN THUS
- x AREA UNDER AMENITY SPACE SHOWN THUS
- x RESIDENTIAL PLOTS SHOWN THUS
- x APPROACH ROAD SHOWN THUS

NOTE -

- ROW - HOUSES PLOTS = 2 TO 6, 9 TO 13, 16 TO 21, 24 TO 30, 33 TO 39, 42 TO 45
- SEMI-DETACHED PLOTS = 1, 7, 8, 14, 15, 22, 23, 31, 32, 40, 41, 46
- DETACHED PLOTS =


Nos.	Plot No.	Size (M)	Area (Sq.m.)	No of Plots	Rounding area of Road (sq.m.)	Net Area Of Each Plot (Sq.m.)	Total Area (Sq.M.)	Built Up Area On Prorata base Of Each (D*Factor Of FSI) Sq.M.	Front Road Width (M.)	Permissible Normal F.S.I.	Permissible B/Up Area On Normal FSI Each Plot Sq.M.
A	B	C	D	E	F=(C-E)	G=(D*F)	H=(F*1.65)	I	J	K=(H*J)	
1	1	1/2(8.00 + 8.95) X 15.05	127.54	1		127.54	127.54	210.44	12.00	1.00	210.44
2	2 TO 6 9 TO 13	6.65 X 15.05	100.08	10		100.08	1000.80	165.13	12.00	1.00	165.13
3	7, 8	8.50 X 15.05	127.92	2		127.92	255.84	211.07	12.00	1.00	211.07
4	14	1/2(9.10 + 8.30) X 15.05	130.93	1		130.93	130.93	216.03	12.00	1.00	216.03
5	15	1/2(11.05 + 10.30) X 14.30	152.65	1	6.05	146.60	146.60	241.89	12.00	1.00	241.89
6	16 TO 21	8.35 X 14.30	119.41	6		119.41	716.43	197.02	9.00	1.00	197.02
7	22	1/2(14.00 + 14.10) X 14.30	200.91	1		200.91	200.91	331.50	9.00	1.00	331.50
8	23	1/2(15.70 + 14.35) X 15.00	225.37	1		225.37	225.37	371.86	9.00	1.00	371.86
9	24 TO 29 34 TO 39	6.80 X 15.00	102.00	12		102.00	1224.00	168.30	9.00	1.00	168.30
10	30, 33	8.50 X 15.00	127.50	2		127.50	255.00	210.38	9.00	1.00	210.38
11	31	1/2(10.00 + 10.80) X 15.00	156.00	1	6.05	149.95	149.95	247.42	12.00	1.00	247.42
12	32	1/2(11.55 + 10.80) X 15.00	167.62	1	6.05	161.57	161.57	266.59	12.00	1.00	266.59
13	40	1/2(13.00 + 14.35) X 15.00	205.12	1		205.12	205.12	338.45	9.00	1.00	338.45
14	41	8.00 X 15.70	125.60	1		125.60	125.60	207.24	9.00	1.00	207.24
15	42 TO 45	7.00 X 15.70	109.90	4		109.90	439.60	181.34	9.00	1.00	181.34
16	46	1/2(9.30 + 8.50) X 15.70	139.73	1	6.05	133.68	133.68	220.57	12.00	1.00	220.57
	TOTAL			46			5498.94				3785.22

AREA CALCULATION (BY TRIANGULATION METHOD) AS PER MEASUREMENT SHEET




SR. NO.	DIMENSION	AREA (SQ.M.)
1	1/2(101.70 + 102.45) X 16.40	1674.03
2	1/2(63.35 + 60.65) X 135.90	8425.80
	TOTAL	10099.83
	SAY	10100.00

AREA CALCULATION (BY TRIANGULATION METHOD) OPEN SPACE



SR. NO.	DIMENSION	AREA (SQ.M.)
1	1/2(22.85 + 20.05) X 47.20	1012.44

AREA CALCULATION (BY TRIANGULATION METHOD) AMENITY SPACE



SR. NO.	DIMENSION	AREA (SQ.M.)
1	1/2(19.58 + 19.50) X 51.70	1010.21

FINAL DEMARCATED RESIDENTIAL LAYOUT
PLAN ON KH.NO. - 613/2, P.H. NO. - 28,
MOUZA - BELA, TAH. - UMRED, DIST.- NAGPUR.
BELONGING TO :- SHRI.- RITESH KAILASHPRASAD SAXENA

STAMP OF APPROVAL OF PLAN OF SANCTIONING AUTHORITY



जो.क.प्रस्तुत/वित्त./कवि 14.01/22
रामक. 316/एनपी-28/20.21-22

वित्त. अधिकारी नमस्कर

PROFORMA - I AREA STATEMENT			
1	AREA OF LAND OF KH.NO. 613/2 (Minimum area of a,b,c, to be considered)	10100.00	SQ.M.
a)	AS PER OWNERSHIP DOCUMENT (7/12, EXTRACT)	10100.00	SQ.M. (1.01 H)
b)	AS PER MEASUREMENT SHEET	10100.00	SQ.M.
c)	AS PER SITE	10100.00	SQ.M.
2	DEDUCTIONS FOR		SQ.M.
a)	PROPOSED D.P./D.P. ROAD WIDENING AREA	0.00	SQ.M.
b)	ANY D.P. RESERVATION AREA	0.00	SQ.M.
c)	NATURAL WATER COURSE AREA	0.00	SQ.M.
	TOTAL (a+b+c)	0.00	SQ.M.
3	BALANCE AREA OF PLOT (1 - 2)	10100.00	SQ.M. 100%
4	AMENITY SPACE		
a)	REQUIRED	1010.00	SQ.M. 10.00%
b)	PROPOSED	1010.21	SQ.M. 10.00%
5	NET PLOT AREA (3-4b)	9089.79	SQ.M.
6	RECREATIONAL OPEN SPACE		
a)	REQUIRED	1010.00	SQ.M. 10.00%
b)	PROPOSED	1012.44	SQ.M. 10.02%
8	INTERNAL ROAD AREA	2578.41	SQ.M. 25.53%
9	SERVICE ROAD AND HIGHWAY WIDENING	0.00	SQ.M.
10	PLOTTABLE AREA	5498.94	SQ.M. 54.45%
11	PRO-RATA FACTOR FOR FSI CALCULATION ON LAYOUT PLOTS (5/10)	1.65	SQ.M.

CERTIFICATE :
THE ABOVE MENTIONED PLANS ARE PREPARED BY ME AS PER UDPCR SIGNATURE OF ARCHITECT / LICENSED ENGINEER / SUPERVISOR.

NAME - UMESH M. LAMGE

LICENSE NO. - CA/95/18907

CONTACT NO. - 9822566554

DATED. - 01/01/2021 TO 31/12/2023

(*) NAME OF THE ACT OF THE PLANNING AUTHORITY, IF ANY, BE MENTIONED.

CERTIFICATE OF AREA:
CERTIFIED THAT THE PLOT UNDER REFERENCE WAS SURVEYED BY ME ON 31/07/2021 AND THE DIMENSIONS OF SIDES ETC. OF PLOTS STATED ON PLAN ARE AS MEASURED ON SITE AND THE AREA SO WORKED OUT TALLIES WITH THE AREA STATED IN DOCUMENT OF OWNERSHIP / T.P. SCHEME RECORDS / LAND RECORDS DEPARTMENT / CITY SURVEY RECORDS.

UMESH M. LAMGE
B.Arch. (Hons)
ARCHITECTS & INTERIOR DESIGNERS
Reg.No. CA/95/18907
NMC Lic No.: R-90
NIT Lic No.: 865

OWNER'S DECLARATION :
I/WE UNDERSIGNED HEREBY CONFIRM THAT I/WE WOULD ABIDE BY PLANS APPROVED BY AUTHORITY/COLLECTOR. I/WE WOULD EXECUTE THE STRUCTURE AS PER APPROVED PLANS. ALSO I/WE WOULD EXECUTE THE WORK UNDER SUPERVISION OF PROPER TECHNICAL PERSON SO AS TO ENSURE THE QUALITY AND SAFETY AT WORK SITE.
OWNER(S) NAME AND SIGNATURE : SHRI. KAILASHPRASAD SAXENA

OWNER'S SIGN :

ARCHITECT'S SIGN :



या कार्यालयाचे पत्र क्र. अकावेक/अंतिम मंजूरी/खे. 29/2/22
ता. 29/2/22 म. नं. 293/22 म. नं. 293/22
दि. 29/2/22 म. नं. 293/22 म. नं. 293/22
प्रयोजनार्थ सिमांकित अभिन्यासास आलेले मंजूरी
करण्यात येत आहे. (Recommended for Sanction)
सहायक संचालक
नगर स्वचा, नागपूर

SHRI.- RITESH KAILASHPRASAD SAXENA

UMESH M. LAMGE
B.Arch. (Hons)
ARCHITECTS & INTERIOR DESIGNERS
Reg.No. CA/95/18907
NMC Lic No.: R-90
NIT Lic No.: 865

UMESH M. LAMGE
B. ARCH.
ARCHITECT & INTERIOR DESIGNER
FIFTH FLOOR, DAYA CHAMBERS,
AJNI SQ., WARDHA ROAD, NAGPUR