

AREA STATEMENT	SQ. MT.
FOR DETAILED AREA CALCULATION REFER AREA KEY PLANS	
1 PLOT AREA =	6428.366
2 F. S. I. =	2.50
3 PERMISSIBLE F. S. I. =	16070.915
4 ADD INTERNAL ROAD AREA OF SANCTION LAYOUT	4600.000
4 MAX. PERMISSIBLE B/UP AREA	20670.915
5 PROPOSED B/UP AREA	
BASEMENT FLOOR	192.784
GROUND FLOOR	235.183
FIRST FLOOR	1266.402
SECOND FLOOR	1266.402
THIRD FLOOR	1266.402
FOURTH FLOOR	1266.402
FIFTH FLOOR	1266.402
SIXTH FLOOR	1266.402
SEVENTH FLOOR	1266.402
EIGHTH FLOOR	1266.402
NINTH FLOOR	1266.402
TENTH FLOOR	1266.402
ELEVENTH FLOOR	1266.402
TWELVTH FLOOR	1266.402
THIRTEENTH FLOOR	1266.402
FOURTEENTH FLOOR	1266.402
FIFTEENTH FLOOR	1266.402
SIXTEENTH FLOOR	1266.402
6 TOTAL PROPOSED B/UP AREA	20863.399

PARKING AREA STATEMENT

	CARS	SCOOTERS	CYCLES
PARKING AREA REQUIRED FOR 2 TENAMENT HAVING CARPET BETWEEN 60-100 SQM. NO. OF UNITS = 224	112 Nos.	448 Nos.	224 Nos.
PARKING AREA REQUIRED FOR 224 TENAMENTS	112 NOS.	448 Nos.	224 Nos.
PARKING AREA PROVIDED	112 NOS.	448 Nos.	448 Nos.

VISITORS PARKING CALCULATION
FOR RESIDENTIAL :- 2% OF PARKING AREA REQUIRED
= 2/100 OF (56 x 2.500 x 5.000 + 56 x 2.500 x 4.800 + 56 x 2.500 x 5.000 x 224 x 1.000)
= 5.6/100 OF 115.080 SQ. MT.
= 115.080 SQ. MT.
VISITORS PARKING AREA PROVIDED = 178.686 SQ. MT.

CERTIFICATE OF AREA

CERTIFIED THAT I HAVE SURVEYED THE PLOT UNDER REFERENCE ON 29/05/2018 AND THAT THE DIMENSIONS OF THE SIDES, ETC. OF THE PLOT STATED ON THE PLAN ARE AS MEASURED ON THE SITE AND THE AREA SO WORKED OUT IS 6428.366 SQUARE METRES AND TALLIES WITH THE AREA STATED IN THE DOCUMENT OF OWNERSHIP / TOWN PLANNING SCHEME RECORDS.

ARCHITECT & PLANNER (RP)
Nagpur Housing & Area Development Board, Nagpur.
SIGN OF ARCHITECT/ENGINEER/SUPERVISOR

OFFICE OF THE CORPORATION OF THE CITY NAGPUR.
Building Permit No. 38/BP/Nagpur/ Dated: 23/04/2019
SANCTIONED
subject to conditions mentioned in the building permit
Assistant Director Town Planning Nagpur Municipal Corporation

The Rain Water Harvesting is required to be provided as per Directon of Govt. of Maharashtra No. TPB 432001/2133 CR - 230/01/UD-II, dated 10th March, 2005 as per schedule for every 300 sq.mtrs. built-up area The system may be by open well 1 mtr. dia & mtrs. deep with filteration chamber for every 300 sq.mtr. built-up area. Other options mentioned in the schedule may be adopted
a) The authority may impose a levy of Rs. 1000/- per annum for every 100 sq.mts. of built-up area, for failure of the owner of the building.

PROVISIONS For Solar Water Heating System:
Solar Water Heating System should be installed on the building for the following uses at the per capita capacity mentioned as under.

Type of Buildings	Per Capita Capacity Recommended
1) Hospitals	-100 Ltrs./day/person.
2) Hotels	---150 Ltrs./day/person.
3) Hostel & other such buildings	---25 Ltrs./day/person.
4) Residential	---25 Ltrs./day/person.

If the provisions as above is not made, the occupancy certificate will not be issued from NMC

SEISMIC ANALYSIS OF THE BUILDING FOR EARTHQUAKE BE SUBMITTED WITH STRUCTURAL DESIGN & DRAWING DULY CHECKED FROM VNIT FOR NMC RECORD, BEFORE ONE MONTH OF COMMENCEMENT OF CONSTRUCTION OR AFTER THREE MONTHS FROM THE SANCTION OF BUILDING PLANS WHICHEVER IS EARLIER.

Executive Engineer Nagpur Hsg. & Area Dev. Board, Nagpur.
CHIEF OFFICER Nagpur Housing & Area Development Board, Nagpur.

NAGPUR HOUSING & AREA DEVELOPMENT BOARD, NAGPUR.

THIS DRAWING IS THE PROPERTY AND COPYRIGHT OF Ar. RAJESH JAISWAL
IT SHALL NOT BE COPIED, REPRODUCED OR USED WITHOUT WRITTEN CONSENT
DO NOT SCALE THE DRAWING

NOTE :-
THIS DRAWING IS SOLELY PREPARED FOR OBTAINING APPROVAL/SANCTIONING FROM NAGPUR MUNICIPAL CORPORATION & SHALL NOT BE USED FOR CONSTRUCTION PURPOSE.

PROJECT: PROPOSED RESIDENTIAL APARTMENT BUILDING AT PLOT NO.:- 2, S. No. 101, 159, EMPRESS MILL No. 5, MOUZA:- NAGPUR, SUBHASH ROAD, NAGPUR.

ARCHITECT SIGN

Sankalp Creations'
Rajesh Jaiswal
ARCHITECT
207, Cotton Market,
Ghat Road, Nagpur-440 018.
CoA/91/18807, NMC/N-13, NIT-832

Ar. RAJESH JAISWAL
ARCHITECTURAL CONSULTANTS & INTERIOR DESIGNERS
207, COTTON MARKET, GHAT ROAD, NAGPUR.
TEL. 2734148, 2734149

JOB NO. | DRG NO. | SCALE | DRAWN BY | CHECKED BY
DR | 1:100 1:200