



FRONT ELEVATION
SCALE 1:100




SECTION A-A'
SCALE 1:100



SECTION B-B'
SCALE 1:100

SECTION VIEW - RESIDENTIAL

PLOT NO.
8,9,10 & 11





SITE PLAN
SCALE 1:100

BUILDING	FLOORS	RESIDENTIAL FSI AREA COMM.	RESI.	IND.	SPECIAL	MEZZ.	BALCONY PROP.	TERRACE PROP.	LIFT	LIFTWELL	DUCT	VENT SHAFT	Other Deduction	TOTAL FSIAREA
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	0.00	2795.66	0.00	0.00	0.00	458.92	0.00	0.00	38.78	18.06	0.00	0.00	2738.82
RESIDENTIAL	GROUND FLOOR	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
RESIDENTIAL	Total	0.00	2795.66	0.00	0.00	0.00	458.92	0.00	0.00	38.78	18.06	0.00	0.00	2738.82

FSI DETAILS


9 Index	Basic FSI (on serial no 1)	Premium FSI (on serial no 1)	TDR (on serial no 1)	Incentive FSI for green building If Applicable (on basic FSI)	Ancillary Area 60% of (2+3+4+5)	Ancillary Area 80% of (2+3+4+5)	Total	Inclusive Housing (20%) If Applicable	Drawing Value
9.1 Permissible Index	1.57	0.30	0.70	0.00	0.00	0.00	2.57	0.00	0.00
9.2 Existing Consumed Index	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9.3 Balance Index to be Consume	1.57	0.30	0.70	0.00	0.00	0.00	0.00	0.00	0.00
9.4 Total Permissible PLine Area()	1606.04	306.30	714.70	0.00	1026.55	0.00	3653.59	0.00	0.00
9.5 Proposed P Line Area (Should not exceed 9.4)	1606.04	106.50	0.00	0.00	1026.28	0.00	2738.82	0.00	2738.82
9.6 Index Consumed	1.57	0.10	0.00	0.00	0.00	0.00	1.67	0.00	0.00





Project Details

Building Type - Building Development
Zone Type - Residential Zone with Shop line. (R-2)
Location - Non-Congested
Ward No - A
Plot No. - 4,5,6,7
Cts No./Servey No. - 0
Sheet No. - 1
Zone Number: HINGNA
Ward Name : TURKMARI
Prorata Value : 1.43



Carpet Area Table

Building Name	Floor Name	Carpet name	Tenement No	Carpet Area	Enclosed Balcony Area	Normal Balcony Area	Total Carpet Area
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	101;201;301;401;501; 601;701	7	53.42	6.53	0.00	59.95
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	102;202;302;402;502; 602;702	7	58.37	2.26	0.00	60.63
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	103;203;303;403;503; 603;703	7	63.42	2.40	0.00	65.82
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	104;204;304;404;504; 604;704	7	55.43	7.02	0.00	62.45

Parking Check (Table 8B)

Building Name	USE	REQ. RATIO car	REQ. RATIO Scooter	NO.OF Tena/Area	PRP. RATIO car	PRP. RATIO Scooter
RESIDENTIAL	Residential	1	5	28	14.00	70.00
Total	-	-	-	-	14.00	70.00
Visitors parking(5%)	-	-	-	-	0.70	3.50
Total	-	-	-	-	14.70	73.50

Parking Check As Per Multiplying Factor : 0.70


Building Name	Required Car/Mini Bus	Required Scooter	Proposed Car/Mini Bus	Proposed Scooter	Status
Total	10	51	14	68	OK
		20% EV	3	13	


SCHEDULE OF OPENING:

BLD NAME	NAME	LENGTH	HEIGHT	NOS.
RESIDENTIAL	V1	0.60	0.60	8
RESIDENTIAL	W	1.80	1.20	1
RESIDENTIAL	W2	1.20	0.90	1
RESIDENTIAL	W3	0.60	0.90	1
RESIDENTIAL	GW	1.20	1.20	1

SCHEDULE OF OPENING:

BLD NAME	NAME	LENGTH	HEIGHT	NOS.
RESIDENTIAL	D	1.20	2.10	1
RESIDENTIAL	D2	0.80	2.10	1
RESIDENTIAL	D1	0.90	2.10	1
RESIDENTIAL	SD	1.50	2.10	1
RESIDENTIAL	FRD	1.80	2.10	1





LEGENDS:

Signature Not Verified

Digitally signed by SANJAY NARENDRA CHIMURKAR
Date: 2023.05.08 16:21:05 IST
Reason: Approved Drawing Plan
Location: Nagpur Metropolitan Region Development Authority

Executive Engineer
Date: 27/06/2023

Deputy Engineer
Date: 27/06/2023

Sectional Engineer
Date: 26/06/2023

PLOT AREA - 1021.01
PRORATA - 1.43
BASIC F.S.I. - 1.1
BASIC F.S.I. AREA = 1021.01 X 1.43 X 1.1
= 1606.04 SQ.M.
P-LINE AREA = 2738.82 SQ.M.
ANCILLARY = P-LINE - P-LINE/1.6
= 1026.28 SQ.M.
PREMIUM = 2738.82 - 1026.28
= 1606.04
= 106.5 SQ.M.

PROPOSED SUBMISSION PLAN FOR RESIDENTIAL FLAT SCHEME ON PLOT NO. 4,5,6, & 7, KH. NO 76, PH. NO. 71 , MOUZA- TURKMARI, , TAH. - HINGNA & DISTT. - NAGPUR FOR
M/S NIVI INFRASTRUCTURE THROUGH ROHAN RAROKAR VINAYAKRAO RAROKAR

Proforma I : Area Statement	
1. Area of plot (Minimum area of a, b, c to be considered) or area of subplot with sanctioned layout No. and subplot No.	1021.01
(a) As per ownership document (7/12, CTS extract)	1021.01
(b) as per TLR or City Survey measurement sheet	1021.01
(c) as per Demarcated drawing area	1024.17
LESS	-
2.Area not in possession	0.00
3. Entire area (1-2)	1021.01
4.Deductions for	-
(a) Proposed D.P./ D.P. Road widening Area /Service Road / Highway widening	0.00
(b) Any D.P. Reservation area	0.00
(Total a+b)	0.00
5.Balance area of plot (3-4)	1021.01
6. Amenity Space	0.00
(Applicable if (1) > 20000 sqmt	-
(Required -(a) Upto 20000 sqmt - Nil	-
(b) Above 20000 sqmt - (a) + 5 % of Total area	0.00
7. Net Plot Area (5-6)	1021.01
8. Recreational Open Space	-
(a) If area (6) is more than 4000 sqmt - 10 % of (6) is required.	0.00
Proposed ____	0.00
(b) If area is less than 4000 sqmt -Check -	-
i) If it is full number like 1,2,125,419,etc. As per 7.12 abstract or City Survey Number - No Recreational open space is required	-
ii) If it is subdivision like 1/2 ,2/5 , 125/1 419/1 etc.then recreational open space is required.	-
(A) 10 % Subject to minimum 200 sqmt	0.00
Proposed ____	0.00
(B) Exemption to leave open space subject to availing basic F.S.I of 75 %	-
(C) Exemption to leave open space subject to payment of 10 % land value of land at (7) as per annual statement of rate.	-

Certificate of Area:
Certified that the plot under reference was surveyed by me on 2023-01-07 and the dimensions of sides etc. of plot stated onplan are as measured on site and the area so worked out tallies with the area stated in document of Ownership/ T.P. Scheme Records/Land Records Dept/City Survey records.
Signature
(Name of Architect/ Licensed Engineer/ Supervisor.)

Owner's Declaration -
I/We undersigned hereby confirm that I/We would abide by plans approved by Authority / Collector. I/We would execute the structure as per approved plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site.

Owner (s) name and signature
Architect/ Licensed Engineer/ Supervisor name and signature
Job No.

Name Of : Owner NIVI INFRASTRUCTURE THROUGH ROHAN RAROKAR VINAYAKRAO RAROKAR

Postal Address : plot no 1839,bhandara road,near santoshi mata mandir,Bhandewadi,Pardi,Nagpur-440035,Maharashtra

Phone No.:9372067666

DESCRIPTION OF PROJECT :
Type of Proposal : Residential
BUILDING ON CTS. NO./SURVEY NO.-0

SITE ADDRESS :
RESIDENTIAL FLAT SCHEME ON PLOT NO. 4,5,6, 7 KH. NO 76, PH. NO. 71, MOUZA- TURKMARI, , TAH. - HINGNA DISTT. - NAGPUR


Name Of Architect : PRIYADARSHAN NAGPURKAR

LOGO | ADDRESS OF OFFICE
OFFICE :-
Mahal Nagpur

OWNERS SIGN - Verified by applicant
TECHNICAL PERSON SIGN - Signature Not Verified
Digitally signed by PRIYADARSHAN NAGPURKAR
Date: 2023.05.08 16:21:05 IST
Reason: Technical Person
Location: Nagpur Metropolitan Region Development Authority

SCALE - 1:100 | Date: 07/01/23
JOB NO - NMRDA-22-03149 | CHECK BY - -


SUBMISSION DRAWING



GROUND FLOOR

GROUND FLOOR PLAN

SCALE 1:100



TYPICAL FLOOR PLAN 1ST TO 7TH FLOOR

SCALE 1:100

TYPICAL 1ST TO 7TH FLOOR

RESIDENTIAL

BUILT-UP AREA CALCULATION FOR GROUND FLOOR RESIDENTIAL

AREA NAME	LENGTH	WIDTH	Area(Sq.M)
BLOCK	3.47	3.47	28.86
		BLOCK AREA TOTAL =28.86Sq.M	
Duct4	-	-	1.29
		TOTAL Deduction =1.29Sq.M	
		Net BuiltUp Area =27.57 Sq.M	

BUILT-UP AREA CALCULATION GROUND FLOOR RESIDENTIAL

BUILT-UP AREA CALCULATION FOR GROUND FLOOR RESIDENTIAL

AREA NAME	LENGTH	WIDTH	Area(Sq.M)
BLOCK	10.27	2.80	28.75
		BLOCK AREA TOTAL =28.75Sq.M	
Duct3	-	-	1.29
		TOTAL Deduction =1.29Sq.M	
		Net BuiltUp Area =27.46 Sq.M	

BUILT-UP AREA CALCULATION GROUND FLOOR RESIDENTIAL

BUILT-UP AREA CALCULATION TYPICAL 1ST TO 7TH FLOOR RESIDENTIAL

BUILT-UP AREA CALCULATION FOR TYPICAL 1ST TO 7TH FLOOR RESIDENTIAL

AREA NAME	LENGTH	WIDTH	Area(Sq.M)
BLOCK	41.55	10.27	399.38
		BLOCK AREA TOTAL =399.38Sq.M	
LiftWell2	-	-	2.77
LiftWell1	-	-	2.77
Duct2	-	-	1.29
Duct1	-	-	1.29
		TOTAL Deduction =8.12Sq.M	
		Net BuiltUp Area =391.26 Sq.M	

STATEMENT OF DISTRIBUTION OF FSI

PLOT NO.	PLOT AREA SQ.M.	TANGENT DEDUCTION	REMAINING PLOT AREA	B/UP AREA ON PRO-RATA BASIS	PERMISSIBLE B/UP AREA
4	255.27		255.27	365.03	401.54
5	252.04		252.04	360.41	396.45
6	248.81		248.81	355.79	391.37
7	274.50	9.61	264.89	378.79	416.67
TOTAL	1030.62		1021.01	1460.02	1606.03

SCHEDULE OF OPENINGS

TYPE	SIZE	DESCRIPTION
D	1.200X2.100	T.W. DOUBLE PANELLED DOOR
D1	0.900X2.100	SINGLE PANELLED FLUSH DOOR
D2	0.800X2.100	SINGLE PANELLED FLUSH DOOR
SD	1.500X2.100	SLIDING DOOR
FRD	1.800X2.100	FIRE RESISTENT DOOR
W	1.800X1.200	ALU SLIDING WINDOW
W1	1.200X1.200	ALU SLIDING WINDOW
W2	1.200X0.900	ALU SLIDING WINDOW
W3	0.600X0.900	ALU SLIDING WINDOW
GW	1.200X1.200	GLAZED WINDOW
V1	0.600X0.600	ALU LOUVERED VENTILATOR

RESIDENTIAL

BUILDING	FLOORS	FSI AREA					BALCONY	TERRACE	LIFT	LIFTWELL	DUCT	VENT	Other	TOTAL
		COMM.	RESI.	IND.	SPECIAL	MEZZ.	PROP.	PROP.	SHAFT			Deduction	Deduction	FSIAREA
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	0.00	2795.66	0.00	0.00	0.00	458.92	0.00	0.00	38.78	18.06	0.00	0.00	2738.82
RESIDENTIAL	GROUND FLOOR	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
RESIDENTIAL	Total	0.00	2795.66	0.00	0.00	0.00	458.92	0.00	0.00	38.78	18.06	0.00	0.00	2738.82

FSI DETAILS

9 Index	Basic FSI (on serial no 1)	Premium FSI (on serial no 1)	TDR (on serial no 1)	Incentive FSI for green building If Applicable (on basic FSI)	Ancillary Area 60% of (2+3+4+5)	Ancillary Area 80% of (2+3+4+5)	Total	Inclusive Housing (20%) If Applicable	Drawing Value
9.1 Permissible Index	1.57	0.30	0.70	0.00	0.00	0.00	2.57	0.00	0.00
9.2 Existing Comsumed Index	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9.3 Balance Index to be Consume	1.57	0.30	0.70	0.00	0.00	0.00	0.00	0.00	0.00
9.4 Total Permissible PLine Area()	1606.04	306.30	714.70	0.00	1026.55	0.00	3653.59	0.00	0.00
9.5 Proposed P Line Area (Should not exceed 9.4)	1606.04	106.50	0.00	0.00	1026.28	0.00	2738.82	0.00	2738.82
9.6 Index Consumed	1.57	0.10	0.00	0.00	0.00	0.00	1.67	0.00	0.00

Carpet Area Table

Building Name	Floor Name	Carpet name	Tenement No	Carpet Area	Enclosed Balcony Area	Normal Balcony Area	Total Carpet Area
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	101;201;301;401;501; 601;701	7	53.42	6.53	0.00	59.95
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	102;202;302;402;502; 602;702	7	58.37	2.26	0.00	60.63
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	103;203;303;403;503; 603;703	7	63.42	2.40	0.00	65.82
RESIDENTIAL	TYPICAL 1ST TO 7TH FLOOR	104;204;304;404;504; 604;704	7	55.43	7.02	0.00	62.45

Parking Check (Table 8B)

Building Name	USE	REQ. RATIO		NO.OF Tena/Area	PRP. RATIO	
		car	Scooter		car	Scooter
RESIDENTIAL	Residential	1	5	28	14.00	70.00
Total	-	-	-	-	14.00	70.00
Visitors parking(5%)	-	-	-	-	0.70	3.50
Total	-	-	-	-	14.70	73.50

Parking Check As Per Multiplying Factor : 0.70


Building Name	Required		Proposed		Status
	Car/Mini Bus	Scooter	Car/Mini Bus	Scooter	
Total	10	51	14	68	OK
		20% EV	3	13	

SCHEDULE OF OPENING:

BLD NAME	NAME	LENGTH	HEIGHT	NOS.
RESIDENTIAL	V1	0.60	0.60	8
RESIDENTIAL	W	1.80	1.20	1
RESIDENTIAL	W2	1.20	0.90	1
RESIDENTIAL	W3	0.60	0.90	1
RESIDENTIAL	GW	1.20	1.20	1

SCHEDULE OF OPENING:


BLD NAME	NAME	LENGTH	HEIGHT	NOS.
RESIDENTIAL	D	1.20	2.10	1
RESIDENTIAL	D2	0.80	2.10	1
RESIDENTIAL	D1	0.90	2.10	1
RESIDENTIAL	SD	1.50	2.10	1
RESIDENTIAL	FRD	1.80	2.10	1



CARPET AREA CALCULATION 101,201,301,401,501,601,701

CARPET AREA CALCULATION FOR 101,201,301,401,501,601,701,


A -	7.647 X 6.669 =	50.997	SQ.M.
B -	3.000 X 0.600 =	1.800	SQ.M.
C -	1.400 X 3.070 =	4.298	SQ.M.
D -	1.400X 1.999 =	2.798	SQ.M.
	TOTAL =	59.893	SQ.M.



CARPET AREA CALCULATION 102,202,302,402,502,602,702

CARPET AREA CALCULATION FOR 102,202,302,402,502,602,702


A -	7.260 X 6.869 =	49.868	SQ.M.
B -	3.060 X 0.600 =	1.836	SQ.M.
C -	2.600 X 0.600 =	1.560	SQ.M.
D -	1.400 X 3.070 =	4.298	SQ.M.
E -	1.400 X 2.199 =	3.078	SQ.M.
	TOTAL =	60.640	SQ.M.



CARPET AREA CALCULATION 103,203,303,403,503,603,703,

CARPET AREA CALCULATION FOR 103,203,303,403,503,603,703


A -	7.600 X 6.970 =	52.972	SQ.M.
B -	2 X 3.000 X 0.600 =	3.600	SQ.M.
C -	1.400 X 3.070 =	4.298	SQ.M.
D -	1.400 X 2.300 =	3.220	SQ.M.
E -	5.800 X 0.300 =	1.740	SQ.M.
	TOTAL =	65.83	SQ.M.




CARPET AREA CALCULATION 104,204,304,404,504,604,704


CARPET AREA CALCULATION FOR 104,204,304,404,504,604,704

A -	7.242 X 7.270 =	52.649	SQ.M.
B -	3.042 X 0.600 =	1.825	SQ.M.
C -	1.400 X 3.070 =	4.298	SQ.M.
D -	1.400 X 2.600 =	3.640	SQ.M.
	TOTAL =	62.412	SQ.M.





SOLAR WATER HEATING SYSTEM



LEGENDS:

EXISTING WORK SHOWN IN BLACK
PROPOSED WORK SHOWN RED
EXISTING WORK TO BE DEMOLISHED LIGHT BUFF LINE SHOWN BLUE DOTTED
EXISTING DOOR & WINDOW SHOWN YELLOW
TERRACE SHOWN GREEN YELLOW
EXISTING WORK BLUE HATCHED

Project Details

Building Type - Building Development	
Zone Type - Residential Zone with Shop line. (R-2)	
Location - Non-Congested	
Ward No - A	
Plot No. - 4,5,6,7	
Cts No./Servey No. - 0	
Sheet No. - 1	
Zone Number:	HINGNA
Ward Name :	TURKMARI
Prorata Value :	1.43

Signature Not Verified

Digitally signed by SANJAY NARENDRA CHIMURKAR
Date: 2023.05.08 16:21:06 IST
Reason: Approved Drawing Plan
Location: Nagpur Metropolitan Region Development Authority


Executive Engineer Date: 27/06/2023

Deputy Engineer Date: 27/06/2023

Sectional Engineer Date: 26/06/2023

PLOT AREA	- 1021.01
PRORATA	- 1.43
BASIC F.S.I.	- 1.1
BASIC F.S.I. AREA	= 1021.01 X 1.43 X 1.1 = 1606.04 SQ.M.
P-LINE AREA	= 2738.82 SQ.M.
ANCILLARY	= P-LINE - P-LINE/1.6 = 1026.28 SQ.M.
PREMIUM	= 2738.82 - 1026.28 = 1606.04 = 106.5 SQ.M.

PROPOSED SUBMISSION PLAN FOR RESIDENTIAL FLAT SCHEME ON PLOT NO. 4,5,6, & 7, KH. NO 76, PH. NO. 71 , MOUZA- TURKMARI, , TAH. - HINGNA & DISTT. - NAGPUR FOR M/S NIVI INFRASTRUCTURE THROUGH ROHAN RAROKAR VINAYAKRAO RAROKAR



PROPOSED SITE

Proforma 1 : Area Statement	
7. Area of plot (Minimum area of a, b, c to be considered) or area of subplot with sanctioned layout No. and subplot No.	1021.01
(a) As per ownership document (7/12, CTS extract)	1021.01
(b) as per TILR or City Survey measurement sheet	1021.01
(c) as per Demarcated drawing area	1024.17
LESS	
2.Area not in possession	0.00
3. Entire area (1-2)	1021.01
4.Deductions for	-
(a) Proposed D.P./ D.P. Road widening Area /Service Road / Highway widening	0.00
(b) Any D.P. Reservation area	0.00
(Total a+b)	0.00
5.Balance area of plot (3-4)	1021.01
6. Amenity Space	0.00
(Applicable if (1) > 20000 sqmt	-
(Required -(a) Upto 20000 sqmt - Nil	-
(b) Above 20000 sqmt - (a) + 5 % of Total area	0.00
7. Net Plot Area (5-6)	1021.01
8. Recreational Open Space	-
(a) If area (6) is more than 4000 sqmt - 10 % of (6) is required.	0.00
Proposed ____	0.00
(b) If area is less than 4000 sqmt -Check -	-
(i) If it is full number like 1,2,125,419,etc. As per 7.12 abstract or City Survey Number - No Recreational open space is required	-
(ii) If it is subdivision like 1/2 ,2/5 , 125/1 419/1 etc.then recreational open space is required.	-
(A) 10 % Subject to minimum 200 sqmt	0.00
Proposed	0.00
(B) Exemption to leave open space subject to availing basic F.S.I. of 75 %	-
(C) Exemption to leave open space subject to payment of 10 % land value of land at (7) as per annual statement of rate.	-

Certificate of Area:
Certified that the plot under reference was surveyed by me on 2023-01-07 and the dimensions of sides etc. of plot stated onplan are as measured on site and the area so worked out tallies with the area stated in document of Ownership/ T.P. Scheme Records/Land Records Department/City Survey records.
Signature
(Name of Architect/ Licensed Engineer/ Supervisor.)

Owner's Declaration -
I/We undersigned hereby confirm that I/We would abide by plans approved by Authority / Collector. I/We would execute the structure as per approved plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site.

Owner (s) name and signature
Architect/ Licensed Engineer/ Supervisor name and signature
Job No.

Name Of : Owner NIVI INFRASTRUCTURE THROUGH ROHAN RAROKAR VINAYAKRAO RAROKAR

Postal Address : plot no 1839,bhandara road,near santoshi mata mandir,Bhandewadi,Pardi,Nagpur-440035,Maharashtra

Phone No. 9372067666

DESCRIPTION OF PROJECT :
Type of Proposal : Residential
BUILDING ON CTS. NO./SURVEY NO.-0

SITE ADDRESS :
RESIDENTIAL FLAT SCHEME ON PLOT NO. 4,5,6, 7 KH. NO 76, PH. NO. 71, MOUZA- TURKMARI, , TAH. - HINGNA DISTT. - NAGPUR

Name Of Architect : PRIYADARSHAN. NAGPURKAR

LOGO	ADDRESS OF OFFICE : OFFICE : Mahal Nagpur
OWNERS SIGN - Verified by applicant	TECHNICAL PERSON SIGN Signature Not Verified
SCALE - 1:100	Date: 07/01/23
JOB NO - NMRDA-22-03149	CHECK BY - -

SUBMISSION DRAWING