

GROUND FLOOR PLAN



GROUND FLOOR BUILT UP AREA CALCULATION

A	3.600	X 3.750	X 1.00	=	13.500 SQM.
B	3.800	X 4.100	X 1.00	=	15.580 SQM.
C	8.500	X 2.500	X 1.00	=	21.250 SQM.
D	3.800	X 4.100	X 1.00	=	15.580 SQM.
E	3.600	X 3.750	X 1.00	=	13.500 SQM.
F	3.600	X 3.750	X 1.00	=	13.500 SQM.
G	3.800	X 4.100	X 1.00	=	15.580 SQM.
H	8.500	X 2.500	X 1.00	=	21.250 SQM.
I	3.800	X 4.100	X 1.00	=	15.580 SQM.
J	3.600	X 3.750	X 1.00	=	13.500 SQM.
TOTAL				=	158.820 SQM.
DEDUCTIONS					
1	1.350	X 1.425	X 1.00	=	1.924 SQM.
2	1.993	X 2.700	X 1.00	=	5.381 SQM.
3	3.300	X 4.650	X 1.00	=	15.345 SQM.
4	3.300	X 4.650	X 1.00	=	15.345 SQM.
5	1.986	X 2.700	X 1.00	=	5.362 SQM.
6	1.350	X 1.425	X 1.00	=	1.924 SQM.
TOTAL DEDUCTION				=	45.281 SQM.
NET AREA				=	113.539 SQM.

OFFICE OF THE CORPORATION OF THE CITY NAGPUR.
Building Permit No.: 5118/Nagpur/
SANCTIONED
subject to condition mentioned in the building permit
Assistant Director
Town Planning
Nagpur Municipal Corporation

PARKING AREA STATEMENT

	CARS	SCOOTERS	CYCLES
PARKING AREA REQUIRED FOR 2 TENAMENT HAVING CARPET BETWEEN 40-100 SQM. NO. OF UNITS = 120	60 No.	240 No.	120 No.
PARKING AREA REQUIRED FOR 120 TENAMENTS	60 NO.	240 No.	120 No.
PARKING AREA PROVIDED	60 NO.	249 No.	241 No.

VISITORS PARKING CALCULATION :
FOR COMMERCIAL & RESIDENTIAL = 5% OF PARKING AREA REQUIRED
= 5% OF (30 x 2.500 x 5.000 + 30 x 2.300 x 4.500 + 240 x 2.000 + 120 x 1.000)
= 5% OF 1285.500 SQ. MT.
= 64.275 SQ. MT.
VISITORS PARKING AREA PROVIDED = 72.000 SQ. MT.

The Rain Water Harvesting is required to be provided as per Direction of Govt. of Maharashtra No. TPS 432003/2138 CR - 230/ 03/UD-II, dated 10th March, 2005 as per schedule for every 300 sq.mts. built-up area. The system may be by open well 1 mtr. dia r mtrs. deep with filteration chamber for every 300 sq.mtr. built-up area. Other options mentioned in the schedule may be adopted. a) The authority may impose a levy of Rs. 3000/- per annum for every 100 sq.mts. of built-up area, for failure of the owner of the building.

Provisions For Solar Water Heating Systems
Solar Water Heating System should be installed as per backing for the following units at the per capita capacity mentioned as under.

Type of Buildings	Per Capita Capacity Recommended
a) Hospitals	-100 Ltrs./day/person.
b) Hotels	-150 Ltrs./day/person.
c) Hostel & other	--
d) Residential	-- 25 Ltrs./ day/ person.
e) Industries	-- 25 Ltrs./ day/ person.

If the provisions as above is not made, the occupancy certificate will not be issued from NMC.

STAMP OF APPROVAL

SEISMIC ANALYSIS OF THE BUILDING FOR EARTHQUAKE BE SUBMITTED WITH STRUCTURAL DESIGN & DRAWING DULY CHECKED FROM VNIT FOR NMC INCLUDE, BEFORE ONE MONTH OF COMMENCEMENT OF CONSTRUCTION
2. THREE MONTHS FROM THE SANCTION OF BUILDING PLAN WHICHEVER IS EARLIER.

BALCONY AREA STATEMENT

FOR DETAILED AREA CALCULATION REFER AREA KEY PLANS & FLOOR PLANS
SECOND FLOOR :- PER. BAL. AREA = =15% OF BUILT UP AREA =15% OF 715. 721 = 107. 358 SQ. MT.

CALCULATION

1	2.400	X 2.200	=	5.280	SQM.
2	3.300	X 1.675	=	5.527	SQM.
3	3.300	X 1.675	=	5.527	SQM.
4	2.150	X 2.025	=	4.354	SQM.
5	2.400	X 2.200	=	5.280	SQM.
6	3.300	X 1.675	=	5.527	SQM.
7	3.300	X 1.675	=	5.527	SQM.
8	2.400	X 2.200	=	5.280	SQM.
9	2.400	X 2.200	=	5.280	SQM.
10	3.300	X 1.675	=	5.527	SQM.
11	3.300	X 1.675	=	5.527	SQM.
12	2.400	X 2.200	=	5.280	SQM.
13	2.150	X 2.025	=	4.354	SQM.
14	3.300	X 1.675	=	5.527	SQM.
15	3.300	X 1.675	=	5.527	SQM.
16	2.400	X 2.200	=	5.280	SQM.
TOTAL			=	84.608	SQM.

BALCONY AREA FOR 2ND TO 15TH FLOOR IS SAME AS FIRST FLOOR = 84. 608 SQM.

AREA STATEMENT		SQ. MT.
FOR DETAILED AREA CALCULATION REFER AREA KEY PLANS		
1	PLOT AREA =	3533.789
2	F.S.I. =	2.50
3	PERMISSIBLE F.S.I. =	8834.473
4	ADD INTERNAL ROAD AREA OF SANCTION LAYOUT	2160.000
5	MAX. PERMISSIBLE B/UP AREA (3+4)	10994.473
6	PROPOSED B/UP AREA	
	BASEMENT FLOOR	113.370
	GROUND FLOOR	113.539
	FIRST FLOOR	717.012
	SECOND FLOOR	717.012
	THIRD FLOOR	717.012
	FOURTH FLOOR	717.012
	FIFTH FLOOR	717.012
	SIXTH FLOOR	717.012
	SEVENTH FLOOR	717.012
	EIGHTH FLOOR	717.012
	NINTH FLOOR	717.012
	TENTH FLOOR	717.012
	ELEVENTH FLOOR	717.012
	TWELVTH FLOOR	717.012
	THIRTEENTH FLOOR	717.012
	FOURTEENTH FLOOR	717.012
	FIFTEENTH FLOOR	717.012
7	TOTAL PROPOSED B/UP AREA	10982.089

ARCHITECT & PLANNER (R.)
Nagpur Housing & Area Development Board, Nagpur.

LEGEND
PLOT BOUNDARY SHOWN THICK BLACK
PROPOSED WORK SHOWN RED FILLED IN
DRAINAGE LINE SHOWN RED DOTTED
WATER LINE SHOWN BLUE DOTTED
EXISTING TO BE RETAINED HATCHED
DEMOLISH ON SHOWN HATCHED YELLOW

OWNER'S NAME & SIGN

Executive Engineer
Nagpur Hsg. & Area Dev Board
Nagpur

SUPERVISOR
Nagpur Housing & Area Development Board, Nagpur.

NAGPUR HOUSING & AREA DEVELOPMENT BOARD, NAGPUR.

PROJECT:
PROPOSED RESIDENTIAL APARTMENT BUILDING AT PLOT NO.:- 3 & 4, S. No. 101, 159, EMPRESS MILL No. 5, MOUZA- NAGPUR, SUBHASH ROAD, NAGPUR.

NORTH

THIS DRAWING IS THE PROPERTY AND COPYRIGHT OF Ar. RAJESH JAISWAL
IT SHALL NOT BE COPIED, REPRODUCED OR USED WITHOUT WRITTEN CONSENT
DO NOT SCALE THE DRAWING

NOTE :-
THIS DRAWING IS SOLELY PREPARED FOR OBTAINING APPROVAL/SANCTIONING FROM NAGPUR MUNICIPAL CORPORATION & SHALL NOT BE USED FOR CONSTRUCTION PURPOSE.

ARCHITECT SIGN:

Ar.RAJESH JAISWAL
ARCHITECT AND INTERIOR DESIGNER
567, COTTON MARKET, GHAT ROAD, NAGPUR
TEL:-2721418, 2721434

JOB NO.	DRG.NO.	SCALE	DRAWN BY	CHECKED BY
JOB		1:100 1:300		

Sanket Creations