

Annexure F
FORM 5
(See Regulation 4)
ANNUAL REPORT STATEMENT OF ACCOUNTS
CHARTERED ACCOUNTANT'S CERTIFICATE

To,

M/S. VCMi CONSTRUCTIONS LLP at N-103, 104, Laxmivihar Apartment, Wardha Road, Somalwada, Nagpur-440025.

Subject: Report on Statement of Accounts on Project Fund Deposit, Utilisation and Withdrawal by "TATTVA APAS" being developed by M/S. VCMi CONSTRUCTIONS LLP for the period from 01/04/2023 to 31/03/2024 with respect to MAHA RERA Number P50500054320.

1. This Certificate is issued in accordance with the provisions of Real Estate (Regulation and Development) Act, 2016 read along with the Maharashtra Real estate (Regulation and Development) (Registration of Real Estate Projects, Registration of Real Estate Agents, Rates of Interest and Disclosures on Website) Rules, 2017.
2. We have obtained all necessary information & explanation from the Promoter, during the course of our Audit, which in our opinion are necessary for the purpose of this certificate.
3. We hereby confirm that We have examined the prescribed Registers, Books & Documents, and the relevant records of M/S. VCMi CONSTRUCTIONS LLP for the period ended 2023-2024 and hereby certify that:

A. DEPOSITS

		For this Fiscal Year	Total for this Project till date
1.	Total amount collected from allottees	99,62,825	99,62,825
2.	% of amount to be deposited as per Act	70%	70%
3.	Amount to be deposited as per Act (1*2)	69,73,978	69,73,978
4.	Total amount deposited in the Designated Bank Account	72,18,281	72,18,281
5.	% of Amount deposited in the Designated Bank Account [(4) / (1) * 100]	72.45%	72.45%
6.	Shortfall / Excess Deposit (3-4)	-2,44,304	-2,44,304



Amount collected/deposited at Sr. No. 1 & 2, does not include pass through charges & indirect taxes.

Firm has the required proportion of the money collected from allottees of the project units, as specified in the Act, deposited in the Designated RERA Bank Account.

B. WITHDRAWALS

		For this Fiscal Year	Total for this Project till date
1.	Opening balance of Designated Bank Account	-	-
2.	Total Deposits	72,18,281 Dr	72,18,281 Dr
3.	Total Amount Withdrawn	68,38,051 Cr	68,38,051 Cr
4.	Closing Balance	3,80,230 Dr	3,80,230 Dr

As specified in the Act, all the amounts withdrawn during the year from RERA Bank Account were within the withdrawal limit as certified under the relevant Form 1, Form 2, and Form 3 issued during the reporting period.

C. UTILISATION

We certify that, the M/S. **VCMI CONSTRUCTIONS LLP** has utilised the amounts withdrawn from the Designated Bank Account towards Project Cost, as specified in the Act as well as withdrawals by the partners of the firm.

D. ANY QUALIFICATIONS / OBSERVATIONS OF CA

1.	Amounts at point no. A & B are taken as per books of accounts. It also includes Amounts deposited and withdrawal by partners and sister concern transactions.
2.	Total amounts collected from allottees at point A (1) are net of any refunds to allottees.

FOR AGRAWAL CHHALLANI & CO.;
CHARTERED ACCOUNTANTS,
FIRM REG NO. 100125W



Agreed and accepted by:

Signature of Promoter
Name: Rahul Jagdish Bondre
Date: 24-12-2024

(S.R. Chhallani),
PARTNER

Membership No. 30154,
UDIN : 24030154BKETON8235